

OCTOBER 5, 2021
REPLACEMENT OF BRIDGE NO.01489 ROUTE 178 OVER BEAMANS BROOK
FEDERAL AID PROJECT NO. N/A
STATE PROJECT NO. 0011-0156
TOWN OF BLOOMFIELD

ADDENDUM NO. 1

This Addendum addresses the following questions and answers contained on the “CT DOT QUESTIONS AND ANSWERS WEBSITE FOR ADVERTISED CONSTRUCTION PROJECTS”:

Question and Answer No. 2.

SPECIAL PROVISION
REVISED SPECIAL PROVISION

The following Special Provision is hereby deleted in its entirety and replaced with the attached like-named Special Provision:

- **SECTION 1.08 – PROSECUTION AND PROGRESS**

The Bid Proposal Form and Detailed Estimate Sheets are not affected by this change.

There will be no change in the number of calendar days due to this Addendum.

The foregoing is hereby made a part of the contract.

SECTION 1.08 – PROSECUTION AND PROGRESS

Article 1.08.04 – Limitation of Operations - Add the following:

In order to provide for traffic operations as outlined in the Special Provision “Maintenance and Protection of Traffic,” the Contractor will not be permitted to perform any work which will interfere with the described traffic operations on all project roadways as follows:

Route 178 (Park Avenue)

Monday through Friday between 6:00 a.m. and 9:00 a.m. & between 3:00pm and 6:00pm
Saturday and Sunday between 10:00 a.m. and 6:00 p.m.

Additional restrictions:

- A. When school is not in session the Contractor shall be allowed to close Route 178 (Park Avenue) for a duration that shall not exceed 70 consecutive days, and detour traffic and pedestrian traffic as shown on the detour plan contained in the contract plans.
- B. The Contractor shall notify the Engineer and the Town of Bloomfield at least 14 days in advance of the start of Route 178 (Park Avenue) closure.

All Other Roadways

Monday through Friday between 6:00 a.m. and 9:00 a.m. & between 3:00pm and 6:00pm
Saturday and Sunday between 10:00 a.m. and 6:00 p.m.

Additional Lane Closure Restrictions

It is anticipated that work on adjacent projects will be ongoing simultaneously with this project. The Contractor shall be aware of those projects and anticipate that coordination will be required to maintain proper traffic flow at all times on all project roadways, in a manner consistent with these specifications and acceptable to the Engineer.

The Contractor will not be allowed to perform any work that will interfere with traffic operations on a roadway when traffic operations are being restricted on that same roadway, unless there is at least a one mile clear area length where the entire roadway is open to traffic or the closures have been coordinated and are acceptable to the Engineer. The one mile clear area length shall be measured from the end of the first work area to the beginning of the signing pattern for the next work area