

TOWN OF MADISON, CONNECTICUT  
CONTRACT DOCUMENTS  
FOR  
REPLACEMENT OF BRIDGE NO. 04852 AND NO. 075002  
COUNTY ROAD OVER THE HAMMONASSET RIVER  
MADISON, CT

ADDENDUM NO. 3  
October 29, 2021

All BIDDERS are hereby notified and warned of the following addition to the CONTRACT DOCUMENTS:

1. Received and answered the following question:

Q1. "I'm working on the estimate for the prestressed voided slabs for the project in Madison, CT that bids next week and was wondering if the beams need to have draped strands as shown in the elevation view. There is nothing called out in the section views and there is also a discrepancy in the number of strands shown in that view versus the amount called out in the elevation view."

A1. Draped strands are required and are shown in the *Elevation* view and in the *Section at End* views on sheets 37, 38 and 39 of 50.

The *Elevation* views on sheets 37 and 38 of 50 call out 18 strands. Change 18 strands to 12 strands.

The *Elevation* view on sheet 39 of 50 calls out 14 strands. Change 14 strands to 10 strands.

END OF ADDENDUM NO. 3