

SECTION 00 91 13

ADDENDUM

January 7, 2022

ADDENDUM NO. 2

TO: Prospective Bidders

FROM: Foth Infrastructure & Environment, LLC
15 Creek Road
Marion MA 02738

RE: Bottom of CAD Cell No. 4 & North Terminal Expansion
Contract No.: NBPA-FY22-001

This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated December 15, 2021.

Acknowledge receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification. All revision noted will be issued to the contractor as part of the Issued for Construction package that will be distributed with the Notice to Proceed.

This addendum consists of 6 pages.

ISSUED FOR INFORMATIONAL REASONS

1. Attachment 1 – Planholder List (as of current date)

QUESTIONS AND RESPONSES FROM PROSPECTIVE BIDDERS FOLLOWING THE PRE-BID CONFERENCE AND ADDENDUM NO. 1

1. Q: What are the limits of the pile infill concrete for the 16-inch diameter pipe piles?
A: No concrete infill is required on 16” diameter pipe piles. Piles can be capped prior to pour of C.I.P. beam.
2. Q: Plate size & connection detail for plate 16” diameter pile cap plate on sheet S05 are not provided. Please provide.
A: 18” diameter x 1” plate with welded connection. 3/8 in weld all around.
3. Q: Is pressure grouting required for the 8-inch mini piles?

- A: Pressure grouting is required inside the casing between the casing and core rod.
4. Q: Is a turbidity curtain required during backfill operations below MHW?
- A: See Section 00800, Supplementary Conditions, Attachment 4, Section II, 4, a. Once the cellular cofferdams are constructed, a silt curtain shall be installed along the entire length of the north side of the site to enclose the fill area.
5. Q: Concrete Deck Section S05-1 and Section S05-2 show fabrication and erection details for the Precast Shell support at the top of the 18-inch pipe pile. What is the width of the plate attached to the 3/4" triangular gusset plate under the Precast Shell support plate?
- A: See Drawing S05, Pile Cap Assembly Plan View, for pile cap assembly dimensions.
6. Q: Should the "Enlarged Deadman Planview" on Sheet S17 be used for the batter pile connection at the top of the 24" pipe pile? It appears that the HP14x89 wale is welded to the two 24" pipe piles and the batter piles connect to the horizontal web of the HP14x89 wale.
- A: 3/8 fillet weld, all mating surfaces, unless otherwise noted.
7. Q: Is the site lighting conduit and conduit for receptacles to be encased in concrete (Drawing E01 & E02)?
- A: Only ductbank A-A (feed to transformer) and ductbank B-B (feed from transformer to switchboard) are concrete encased. Lighting and receptacle circuits are not concrete encased.
8. Q: Is the surface treatment of the site infield area (shaded area on C01) 1'-6" of Dense Grade Aggregate (Drawing C10)?
- A: Correct, approximately 144,00 SF (8,000 CY) of Dense grade shall be installed prior to the construction of the stockpile area.
9. Q: Please provide depth of Gravel base for "Full Depth Pavement – Section 2" detail on Drawing C10.
- A: 12" Gravel base is required for the full depth pavement section.
10. Q: Please provide depth of existing asphalt top course that is to be milled and resurfaced.
- A: Mill existing asphalt 1.5" to match depth of proposed top course.

11. Q: No rebar connection detail exists between the 7” precast slab and CIP topping slab. Please confirm that no rebar connection is required.
- A: See Section 12-1 for #8 Headed Reinf. Shear connection – 2 per precast panel.
12. Q: No rebar connection detail exists between the precast tub and CIP concrete beam along A line. Please confirm that no rebar connection is required.
- A: See Section 12-1 for #8 Headed Reinf. Shear connection – 4 per pile and construction sequence notes.
13. Q: Please confirm whether MBE, WBE paperwork is due with the bid or 5 days after the bid.
- A: MBE and WBE paperwork is due with the contractor’s bids.
14. Q: Bid Item No. 3 Construction of Terminal Expansion Item A Work Covered by Contract Price 1.8 A 5 States “Excavation/dredging/removal of unsuitable material from within the footprint of the cellular cofferdams”. This work is also described under Bid Item No. 4. Please clarify which item we will be compensated for dredging and disposal of unsuitable material in the cellular cofferdams.
- A: All costs for dredging and disposal of unsuitable material in the cellular cofferdams shall be carried under Bid Item No. 4.

Susan E. Nilson, P.E.
Certifying Engineer
Foth Infrastructure & Environment, LLC

END OF ADDENDUM

Attachment 1
Planholder List (updated)

Planholders List

	Date of Request	Company	Contact Name	Email	Telephone No.	PDF of Bid Package Sent
1	12/15/2021	D.W. White Construction, Inc.	Joel Kosberg	jkosberg@dwwhite.com	508-763-8868, ext. 105	12/15/2021
2	12/15/2021	Smith Marine, Inc.	Matthew Plauche'	matt@smithmarine.com	781-631-4800, ext. 11	12/15/2021
3	12/15/2021	Mas Building & Bridge, Inc.	Christine Evers	cevers@masbuildingandbridge.com	508-520-2277, ext. 301	12/15/2021
4	12/15/2021	P.A. Landers, Inc.	Mike Lyons	mlyons@palanders.com	781-826-8818	12/15/2021
5	12/15/2021	David G Roach & Son's, Inc.	Daniel Roach	dan.roach@roachsitework.com	978-257-8560	12/15/2021
6	12/15/2021	Charter Contracting Company	Lisa Arseneault	larseneault@charter.us	857-246-6835	12/15/2021
7	12/15/2021	Projectdog, Inc.	Brendan Dodier	addenda@projectdog.com	978-499-9014	12/15/2021
8	12/16/2021	Burnham Associates, Inc.	Matt Sullivan, Craig Burnham, Kyle Burnham, Theodore Augustine, Stephen Driscoll	matt@burnhammarine.com ; craig@burnhammarine.com ; kyle@burnhammarine.com ; tspaugustine@gmail.com ; sdriscoll54@gmail.com	978-745-1788	12/16/2021
9	12/16/2021	AGM Marine Contractors, Inc.	Jonah Mikutowicz	Jonah.mikutowicz@agmmarine.com	508-477-8801	12/16/2021
10	12/16/2021	Coastline Consulting & Development, LLC	Mark Jackson	mark@coastlineconsulting-ct.com	203-433-4486, ext. 10	12/16/2021
11	12/16/2021	Construct Connect	Melinda Drew	melinda.drew@constructconnect.com	513-588-1524	12/16/2021
12	12/16/2021	Jay Cashman, Inc. / Cashman Dredging & Marine Contracting Company, LLC	Michael Empey, Devon Callahan	mempey@jaycashman.com ; dcallahan@jaycashman.com	617-890-0600	12/16/2021
13	12/16/2021	Manafort Transit	Thomas Le, Jason Baldiga	tle@manaforttransit.com ; jbaldiga@manaforttransit.com	781-328-2367	12/16/2021
14	12/16/2021	Ballard Marine Construction	Liam O'Brien	liam.obrien@ballardmc.com	866-782-6750	12/16/2021
15	12/17/2021	Dagle Electrical Construction Corp. (D.E.C.)	Elin Carbonneau, Linda Callanan	ecarbonneau@deccorp.com ; lcallanan@deccorp.com	800-379-1459	12/17/2021
16	12/17/2021	R. Zoppo Corp.	Alissa Romano	aromano@zoppo.com	781-344-8822	12/17/2021
17	12/20/2021	Northern Construction Service, LLC	Dolce Montana	dmontana@northernconstruction.com	413-289-1230, ext. 206	12/20/2021
18	12/20/2021	ACK – Marine & General Contracting	Kim Shaughnessy, Michael Boucher	Kimmarie@ack-marinecontracting.com ; Michael@ack-marinecontracting.com	617-481-5566	12/20/2021
19	12/21/2021	Coastal MC Estimating	Gene Kelley	estimating@coastalmc.net	339-502-8667	12/21/2021
20	12/21/2021	True Value Standard Marine & Hardware	Michael Quinn	mike@smotruevalue.com	508-990-0369	12/21/2021
21	12/21/2021	Team E.J. Prescott	Reid Pomerleau, David Hamilton	Reid.Pomerleau@ejprescott.com ; David.Hamilton@ejprescott.com	207-582-2006	12/21/2021

	Date of Request	Company	Contact Name	Email	Telephone No.	PDF of Bid Package Sent
22	12/23/2021	Construct Connect	Jonathan Ditter	Jonathan.ditter@constructconnect.com	513-458-5951	12/23/2021
23	12/27/2021	MIG Corporation, Inc	Stephanie LaRosee	slarosee@migcorporation.com	978-264-4800	12/27/2021
24	12/27/2021	Musco Lighting, LLC	Zack Schrock	zack.schrock@musco.com	603-703-9870	12/27/2021
25	12/28/2021	Maron Construction Co., Inc.	William Hunter, Tom Maron	whunter@maronco.com ; tmaron@mccri.com	401-272-4930	12/28/2021
26	12/29/2021	Construction Journal	Anthony Hernandez	AHernandez@constructionjournal.com	772-781-2144, ext. 721	12/29/2021
27	1/3/2022	Schoellhorn-Albrecht Machine Co.	Ralph Griffin	griffin@schoellhorn-albrecht.com	314-965-3339	1/3/2022
28	1/4/2022	Marine Structures	Andy Pigott	andy@marinestructures.com	252-241-8823	1/4/2022
29	1/5/2022	Robert B. Our Co., Inc. – Robert B. Our Marine Division	Abby Our Rose	ajour@robertbour.com	508-432-0530	1/5/2022
30	1/5/2022	K. R. Rezendes Inc.	Jordan Rezendes	jordanrezendes@krrezendes.com ; jordanrezendes@jrdinc.com	508-644-5795	1/5/2022