

Reconstruct Taxiway C (2,433 LF x 35 FT) and Extend Taxiway C (1,137 LF x 35 FT)
Lawrence Municipal Airport
North Andover, Massachusetts

SCHEDULE OF PRICES

Item No.	Pay Item No.	Item of Work	Estimated Quantity	Units	Unit Bid Price Written in Words	Unit Bid Price Numerical	Bid Amount
1	Div II-27.01	Construction Safety and Phasing	1	LS			
2	Div II-27.02	Construction Layout	1	LS			
3	C-100.01	Contractor Quality Control Program (CQCP)	1	LS			
4	C-102.01	Installation and Removal of Compost Filter Tube	11,000	LF			
5	C-102.02	First Installation of Compost Filter Tube Placed Around Perimeter of Catch Basin	45	EA			
6	C-102.03	Removal of First and Installation and Removal of Second Compost Filter Tube Placed Around Perimeter of Catch Basin	25	EA			
7	C-102.04	Installation and Removal of Drain Inlet Protection	45	EA			
8	C-102.05	Installation and Removal of Temporary Stabilized Construction Exits	4	EA			
9	C-102.06	Installation and Removal of Temporary Construction Access Roads	400	LF			
10	C-102.07	Temporary Seeding and Mulching	1,000	SY			
11	C-105.01	Mobilization (Limited to 10% of the Total Project Cost)	1	LS			
12	C-105.02	Resident Project Representative (RPR) Field Office	8	MONTHS			
13	P-101.01	Pavement Removal	28,000	SY			
14	P-101.02	Pavement Key Milling	2,000	SF			
15	P-101.03	Removal of Drainage Pipe Inside Limits of Grading	1,600	LF			
16	P-101.04	Removal of Drainage Pipe Outside Limits of Grading	500	LF			
17	P-101.05	Removal of Drainage Structure	9	EA			
18	P-152.01	Unclassified Excavation	30,000	CY			

Reconstruct Taxiway C (2,433 LF x 35 FT) and Extend Taxiway C (1,137 LF x 35 FT)
Lawrence Municipal Airport
North Andover, Massachusetts

SCHEDULE OF PRICES

Item No.	Pay Item No.	Item of Work	Estimated Quantity	Units	Unit Bid Price Written in Words	Unit Bid Price Numerical	Bid Amount
19	P-152.02	Rock Excavation	100	CY			
20	P-153.01	Controlled Low-Strength Material (CLSM)	100	CY			
21	P-154.01	Subbase Course	8,000	CY			
22	P-154.02	Separation Geotextile	18,000	SY			
23	P-209.01	Crushed Aggregate Base Course	4,100	CY			
24	P-401.01	Asphalt Surface Course	6,500	TON			
25	P-603.01	Emulsified Asphalt Tack Coat	1,700	GAL			
26	P-605.01	Joint Sawing and Sealing	1,300	LF			
27	P-620.01	Removal of Markings	8,000	SF			
28	P-620.02	Surface Preparation Prior to First Application of Markings	10,000	SF			
29	P-620.03	Surface Preparation Prior to Second Application of Markings	60,000	SF			
30	P-620.04	First Application of Markings	10,000	SF			
31	P-620.05	Second Application of Markings	60,000	SF			
32	P-620.06	Reflective Media, Type III, for Second Application of Markings	40,000	SF			
33	P-620.07	Reflective Media, Type I, Gradation A, for Second Application of Markings	700	SF			
34	D-701.01	12-inch Class V RCP Installed Inside Limits of Grading	100	LF			
35	D-701.02	12-inch Class V RCP Installed Outside Limits of Grading	80	LF			
36	D-701.03	15-inch Class V RCP Installed Inside Limits of Grading	3,500	LF			

Reconstruct Taxiway C (2,433 LF x 35 FT) and Extend Taxiway C (1,137 LF x 35 FT)
Lawrence Municipal Airport
North Andover, Massachusetts

SCHEDULE OF PRICES

Item No.	Pay Item No.	Item of Work	Estimated Quantity	Units	Unit Bid Price Written in Words	Unit Bid Price Numerical	Bid Amount
37	D-701.04	15-inch Class V RCP Installed Outside Limits of Grading	110	LF			
38	D-701.05	18-inch Class V RCP Installed Inside Limits of Grading	50	LF			
39	D-701.06	21-inch Class V RCP Installed Inside Limits of Grading	100	LF			
40	D-701.07	21-inch Class V RCP Installed Outside Limits of Grading	275	LF			
41	D-701.08	24-inch Class V RCP Installed Inside Limits of Grading	200	LF			
42	D-701.09	Connection of Existing Pipe to New Structure	8	EA			
43	D-701.10	Connection of New Pipe to Existing Structure	3	EA			
44	D-705.01	Removal of Underdrain Pipe and Cleanouts	1,500	LF			
45	D-705.02	6-inch Underdrain Pipe	7,000	LF			
46	D-705.03	Underdrain Cleanout	44	EA			
47	D-705.04	Existing Underdrain Cleanout Adjustment	15	EA			
48	D-705.05	2" Schedule 40 PVC Lighting System Drain Pipe	700	LF			
49	D-705.06	2" Schedule 80 PVC Lighting System Drain Pipe	50	LF			
50	D-751.01	Manholes, Type 2	2	EA			
51	D-751.02	Catch Basins, Type 1	17	EA			
52	D-751.03	Catch Basins, Type 2	5	EA			
53	D-751.04	Existing Drainage Structure Adjustment	4	EA			
54	D-751.05	Replacement of Frame and Grate	4	EA			

Reconstruct Taxiway C (2,433 LF x 35 FT) and Extend Taxiway C (1,137 LF x 35 FT)
Lawrence Municipal Airport
North Andover, Massachusetts

SCHEDULE OF PRICES

Item No.	Pay Item No.	Item of Work	Estimated Quantity	Units	Unit Bid Price Written in Words	Unit Bid Price Numerical	Bid Amount
55	D-751.06	Concrete Drainage Pad	25	EA			
56	T-901.01	Seeding	545	MSF			
57	T-905.01	Topsoil	7,000	CY			
58	T-908.01	Mulching	61,000	SY			
59	F-162.01	Chain-Link Fence	50	LF			
60	F-162.02	Temporary Construction Access Gate	1	EA			
61	L-108.01	Removal of Cable from Conduit or Duct Bank to Remain	3,000	LF			
62	L-108.02	Removal of Direct-Buried Cable, Inside Limits of Grading	10,500	LF			
63	L-108.03	Removal of Direct-Buried Cable, Outside Limits of Grading	9,000	LF			
64	L-108.04	No. 8 AWG, 5kV, L-824, Type C Cable, Installed in Duct Bank or Conduit	26,500	LF			
65	L-108.05	No. 8 AWG, 5kV, L-824, Type C Direct-Buried Cable, Installed in Trench	6,000	LF			
66	L-108.06	Trench for L-824 Direct-Buried Cable, Inside Limits of Grading	1,600	LF			
67	L-108.07	Trench for L-824 Direct-Buried Cable, Outside Limits of Grading	1,050	LF			
68	L-108.08	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed Above the Duct Bank or Conduit, Including Connections/Terminations	16,500	LF			
69	L-108.09	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed in Separate Trench, Inside Limits of Grading, Including Connections/Terminations	1,600	LF			
70	L-108.10	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed in Separate Trench, Outside Limits of Grading, Including Connections/Terminations	500	LF			
71	L-108.11	No. 6 AWG, Insulated, Stranded Equipment Ground, Installed in Duct Bank or Conduit	13,000	LF			
72	L-108.12	Temporary No. 8 AWG, 5kV, L-824, Type C Direct Buried Cable, Installed in Conduit or Duct Bank	2,500	LF			

Reconstruct Taxiway C (2,433 LF x 35 FT) and Extend Taxiway C (1,137 LF x 35 FT)
Lawrence Municipal Airport
North Andover, Massachusetts

SCHEDULE OF PRICES

Item No.	Pay Item No.	Item of Work	Estimated Quantity	Units	Unit Bid Price Written in Words	Unit Bid Price Numerical	Bid Amount
73	L-108.13	Temporary No. 8 AWG, 5kV, L-824, Type C Direct Buried Cable, Installed in Trench	500	LF			
74	L-109.01	Installation of 10 kW Regulator	1	EA			
75	L-109.02	Installation of Equipment within Existing Vault in Place	1	LS			
76	L-110.01	Removal of Concrete Encased Electrical Duct Bank	1,500	LF			
77	L-110.02	Removal of Non-Encased Electrical Conduit	1,200	LF			
78	L-110.03	Non-Encased 2" Schedule 40 PVC Electrical Conduit Installed Inside Limits of Grading	10,500	LF			
79	L-110.04	Non-Encased 2" Schedule 40 PVC Electrical Conduit Installed Outside Limits of Grading	2,800	LF			
80	L-110.05	Non-Encased 2" Schedule 80 PVC Electrical Conduit Installed Inside Limits of Grading	300	LF			
81	L-110.06	Concrete Encased Schedule 40 PVC Electrical Duct Bank, 4-Way by 4"	800	LF			
82	L-110.07	Non-Encased Schedule 40 PVC Electrical Duct Bank, 4-Way by 4"	500	LF			
83	L-110.08	Extend Concrete Encased Schedule 40 PVC Electrical Duct Bank, 4-Way by 4"	50	LF			
84	L-110.09	Temporary Non-Encased Schedule 80 PVC Electrical Duct, 1-Way by 4"	150	LF			
85	L-115.01	Removal of Electrical Manhole/Handhole	2	EA			
86	L-115.02	Removal of Electrical Junction Structure	20	EA			
87	L-115.03	Electrical Handhole, 4' by 4' Precast Concrete	14	EA			
88	L-115.04	Relocate Existing Precast Concrete Electrical Handhole	2	EA			
89	L-115.05	L-868 Electrical Junction Structure	3	EA			
90	L-115.06	Remove and Replace Existing FAA Junction Can and Engraved Cover	1	EA			

Reconstruct Taxiway C (2,433 LF x 35 FT) and Extend Taxiway C (1,137 LF x 35 FT) Lawrence Municipal Airport North Andover, Massachusetts SCHEDULE OF PRICES								
Item No.	Pay Item No.	Item of Work	Estimated Quantity	Units	Unit Bid Price Written in Words	Unit Bid Price Numerical	Bid Amount	
91	L-125.01	Removal of Existing Elevated Taxiway Edge Light	200	EA				
92	L-125.02	Removal of Existing Elevated Runway Edge Light	3	EA				
93	L-125.03	Removal of Existing Illuminated Airfield Sign	35	EA				
94	L-125.04	L-861T(L) LED Base Mounted Taxiway Edge Light	151	EA				
95	L-125.05	Relocation of Existing Base Mounted Taxiway Edge Light	9	EA				
96	L-125.06	Relocation of Existing Stake Mounted Taxiway Edge Light	7	EA				
97	L-125.07	Relocation of Existing Base Mounted Runway 5-23 Edge Light	1	EA				
98	L-125.08	L-861 Stake Mounted Runway 14-32 Edge Light	2	EA				
99	L-125.09	L-858(L) LED Size 1, Style 2, Class 2 Illuminated Airfield Guidance Sign	33	EA				
100	L-125.10	L-849I(L), Style E Runway End Identifier Light (REIL)	2	EA				
101	L-125.11	Airfield Lighting Control and Monitoring System Coordination	1	ALLOWANCE	Five Thousand Dollars and Zero Cents	\$5,000.00	\$5,000.00	
102	L-125.12	Airfield Lighting Spare Parts	1	ALLOWANCE	Ten Thousand Dollars and Zero Cents	\$10,000.00	\$10,000.00	
Total Contract Price to be entered into Line C. of the Form For General Bid =								
Notes: 1. Prices should generally be written in whole dollars and cents. The extended total amount of each item should not be rounded. 2. It is understood that the quantities given in the Schedule of Prices are approximate only and are given as a basis for comparison of Bids. The Owner does not expressly or by implication agree that the actual amount of work will even approximately correspond herewith, but reserves the right to increase or decrease the amount of any item of the work listed, and the unit prices quoted in Bid shall apply without change to such variation in the quantity of each of the items, except as further clarified herein. The Owner further reserves the right to delete any item of work in whole or in part, in order to meet the available funding.								