

## **DISTRIBUTION OF QUANTITIES**

**Table of Contents - Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

<b>ItemCode</b>	<b>Description</b>	<b>Page</b>
201.0321	CLEARING AND GRUBBING	1
201.0409	REMOVE AND DISPOSE FLEXIBLE PAVEMENT	1
201.9901	REMOVE AND DISPOSE CONCRETE SLOPE PAVING	1
201.9902	PARTIAL REMOVAL AND DISPOSAL OF CONCRETE BLOCK WALL	1
202.0100	EARTH EXCAVATION	1
202.0800	GRAVEL BORROW	1
202.9901	SOIL STABILIZATION	2
203.0700	PERVIOUS FILL	2
209.0210	HIGH FLOW SACK INSERT CATCH BASIN INLET PROTECTION	2
212.2100	MAINTENANCE AND CLEANING OF EROSION AND POLLUTION CONTROLS	2
401.3003	CLASS 9.5 HMA FOR PATCHING	2
402.9901	FRICTION COURSE WITHOUT PAY ADJUSTMENTS	3
403.0300	ASPHALT EMULSION TACK COAT	3
416.9901	PAY ADJUSTMENTS	3
601.0300	CLASS A PORTLAND CEMENT CONCRETE	3
703.9901	4 INCH PERFORATED CORRUGATED POLYETHYLENE PIPE	3
707.0900	ADJUST MANHOLES TO GRADE	3
707.1100	ADJUST CATCH BASINS	4
708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	5
708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	5
708.9042	CLEANING MANHOLES ALL TYPES AND SIZES	6
820.0100	CONCRETE SURFACE TREATMENT PROTECTIVE SEALER	7
904.0101	REMOVE AND RESET FENCE AND/OR RAILING CHAIN LINK	7
905.9901	PORTLAND CEMENT CONCRETE SLOPE PAVING	7
906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES	7
907.0100	WATER FOR DUST CONTROL	8
909.9901	PRECAST CONCRETE BARRIER	8
909.9902	PRECAST CONCRETE TRANSITION	8
916.9901	NARROW CONDITION IMPACT ATTENUATOR FOR TEMPORARY TRAFFIC CONTROL	8
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	8
923.0105	DRUM BARRICADE STANDARD 26.2.0	9
923.0125	PLASTIC PIPE TYPE III BARRICADE STANDARD 26.3.1	9
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	9
924.0113	ADVANCE WARNING ARROW PANEL	9
925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	9
926.9901	TEMPORARY TL-3 BARRIER	9
928.0500	SHADOW OR ADVANCE WARNING VEHICLE WITH IMPACT ATTENUATOR AND FLASHING ARROW BOARD	9
929.0110	FIELD OFFICE	10
931.0110	CLEANING AND SWEEPING PAVEMENT	10
932.0100	CUTTING AND MATCHING ASPHALT	10
932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	10
935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	10
936.0100	MOBILIZATION AND DEMOBILIZATION	10
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	10
L01.0104	PLANTABLE SOIL 4 INCHES DEEP	10

### Table of Contents - Distribution of Quantities

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

ItemCode	Description	Page
L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1)	11
L05.0505	EROSION CONTROL BLANKET	11
L06.9901	PINUS STROBUS 'FASTIGIATA', COLUMNAR EASTERN WHITE PINE 7'- 8' HT, B&B	11
L11.0102	TREE PLANT PROTECTION DEVICE STANDARD 51.1.0	12
T15.0200	REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN	12
T18.0201	REFLECTOR UNIT-SINGLE WHITE DELINEATOR	12
T19.0100	MILE POST MARKER 10" X 18"	12
T19.0200	MILE POST MARKER 10" X 27"	12
T20.0706	6 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS	12
T20.0906	6 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS	12
T20.2406	6 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS	13
T20.2806	6 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS	13
T20.4006	6 INCH WHITE PREFORMED TAPE PAVEMENT MARKINGS	13
T20.4506	REMOVE PAVEMENT MARKING LINE - LESS THAN OR EQUAL TO 6 INCHES WIDE	13

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
001	201.0321	<b>CLEARING AND GRUBBING</b>	<b>SY</b>	
		I-95 NB		9,400.00
		I-95 SB		6,600.00
<b>Item 201.0321 Total:</b>				<b>16,000.00</b>
002	201.0409	<b>REMOVE AND DISPOSE FLEXIBLE PAVEMENT</b>	<b>SY</b>	
		I-95 NB		
		37+00 - 46+55		110.00
		56+70 - 80+95		270.00
		I-95 SB		
		35+90 - 46+25		120.00
		56+35 - 77+15		240.00
<b>Item 201.0409 Total:</b>				<b>740.00</b>
003	201.9901	<b>CLEARING AND GRUBBING IN SENSITIVE TREE AREA</b>	<b>SY</b>	
		I-95 NB		1,300.00
		I-95 SB		4,400.00
<b>Item 201.9901 Total:</b>				<b>5,700.00</b>
004	201.9902	<b>REMOVE AND DISPOSE CONCRETE SLOPE PAVING</b>	<b>SY</b>	
		I-95 NB		
		36+90 - 46+35:		610.00
		MILFORD ST BRIDGE		80.00
		56+58 - 80+79		1,560.00
		LAURENS ST BRIDGE		80.00
		PARK AVE BRIDGE		90.00
		I-95 SB		
		36+14 - 46+33		660.00
		MILFORD ST BRIDGE		80.00
		56+58 - 77+16		1,330.00
		LAURENS ST BRIDGE		80.00
		PARK AVE BRIDGE		90.00
<b>Item 201.9902 Total:</b>				<b>4,660.00</b>
005	201.9902	<b>PARTIAL REMOVAL AND DISPOSAL OF CONCRETE BLOCK WALL</b>	<b>SY</b>	
		I-95 NB		3,500.00
		I-95 SB		3,450.00
<b>Item 201.9902 Total:</b>				<b>6,950.00</b>
006	202.0100	<b>EARTH EXCAVATION</b>	<b>SY</b>	
		I-95 NB		3,980.00
		I-95 SB		3,700.00
<b>Item 202.0100 Total:</b>				<b>7,680.00</b>

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
007	202.0800	<b>GRAVEL BORROW</b>	<b>SY</b>	
		I-95		
		AT R&R CURB		500.00
		BENEATH SLOPE PAVING		1,150.00
		BENEATH PRECAST BARRIER		450.00
<b>Item 202.0800 Total:</b>				<b>2,100.00</b>
008	202.9901	<b>SOIL STABILIZATION</b>	<b>LBS</b>	
		I-95 NB		
		61+00 - 76+00		310,000.00
<b>Item 202.9901 Total:</b>				<b>310,000.00</b>
009	203.0700	<b>PERVIOUS FILL</b>	<b>CY</b>	
		I-95 NB		650.00
		I-95 SB		600.00
<b>Item 203.0700 Total:</b>				<b>1,250.00</b>
010	209.0210	<b>HIGH FLOW SACK INSERT CATCH BASIN INLET PROTECTION</b>	<b>EACH</b>	
		I-95 NB		
		37+70		1.00
		40+30		1.00
		42+60		1.00
		45+30		1.00
		58+20		1.00
		60+50		2.00
		63+00		1.00
		65+50		1.00
		71+00		1.00
		73+50		1.00
		75+80		2.00
		78+50		1.00
		I-95 SB		
		37+50		1.00
		40+00		1.00
		42+50		1.00
		45+10		1.00
		58+25		1.00
		60+50		2.00
		63+00		1.00
		65+50		1.00
		71+00		1.00
		73+50		1.00
		75+80		2.00
<b>Item 209.0210 Total:</b>				<b>27.00</b>

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
011	212.2100	MAINTENANCE AND CLEANING OF EROSION AND POLLUTION CONTROL PROJECT WIDE	LS	1.00
Item 212.2100 Total:				1.00
012	401.3003	CLASS 9.5 HMA FOR PATCHING I-95 NB 37+00 - 46+55 56+70 - 80+95 I-95 SB 35+90 - 46+25 56+35 - 77+15	TON	20.00 50.00 25.00 45.00
Item 401.3003 Total:				140.00
013	402.9901	FRICITION COURSE WITHOUT PAY ADJUSTMENTS I-95 NB 61+00 - 76+00	TON	1,400.00
Item 402.9901 Total:				1,400.00
014	403.0300	ASPHALT EMULSION TACK COAT I-95 NB 61+00 - 76+00	SY	12,000.00
Item 403.0300 Total:				12,000.00
015	416.9901	PAY ADJUSTMENTS PROJECT WIDE	EACH	5,000.00
Item 416.9901 Total:				5,000.00
016	601.0300	CLASS A PORTLAND CEMENT CONCRETE I-95 NB 37+00 - 46+55 56+70 - 80+95 I-95 SB 35+90 - 46+25 56+35 - 77+15	CY	40.00 90.00 40.00 80.00
Item 601.0300 Total:				250.00
017	703.9901	4 INCH PERFORATED CORRUGATED POLYETHYLENE PIPE I-95 NB I-95 SB	LF	3,500.00 3,200.00
Item 703.9901 Total:				6,700.00
018	707.0900	ADJUST MANHOLE TO GRADE I-95 NB 37+60 38+50	EACH	1.00 1.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
018	707.0900 Cont.	41+00		1.00
		44+00		1.00
		59+50		1.00
		60+60		1.00
		62+50		1.00
		65+50		1.00
		68+50		1.00
		71+70		1.00
		75+00		1.00
		75+60		1.00
		78+00		1.00
		I-95 SB		
		37+50		1.00
		38+00		1.00
		40+20		1.00
		41+00		1.00
		44+00		1.00
		59+50		1.00
		60+70		1.00
		62+50		1.00
		65+50		1.00
		68+50		1.00
		71+70		1.00
		75+00		1.00
		75+60		1.00
<b>Item 707.0900 Total:</b>				<b>26.00</b>
019	707.1100	<b>ADJUST CATCH BASINS</b>	<b>EACH</b>	
		I-95 NB		
		37+70		1.00
		40+30		1.00
		42+60		1.00
		45+30		1.00
		58+20		1.00
		60+50		2.00
		63+00		1.00
		65+50		1.00
		71+00		1.00
		73+50		1.00
		75+80		2.00
		78+50		1.00
		I-95 SB		
		37+50		1.00
		40+00		1.00
		42+50		1.00
		45+10		1.00
		58+25		1.00
		60+50		2.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
019	707.1100	Cont.		
		63+00		1.00
		65+50		1.00
		71+00		1.00
		73+50		1.00
		75+80		2.00
<b>Item 707.1100 Total:</b>				<b>27.00</b>
020	708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	LF	
		I-95 NB		
		37+70		60.00
		40+30		60.00
		42+60		60.00
		45+20		60.00
		58+20		60.00
		60+50		60.00
		63+00		60.00
		65+50		60.00
		71+00		60.00
		75+80		60.00
		78+50		60.00
		36+70 - 46+50 SUBDRAIN		1,120.00
		56+40 - 80+70 SUBDRAIN		2,620.00
		I-95 SB		
		37+50		60.00
		40+00		60.00
		42+50		60.00
		45+20		60.00
		58+20		60.00
		60+50		60.00
		63+00		60.00
		65+50		60.00
		71+00		60.00
		73+40		60.00
		75+80		60.00
		36+70 - 46+50 SUBDRAIN		1,120.00
		56+50 - 77+00 SUBDRAIN		2,320.00
		LATERAL WALL DRAINS		750.00
<b>Item 708.9040 Total:</b>				<b>9,250.00</b>
021	708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	EACH	
		I-95 NB		
		37+70		1.00
		40+30		1.00
		42+60		1.00
		45+30		1.00



**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
021	708.9041	Cont.		
		58+20		1.00
		60+50		2.00
		63+00		1.00
		65+50		1.00
		71+00		1.00
		73+50		1.00
		75+80		2.00
		78+50		1.00
		I-95 SB		
		37+50		1.00
		40+00		1.00
		42+50		1.00
		45+10		1.00
		58+25		1.00
		60+50		2.00
		63+00		1.00
		65+50		1.00
		71+00		1.00
		73+50		1.00
		75+80		2.00
<b>Item 708.9041 Total:</b>				<b>27.00</b>
022	708.9042	CLEANING MANHOLES ALL TYPES AND SIZES	EACH	
		I-95 NB		
		37+60		1.00
		38+50		1.00
		41+00		1.00
		44+00		1.00
		59+50		1.00
		60+60		1.00
		62+50		1.00
		65+50		1.00
		68+50		1.00
		71+70		1.00
		75+00		1.00
		75+60		1.00
		78+00		1.00
		I-95 SB		
		37+50		1.00
		38+00		1.00
		40+20		1.00
		41+00		1.00
		44+00		1.00
		59+50		1.00
		60+70		1.00
		62+50		1.00
		65+50		1.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
022	708.9042 Cont.	68+50		1.00
		71+70		1.00
		75+00		1.00
		75+60		1.00
<b>Item 708.9042 Total:</b>				<b>26.00</b>
023	820.0100	<b>CONCRETE SURFACE TREATMENT PROTECTIVE SEALANT</b>	<b>SF</b>	
		I-95 NB		
		36+60 - 46+40		4,625.00
		56+30 - 80+75		11,525.00
		I-95 SB		
		36+10 - 46+60		4,950.00
		56+55 - 77+55		9,900.00
<b>Item 820.0100 Total:</b>				<b>31,000.00</b>
024	904.0101	<b>REMOVE AND RESET FENCE AND/OR RAILING CHAIN LINK</b>	<b>LF</b>	
		I-95 NB		
		38+38 - 39+60		125.00
		40+05 - 41+30		135.00
		58+92 - 60+14		130.00
		60+59 - 61+78		125.00
		75+44 - 76+65		125.00
		77+18 - 78+37		125.00
		I-95 SB		
		39+37 - 39+60		25.00
		40+05 - 41+24		125.00
		75+35 - 76+65		135.00
<b>Item 904.0101 Total:</b>				<b>1,050.00</b>
025	905.9901	<b>PORTLAND CEMENT CONCRETE SLOPE PAVING</b>	<b>CY</b>	
		I-95 NB		
		37+08 - 46+48		110.00
		39+61 - 40+03 MILFORD ST BRIDGE		20.00
		56+76 - 80+86		260.00
		61+15 - 60+58 LAURENS ST BRIDGE		20.00
		76+67 - 77+16 PARK AVE BRIDGE		20.00
		I-95 SB		
		35+98 - 46+18		110.00
		39+61 - 40+03 MILFORD ST BRIDGE		20.00
		56+45 - 77+16		230.00
		61+15 - 60+58 LAURENS ST BRIDGE		20.00
		76+67 - 77+16 PARK AVE BRIDGE		20.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
025	905.9901 Cont.	Item 905.9901 Total:		830.00
026	906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES	LF	
		I-95 NB		
		37+00 - 46+55		960.00
		56+70 - 80+95		2,440.00
		I-95 SB		
		35+90 - 46+25		1,065.00
		56+35 - 77+15		2,135.00
		Item 906.0700 Total:		6,600.00
027	907.0100	WATER FOR DUST CONTROL PROJECT WIDE	MGAL	240.00
		Item 907.0100 Total:		240.00
028	909.9901	PRECAST CONCRETE BARRIER	LF	
		I-95 NB		
		36+60 - 46+40		1,000.00
		56+30 - 80+75		2,500.00
		I-95 SB		
		36+10 - 46+60		1,065.00
		56+55 - 77+55		2,135.00
		Item 909.9901 Total:		6,700.00
029	909.9902	PRECAST CONCRETE TRANSITION	EACH	
		I-95 NB		
		46+40		1.00
		80+80		1.00
		I-95 SB		
		36+05		1.00
		56+50		1.00
		Item 909.9902 Total:		4.00
030	916.9901	NARROW CONDITION IMPACT ATTENUATOR FOR TEMPORARY TRAFFIC CONTROL AS DIRECTED	EACH	2.00
		Item 916.9901 Total:		2.00
031	922.0100	TEMPORARY CONSTRUCTION SIGNS STD. 29.1.0 AND 27.1.1 PROJECT WIDE	SF	
		AS DIRECTED		125.50
		W20-1		128.00
		RI STD 27.1.1		96.00
		W20-5AR		64.00
		W4-2R		64.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
031	922.0100 Cont.	W21-5R		64.00
		E5-2		10.00
		E5-1		30.00
		R1-2		14.00
		W3-2A		16.00
		W20-2		32.00
		M4-8		16.25
		M4-8A		3.00
		M3-3		10.00
		M6-3		4.50
		M6-2R		4.50
		M6-1		2.25
		M1-1		20.00
		W4-2L		64.00
		W20-5AL		64.00
		W20-5R		64.00
		W20-5L		64.00
<b>Item 922.0100 Total:</b>				<b>960.00</b>
032	923.0105	DRUM BARRICADE STD. 26.2.0	BDAY	
		PROJECT WIDE		
		AS DIRECTED		3,600.00
<b>Item 923.0105 Total:</b>				<b>3,600.00</b>
033	923.0125	PLASTIC PIPE TYPE III BARRICADE	EACH	
		STANDARD 26.3.1		
		RAMP CLOSURE		
		AS DIRECTED		5.00
<b>Item 923.0125 Total:</b>				<b>5.00</b>
034	923.0200	FLUORESCENT TRAFFIC CONES RI STD.	EACH	
		26.1.0		
		PROJECT WIDE		
		AS DIRECTED		200.00
<b>Item 923.0200 Total:</b>				<b>200.00</b>
035	924.0113	ADVANCE WARNING ARROW PANEL	PDAY	
		PROJECT WIDE		
		AS DIRECTED		160.00
<b>Item 924.0113 Total:</b>				<b>160.00</b>
036	925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	PDAY	
		PROJECT WIDE		
		AS DIRECTED		240.00
<b>Item 925.0112 Total:</b>				<b>240.00</b>

### Distribution of Quantities

Project Name - Route 95 Pavement and Retaining Wall Restoration  
 R.I. Contract No. 2022-CH-017  
 FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
037	926.9901	TEMPORARY TL-3 BARRIER PROJECT WIDE AS DIRECTED	PDAY	9,300.00
Item 926.9901 Total:				9,300.00
038	928.0500	SHADOW OR ADVANCE WARNING VEHICLE WITH IMPACT ATTENUATOR PROJECT WIDE AS DIRECTED	HRS	1,140.00
Item 928.0500 Total:				1,140.00
039	929.0110	FIELD OFFICE PROJECT WIDE AS DIRECTED	PMO	12.00
Item 929.0110 Total:				12.00
040	931.0110	CLEANING AND SWEEPING PAVEMENT PROJECT WIDE FRICTION COURSE AREA BARRIER LIMITS	SY	11,200.00 7,500.00
Item 931.0110 Total:				18,700.00
041	932.0100	CUTTING AND MATCHING ASPHALT I-95 NB 61+00 76+00	LF	65.00 65.00
Item 932.0100 Total:				130.00
042	932.0200	FULL DEPTH SAWCUT OF BITUMINOUS PAVEMENT I-95 NB 37+00 - 46+55 56+70 - 80+95 I-95 SB 35+90 - 46+25 56+35 - 77+15	LF	960.00 2,440.00 1,065.00 2,135.00
Item 932.0200 Total:				6,600.00
043	935.0400	REMOVING BITUMINOUS PAVEMENT BY MICROMILLING I-95 NB 61+00 - 76+00	SY	11,100.00
Item 935.0400 Total:				11,100.00
044	936.0110	MOBILIZATION AND DEMOBILIZATION PROJECT WIDE PROJECT WIDE	LS	1.00
Item 936.0110 Total:				1.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
045	937.0200	MAINTENANCE AND MOVEMENT OF TRAFFIC PROTECTION PROJECT WIDE PROJECT WIDE	LS	
				1.00
		<b>Item 937.0200 Total:</b>		<b>1.00</b>
046	L01.0104	PLANTABLE SOIL 4 INCHES DEEP I-95 NB 36+65 - 39+60 40+05 - 46+55 56+35 - 60+15 60+55 - 76+65 77+15 - 80+90 I-95 SB 36+05 - 39+60 40+05 - 46+60 56+40 - 60+15 60+55 - 76+65 77+15 - 77+65	SY	
				1,100.00
				2,400.00
				1,400.00
				5,900.00
				1,400.00
				1,500.00
				2,500.00
				1,400.00
				5,900.00
				200.00
		<b>Item L01.0104 Total:</b>		<b>23,700.00</b>
047	L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1) I-95 NB 36+65 - 39+60 40+05 - 46+55 56+35 - 60+15 60+55 - 76+65 77+15 - 80+90 I-95 SB 36+05 - 39+60 40+05 - 46+60 56+40 - 60+15 60+55 - 76+65 77+15 - 77+65	SY	
				1,100.00
				2,400.00
				1,400.00
				5,900.00
				1,400.00
				1,500.00
				2,500.00
				1,400.00
				5,900.00
				200.00
		<b>Item L02.0101 Total:</b>		<b>23,700.00</b>
048	L05.0505	EROSION CONTROL BLANKET I-95 NB 36+65 - 39+60 40+05 - 46+55 56+35 - 60+15 60+55 - 76+65 77+15 - 80+90 I-95 SB 36+05 - 39+60 40+05 - 46+60 56+40 - 60+15 60+55 - 76+65	SY	
				1,100.00
				2,400.00
				1,400.00
				5,900.00
				1,400.00
				1,500.00
				2,500.00
				1,400.00
				5,900.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
048	L05.0505 Cont.	77+15 - 77+65		200.00
Item L05.0505 Total:				23,700.00
049	L06.9901	PINUS STROBUS 'FASTIGIATA', COLUMNAR EASTERN WHITE PINE 7'-8' HT, B&B PROJECT WIDE AS DIRECTED	EACH	50.00
Item L06.9901 Total:				50.00
050	L09.9901	REMOVE AND DISPOSE IVY VINES FROM EXISTING TREES TO REMAIN PROJECT WIDE AS DIRECTED	EACH	120.00
Item L09.9901 Total:				120.00
051	L11.0102	TREE PLANT PROTECTION DEVICE STANDARD 51.1.0 PROJECT WIDE AS DIRECTED	EACH	40.00
Item L11.0102 Total:				40.00
052	T15.0200	REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN I-95 NB STA. 80+80	EACH	1.00
Item T15.0200 Total:				1.00
053	T18.0201	REFLECTOR UNIT SINGLE WHITE DELINEATOR PROJECT WIDE PROJECT WIDE	EACH	10.00
Item T18.0201 Total:				10.00
054	T19.0100	MILE POST MARKER 10"X18" I-95 NB 44+60 76+50 I-95 SB 56+50	EA	1.00 1.00 1.00
Item T19.0100 Total:				3.00
055	T19.0200	MILE POST MARKER 10"X27" I-95 NB 67+00 I-95 SB 69+30	EA	1.00 1.00
Item T19.0200 Total:				2.00

**Distribution of Quantities**

Project Name - Route 95 Pavement and Retaining Wall Restoration

R.I. Contract No. 2022-CH-017

FAP No. 401-422-101

Item No.	Item Code	Description	UM	Qty.
056	T20.0706	6 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS PROJECT WIDE PROJECT WIDE	LF	2,250.00
Item T20.0706 Total:				2,250.00
057	T20.0906	6 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS PROJECT WIDE PROJECT WIDE	LF	3,000.00
Item T20.0906 Total:				3,000.00
058	T20.2406	6 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS PROJECT WIDE PROJECT WIDE	LF	3,525.00
Item T20.2406 Total:				3,525.00
059	T20.2806	6 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS PROJECT WIDE PROJECT WIDE	LF	1,500.00
Item T20.2806 Total:				1,500.00
060	T20.4006	6 INCH WHITE PREFORMED TAPE PAVEMENT MARKINGS PROJECT WIDE PROJECT WIDE	LF	12,000.00
Item T20.4006 Total:				12,000.00
061	T20.4506	REMOVE PAVEMENT MARKING LINE - LESS THAN OR EQUAL TO 6 INCHES WIDE PROJECT WIDE PROJECT WIDE	LF	14,400.00
Item T20.4506 Total:				14,400.00