



Proposal No. 607680-124171

November 17, 2023

# ADDENDUM NO. 1

To Prospective Bidders and Others on:

### **FITCHBURG**

Bridge Rehabilitation, F-04-010, River Street (ST 31) over North Nashua River

THIS PROPOSAL TO BE OPENED AND READ: TUESDAY, DECEMBER 5, 2023 at 2:00 P.M.

Transmitting changes to the Contract Documents as follows:

QUESTIONS AND RESPONSES: Three pages.

DOCUMENT 00010: Revised page 3.

DOCUMENT 00813: Deleted document in its entirety and inserted

new document (4 pages).

DOCUMENT A00873: Inserted new document (34 pages).

Please take note of the above, substitute the revised page for the original, delete document indicated, insert new documents in proper order, and acknowledge Addendum No. 1 in your Expedite Proposal file before submitting your bid.


Very truly yours,

Eric M. Cardone, P.E.

Construction Contracts Engineer

EMC/mac

cc: Harry Adolphe, Project Manager



#### **FITCHBURG**

# Bridge Rehabilitation, F-04-010, River Street (ST 31) over North Nashua River

Questions and Responses

Addendum No. 1, November 17, 2023

# **UEL Contractors, email dated Monday, November 13, 2023**

- Question 1) Could you please tell me what the peak follow will be for the bypass sewer pumping?
- Response 1) The estimated peak flow for the 12-inch diameter pipe is 1.63 million gallons per day (MGD) which is the full pipe capacity (1.3 MGD) multiplied by 1.25 as specified on page A00801 96.

# Kodiak Corporation, email dated Tuesday, November 14, 2023

Question 2) Item 992.3 Temporary Supports for Bridge Structure suggests overhang brackets with timber blocking.

The support system requires the Contractor to submit engineered drawings proving the systems integrity will support "what"? Please provide degree of support.

Also, the available bridge inspection reports do not provide sufficient information regarding condition of deck above Beam # 4 nor the conditions of Beam # 3 & Beam # 4 Webs to allow for proper required P.E. drawings.

Does the Commonwealth have such necessary information available, or might they procure that information needed so that bidder may have sufficient information to estimate a most likely cost prior to bid.

Response 2) Item 992.3 covers temporary support for the existing bridge deck overhang during Phases 1A and 1B. The temporary barrier is unrestrained and the overhang shown accommodates the required working width (4'-5") for the unrestrained temporary barrier.

See Document A00873 provided in this addendum.

# Kodiak Corporation, email dated Tuesday, November 14, 2023

- Question 3) Construction Staging Notes (Phase 2B) Note 3 says contractor to assist Verizon. Please elaborate on degree of assistance contractor is expected to provide.
- Response 3) Contractor to install cross frames and provide site access for Verizon's contractor to drop conduits from temporary telephone duct support, pull wires through conduits and remove temporary telephone duct support from site. Contractor activities in this area will need to be coordinated with Verizon. No other assistance is anticipated.

## **FITCHBURG**

# Bridge Rehabilitation, F-04-010, River Street (ST 31) over North Nashua River

Questions and Responses

Addendum No. 1, November 17, 2023

# Kodiak Corporation, email dated Tuesday, November 14, 2023

- Question 4) Construction Staging Notes (Phase 2A) Note 4 shows "Verizon's Contractor" to construct duct support etc. Is the bridge contractor responsible for any of this support including providing adequate foundations and or certain types of access or access safety? If so, please explain.
- Response 4) The temporary telephone duct support (including foundations for the duct support) will be engineered, installed and removed from the site by Verizon's contractor. Activities such as demolition, excavation and pile installation will need to be coordinated with Verizon's contractor, as required. Verizon's contractor should be allowed access to the site and space to install their temporary telephone duct support.

# Kodiak Corporation, email dated Tuesday, November 14, 2023

- Question 5) Construction Staging Notes (Phase 2A) Note 2 shows temporary support for existing telephone utilities as the responsibility of the contractor. Under what item is this support paid for? Can the Commonwealth provide information regarding type / weight / size, etc. of what is being supported? Will a P.E. stamped drawing of support be required?
- Response 5) The existing telephone utilities consist of conduit banks (approx. 4" in diameter PVC conduits) as shown on the drawings. Temporary support of the telephone utilities will be needed during trench installation for the 60" HDPE pipe. Support drawings are not required for this activity. Cost of temporary support to be included in Item 142. Class B Trench Excavation.

# Kodiak Corporation, email dated Tuesday, November 14, 2023

- Question 6) Sheet 16 / 38 Bridge plans shows in 2 locations "existing stone masonry wall to be reconstructed". Please provide detail, dimensions etc. also item paying for this.
- Response 6) Existing stone masonry wall will be reconstructed with concrete. See Sheet 17 of 38 for details. Coordinate with plan views in the Stage Construction drawings. Excavation will be paid for under Item 140. Bridge Excavation (see spec). Concrete and steel for the reconstruction will be paid under Item 901.01 Concrete for Flood Wall, and Item 910.11 Steel Reinforcement for Flood Wall Epoxy Coated, respectively.

# **FITCHBURG**

# Bridge Rehabilitation, F-04-010, River Street (ST 31) over North Nashua River

Questions and Responses

Addendum No. 1, November 17, 2023

# **UEL Contractors, email dated Thursday, November 16, 2023**

- Question 7) Item 182.21 Removal of Asbestos is a lump sum item, can you identify / quantify what needs to be done?
- Response 7) The existing waterproofing membrane over the bridge deck and the existing utility pipes under the bridge may contain asbestos and must be tested to determine whether or not they contain asbestos. Payment for inspection and testing for asbestos will be paid for under the Item 182.1 "Inspection and Testing for Asbestos." Payment for removal of asbestos, if found, will be paid for under Item 182.21 "Removal of Asbestos."

# Kodiak Corporation, email dated Thursday, November 16, 2023

- Question 8) Sheet 9 of 38 show East Elevation of bridge. The 30" "pre-drilled" hole for piles is shown being drilled through the existing bridge footings. No existing bridge plans were made available in proposal package. Do the existing bridge footings contain rebar? Is the cost of drilling through the concrete footings covered under the item 944.2 Pre-drilling for Piles or 944.3 Drilling for Obstructions?
- Response 8) The existing bridge plans do not provide any detail of the existing abutments. The Contractor is advised to review the boring logs in the drawings and make a determination on the obstructions. Borings BB-4 and BB-5 are along the centerline of piles at the south abutment. Borings BB-1 and BB-6 are along the centerline of piles at the north abutment. Pile related pre-drill bid items are as follows:
  - Item 944.21 Test Probing for Pile Obstructions drilling a test hole at each pile location to the estimated pile tip elevation, to identify extents of obstructions.
  - Item 944.2 Pre-drilling for piles this item is used to pre-drill holes for piles to the limits shown on the Contract Drawings (identified as "Min. Bot. of Pre-drilling."
  - Item 944.3 Drilling for Pile Obstructions this item is used to drill through obstructions beyond the limits for Item 944.2, if identified as obstructions during test hole drilling.

# Kodiak Corporation, email dated Friday, November 17, 2023

- Question 9) Item 995 shows 4 different types of concrete yet the spec only one points out use of one type, please show use of the other three.
- Response 9) This response will be provided in a future addendum.



# TABLE OF CONTENTS (Continued)

1

DOCUMENT A00871 UNITED STATES DEPARTMENT OF THE INTERIOR FISH AND WILDLIFE SERVICE CONSISTENCY LETTER	A00871-1 through 10
DOCUMENT A00873 BRIDGE INSPECTION REPORTS	A00873-1 through 34
DOCUMENT A00875 POLICY DIRECTIVE P-22-001 AND POLICY DIRECTIVE P-22-002	A00875-1 through 8
DOCUMENT B00420 PROPOSAL	B00420-1 through 18
DOCUMENT B00842 SCHEDULE OF PARTICIPATION BY MINORITY OR WOMEN BUSINESS ENTERPRISE (M/WBE)	B00842-1 through 2
DOCUMENT B00843 MINORITY OR WOMENS BUSINESS ENTERPRISE PARTICIPATION LETTER OF INTENT	B00843-1 through 2
DOCUMENT B00846 M/WBE OR SDVOBE JOINT CHECK ARRANGEMENT APPROVAL FORM	B00846-1 through 2
DOCUMENT B00847 JOINT VENTURE AFFIDAVIT	B00847-1 through 4

\*\*\* END OF DOCUMENT \*\*\*

#### DOCUMENT 00813

#### SPECIAL PROVISIONS

#### PRICE ADJUSTMENTS FOR STRUCTURAL STEEL AND REINFORCING STEEL

November 16, 2023

This special provision applies to all projects containing the use of structural steel and/or reinforcing steel as specified elsewhere in the Contract work. It applies to all structural steel and all reinforcing steel, as defined below, on the project. Compliance with this provision is mandatory, i.e., there are no "opt-in" or "opt-out" clauses. Price adjustments will be handled as described below and shall only apply to unfabricated reinforcing steel bars and unfabricated structural steel material, consisting of rolled shapes, plate steel, sheet piling, pipe piles, steel castings and steel forgings.

Price adjustments will be variances between Base Prices and Period Prices. Base Prices and Period Prices are defined below.

Price adjustments will only be made if the variances between Base Prices and Period Prices are 5% or more. A variance can result in the Period Price being either higher or lower than the Base Price. Once the 5% threshold has been achieved, the adjustment will apply to the full variance between the Base Price and the Period Price.

Price adjustments will be calculated by multiplying the number of pounds of unfabricated structural steel material or unfabricated reinforcing steel bars on a project by the index factor calculated as shown below under <u>Example of a</u> Period Price Calculation.

Price adjustments will <u>not</u> include guardrail panels or the costs of shop drawing preparation, handling, fabrication, coatings, transportation, storage, installation, profit, overhead, fuel costs, fuel surcharges, or other such charges not related to the cost of the unfabricated structural steel and unfabricated reinforcing steel.

The weight of steel subject to a price adjustment shall not exceed the final shipping weight of the fabricated part by more than 10%.

### Base Prices and Period Prices are defined as follows:

<u>Base Prices</u> of unfabricated structural steel and unfabricated reinforcing steel on a project are fixed prices determined by the Department and found in the table below. While it is the intention of the Department to make this table comprehensive, some of a project's unfabricated structural steel and/or unfabricated reinforcing steel may be inadvertently omitted. Should this occur, the Contractor shall bring the omission to the Department's attention so that a contract alteration may be processed that adds the missing steel to the table and its price adjustments to the Contract.

The Base Price Date is the month and year of the most recent finalized period price index at the time that MassDOT opened bids for the project. The Base Price Index for this contract is the Steel PPI listed in the Notice to Contractors.

<u>Period Prices</u> of unfabricated structural steel and unfabricated reinforcing steel on a project are variable prices that have been calculated using the Period Price Date and an index of steel prices to adjust the Base Price.

The Period Price Date is the date the steel was delivered to the fabricator as evidenced by an official bill of lading submitted to the Department containing a description of the shipped materials, weights of the shipped materials and the date of shipment. This date is used to select the Period Price Index.

The index used for the calculation of Period Prices is the U.S. Department of Labor Bureau of Labor Statistics Producer Price Index (PPI) Series ID WPU101702 (Not Seasonally Adjusted, Group: Metals and Metal Products, Item: Semi-finished Steel Mill Products.) As this index is subject to revision for a period of up to four (4) months after its original publication, no price adjustments will be made until the index for the period is finalized, i.e., the index is no longer suffixed with a "(P)".

#### Period Prices are determined as follows:

Period Price = Base Price X Index Factor Index Factor = Period Price Index / Base Price Index

#### Example of a Period Price Calculation:

Calculate the Period Price for December 2009 using a Base Price from March 2009 of \$0.82/Pound for 1,000 Pounds of ASTM A709 (AASHTO M270) Grade A36 Structural Steel Plate.

The Period Price Date is December 2009. From the PPI website\*, the Period Price Index = 218.0.

The Base Price Date is March 2009. From the PPI website\*, the Base Price Index = 229.4.

Index Factor = Period Price Index / Base Price Index = 218.0 / 229.4 = 0.950 Period Price = Base Price X Index Factor = \$0.82/Pound X 0.950 = \$0.78/Pound

Since \$0.82 - \$0.78 = \$0.04 is less than 5% of \$0.82, no price adjustment is required.

If the \$0.04 difference shown above was greater than 5% of the Base Price, then the price adjustment would be 1,000 Pounds X \$0.04/Pound = \$40.00. Since the Period Price of \$0.78/Pound is less than the Base Price of \$0.82/Pound, indicating a drop in the price of steel between the bid and the delivery of material, a credit of \$40.00 would be owed to MassDOT. When the Period Price is higher than the Base Price, the price adjustment is owed to the Contractor.

\* To access the PPI website and obtain a Base Price Index or a Period Price Index, go to <a href="http://data.bls.gov/cgi-bin/srgate">http://data.bls.gov/cgi-bin/srgate</a>

#### End of example.

The Contractor will be paid for unfabricated structural steel and unfabricated reinforcing steel under the respective contract pay items for all components constructed of either structural steel or reinforced Portland cement concrete under their respective Contract Pay Items.

Price adjustments, as herein provided for, will be paid separately as follows:

#### Structural Steel

Pay Item Number 999.449 for positive (+) pay adjustments (payments to the Contractor)

Pay Item Number 999.457 for negative (-) pay adjustments (credits to MassDOT Highway Division)

#### Reinforcing Steel

Pay Item Number 999.466 for positive (+) pay adjustments (payments to the Contractor)

Pay Item Number 999.467 for negative (-) pay adjustments (credits to MassDOT Highway Division)

No price adjustment will be made for price changes after the Contract Completion Date, unless the MassDOT Highway Division has approved an extension of Contract Time for the Contract.



# **TABLE**

Steel		Price per Pound
1	ASTM A615/A615M Grade 60 (AASHTO M31 Grade 60 or 420) Reinforcing Steel	\$0.72
2	ASTM A27 (AASHTO M103) Steel Castings, H-Pile Points & Pipe Pile Shoes (See Note	\$0.98
2	below.)	\$0.76
3	ASTM A668 / A668M (AASHTO M102) Steel Forgings	\$0.98
4	ASTM A108 (AASHTO M169) Steel Forgings for Shear Studs	\$1.02
5	ASTM A709/A709M Grade 36 / AASHTO M270M/M270 Grade 36 or 250 Structural Steel	\$1.08
3	Plate	Ψ1.00
6	ASTM A709/A709M Grade 36 / AASHTO M270M/M270 Grade 36 or 250 Structural Steel	\$1.01
	Shapes	
7	ASTM A709/A709M Grade 50 / AASHTO M270M/M270 Grade 50 or 345 Structural Steel	\$1.08
	Plate	
8	ASTM A709/A709M Grade 50 / AASHTO M270M/M270 Grade 50 or 345 Structural Steel	\$1.01
0	Shapes	01.10
9	ASTM A709/A709M Grade 50WT / AASHTO M270M/M270 Grade 50WT or 345WT	\$1.12
10	Structural Steel Plate ASTM A709/A709M Grade 50WT / AASHTO M270M/M270 Grade 50WT or 345WT	\$1.02
10	Structural Steel Shapes	\$1.02
11	ASTM A709/A709M Grade 50W / AASHTO M270M/M270 Grade 50W 345W Structural Steel	\$1.12
	Plate	,
12	ASTM A709/A709M Grade 50W / AASHTO M270M/M270 Grade 50W or 345W Structural	\$1.02
	Steel Shapes	
13	ASTM A709/A709M Grade HPS 50W / AASHTO M270M/M270 Grade HPS 50W or 345W	\$1.18
	Structural Steel Plate	
14	ASTM A709/A709M Grade HPS 70W / AASHTO M270M/M270 Grade HPS 70W or 485W	\$1.25
15	Structural Steel Plate ASTM A514/A514M-05 Grade HPS 100W / AASHTO M270M/M270 Grade HPS 100W or	\$1.91
13	690W Structural Steel Plate	\$1.91
16	ASTM A992/A992M Grade 50S / AASHTO M270M/M270 Grade 50S or 345S Structural Steel	\$1.12
10	Plate	Ψ1.12
17	ASTM A992/A992M Grade 50S / AASHTO M270M/M270 Grade 50S or 345S Structural Steel	\$1.02
	Shapes	
18	ASTM A276 Type 316 Stainless Steel	\$5.72
19	ASTM A240 Type 316 Stainless Steel	\$5.72
20	ASTM A148 Grade 80/50 Steel Castings (See Note below.)	\$1.97
21	ASTM A53 Grade B Structural Steel Pipe	\$1.26
22	ASTM A500 Grades A, B, 36 & 50 Structural Steel Pipe	\$1.26
23	ASTM A252, Grades 240 (36 KSI) & 414 (60 KSI) Pipe Pile	\$1.00
24	ASTM 252, Grade 2 Permanent Steel Casing	\$1.00
	ASTM 232, Grade 2 remainent steer casing  ASTM A36 (AASHTO M183) for H-piles, steel supports and sign supports	\$1.07
25	, , , , , , , , , , , , , , , , , , , ,	
26	ASTM A572 / A572M Grade 50 (AASHTO M202) Steel Sheetpiling	\$1.88
27	ASTM A2C/2CM G 1 50	\$1.88
28	ASTM A36/36M, Grade 50	\$1.08
29	ASTM A570, Grade 50	\$1.07
30	ASTM A572 (AASHTO M223), Grade 50 H-Piles	\$1.08
31	ASTM A1085 Grade A (50 KSI) Steel Hollow Structural Sections (HSS), heat-treated per ASTM A1085 Supplement S1	\$1.26
32	AREA 140 LB Rail and Track Accessories	\$0.65

NOTE: Steel Castings are generally used only on moveable bridges. Cast iron frames, grates and pipe are not "steel" castings and will not be considered for price adjustments.

END OF DOCUMENT

THIS PAGE INTENTIONALLY LEFT BLANK

DOCUMENT A00873

# **BRIDGE INSPECTION REPORTS**

THIS PAGE INTENTIONALLY LEFT BLANK

# MASSACHUSETTS DEPARTMENT OF TRANSPORTATION PAGE \_1 OF \_23

STRUCTURES INSPECTION FIELD REPORT BR. DEPT. NO. 2-DIST B.I.N. ROUTINE INSPECTION 03 1KR F-04-010 CITY/TOWN 8.-STRUCTURE NO. 11-Kilo. POINT 41-STATUS 90-ROUTINE INSP. DATE **FITCHBURG** F04010-1KR-DOT-NBI 080.339 A:OPEN **AUG 15, 2022** 07-FACILITY CARRIED 27-YR BUILT 106-YR REBUILT YR REHAB'D (NON 106) MEMORIAL NAME/LOCAL NAME ST 31 RIVER ST 1900 1952 0000 06-FEATURES INTERSECTED 26-FUNCTIONAL CLASS DIST. BRIDGE INSPECTION ENGINEER WATER N NASHUA RIVER **Urban Arterial** 43-STRUCTURE TYPE 22-OWNER 21-MAINTAINER TEAM LEADER J. Snyder State Highway State Highway 402 : Steel continuous Stringer/Girder Agency Agency WEATHER TEMP. (air) TEAM MEMBERS 107-DECK TYPE K. A. OPENSHAW 1 : Concrete Cast-in-Place Sunny 27°C **ITEM 58 ITEM 59** ITEM 60 5 5 5 SUBSTRUCTURE SUPERSTRUCTURE **DECK** DEF DEF DEF 1. Abutments 5 S-P Ν Dive Cur 1.Wearing Surface 1.Stringers 2.Floorbeams a. Pedestals Ν Ν Ν 5 S-P 2. Deck Condition M-P b. Bridge Seats Ν 7 3. Floor System Bracing Ν 3.Stay in Place Forms Ν c. Backwalls Ν 5 S-P 5 4. Girders or Beams S-P S-P Ν 5 d. Breastwalls 5 S-P 4.Curbs 6 M-P e. Channel Walls Ν 5.Trusses - General Ν 5. Median Ν S-P f. Slope Paving/Rip-Rap Ν 6 a. Upper Chords Ν 4 S-A Ν 6 M-P q. Pointing 6.Sidewalks Ν b. Lower Chords h, Footings Ν Н Ν 7.Parapets i. Piles Ν Ν c. Web Members Ν 5 S-P 7 8.Railing j. Scour Ν d. Lateral Bracing N M-P Ν 6 k. Settlement Ν 9. Anti Missile Fence Ν e. Sway Bracings Ν N 7 10.Drainage System Ν Ν Ν f. Portals 2. Piers or Bents 7 Ν 11.Lighting Standards g. End Posts N Ν Ν a. Pedestals 5 S-P 12.Utilities 6.Pin & Hangers b. Caps Ν Ν Ν 13.Deck Joints 7. Conn Pit's, Gussets & Angles 6 c. Columns Ν M-P d. Stems/Webs/Pier Walls Ν 7 Ν 8.Cover Plates 14. Ν Ν Ν e. Pointing 9. Bearing Devices 6 M-P 15. N Н Ν f. Footing 6 Ν Ν 10. Diaphragms/Cross Frames g. Piles M-P Ν 16. Ν 7 h. Scour 11. Rivets & Bolts 7 i. Settlement Ν 7 F w 7 12. Welds Ν Ν **CURB REVEAL** 235 240 Ν N 7 (In millimeters) 13. Member Alignment 3. Pile Bents 4 14. Paint/Coating S-A **APPROACHES** DEF a. Pile Caps Ν Ν N 15. b. Piles Ν Ν a. Appr. Pavement Condition 5 S-P Ν Ν c. Diagonal Bracing 1976 Year Painted 7 b. Appr. Roadway Settlement d. Horizontal Bracing Ν Ν e. Fasteners Ν c. Appr. Sidewalk Settlement 6 M-P COLLISION DAMAGE: Please explain None (X) Minor ( ) Moderate ( ) Severe ( Ν UNDERMINING (Y/N) If YES please explain Ν OAD DEFLECTION: Please explain **OVERHEAD SIGNS** None ( ) Minor ( **X** ) Moderate ( ) Severe ( **COLLISION DAMAGE:** (Y/N) Ν (Attached to bridge) None (X) Minor ( ) Moderate ( ) Severe ( ) LOAD VIBRATION: Please explain DEF None ( ) Minor ( X ) Moderate ( ) Severe ( SCOUR: Please explain a Condition of Welds N None (X) Minor ( ) Moderate ( ) Severe ( b. Condition of Bolts Ν Any Fracture Critical Member: (Y/N) Ν Ν I-60 (This Report): 5 I-60 (Dive Report): Ν c. Condition of Signs Any Cracks: (Y/N) 00/00/0000 93B-U/W (DIVE) Insp

PAGE 2 OF 23

	N DATE							
FITCHBURG   1KR   F-04-010   F04010-1KR-DOT-NBI   AUG 1	5, 2022							
ITEM 61 TRAFFIC SAFETY ACCESSIBILITY	(Y/N/P)							
36 COND DEF	Needed Used							
A. Bridge Railing 0 5 S-P Lift Bucket	N N							
B. Iransitions	P N							
Dive Cur DEF C. Approach Guardrail N N - Boat	N N							
1.Channel Scour N 5 M-P D. Approach Guardrail Ends N N - Waders	P N							
2.Embankment Erosion N 7 - WEIGHT POSTING Not Applicable X Inspector 50	YY							
3.Debris N 7 - Rigging	N N							
4. Vegetation N 5 M-P Actual Posting N N N Staging	N N							
5.Utilities N N - Recommended Posting N N N N	N N							
6.Rip-Rap/Slope Protection N 7 - Waived Date: 11/19/2019 EJDMT Date: 00/00/0000 Police	N N							
7 Agrandation N 7	YY							
Signs In Place N S N S	N N							
8.Fender System N N - (Y=Yes,N=No, NR=NotRequired)	N N							
Legibility Visibility TOTAL HOURS	8							
CLEARANCE POSTING E W PLANS (Y/N	I): <b>Y</b>							
Not X ft in ft in meter	·/·							
I Poeted Clearance II II 0 III I 1 \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	N							
Tidal ( ) High ( ) Moderate ( ) Low ( X ) None ( )  At bridge Advance TAPE#:								
ITEM 61 (Dive Report): N ITEM 61 (This Report): 5 (Y=Yes,N=No,								
93b-U/W INSP. DATE: 00/00/0000   NR=Not Required)   NONE								
Visibility								
RATING Rating Report (Y/N):  Y  Recommend for Rating or Rerating (Y/N):  N  If YES please give priority:  HIGH ( ) MEDIUM ( ) LOW (	\							
Recommend for Rating of Relating (174).	,							
Date: 03/01/2019   REASON:								
Inspection data at time of existing rating  158: 5   159: 5   160: 6   Date : 08/14/2018								
60,11,2616								
CONDITION RATING GUIDE (For Items 58, 59, 60 and 61)								
CODE CONDITION DEFECTS								
N NOT APPLICABLE								
G 9 EXCELLENT Excellent condition.								
G 8 VERY GOOD No problem noted.								
G 7 GOOD Some minor problems.								
F 6 SATISFACTORY Structural elements show some minor deterioration.  F F FAIR  All primary structural elements are sound but may have minor action loss arraking appliing are sound.								
F 5 FAIR All primary structural elements are sound but may have minor section loss, cracking, spalling or scour.  P 4 POOR Advanced section loss, deterioration, spalling or scour.								
Loss of section, deterioration, spalling or scour have seriously affected primary structural components. Local failures are possible. Fatigue cra	acks							
P 3 SERIOUS in steel or shear cracks in concrete may be present.  Advanced deterioration of primary structural elements. Fatigue cracks in steel or shear cracks in concrete may be present or scour may have								
C 2 CRITICAL removed substructure support. Unless closely monitored it may be necessary to close the bridge until corrective action is taken.	_							
C 1 "IMMINENT" FAILURE Major deterioration or section loss present in critical structural components or obvious vertical or horizontal movement affecting structure stable Bridge is closed to traffic but corrective action may put it back in light service.	ility.							
0 FAILED Out of service - beyond corrective action.								
DEFICIENCY REPORTING GUIDE								
<b>DEFICIENCY:</b> A defect in a structure that requires corrective action.								
CATEGORIES OF DEFICIENCIES:								
M= Minor Deficiency Deficiencies which are minor in nature, generally do not impact the structural integrity of the bridge and could easily be repaired. Examples include but are not limited to: Spalled concrete, No Deficiency Defic	linor pot							
S= Severe/Major Deficiency Deficiencies which are more extensive in nature and need more planning and effort to repair. Examples include but are not limited to: Moderate to major deterioration in concrete, or severe/Major Deficiency Corroded rebars, Considerable settlement, Considerable scouring or undermining, Moderate to extensive corrosion to structural steel with measurable loss of section, etc.								
C-S= Critical Structural Deficiency A deficiency in a structural element of a bridge that poses an extreme unsafe condition due to the failure or imminent failure of the element which will affect the structural element.								
C. H Critical Hazard Deficionary. A deficiency in a component or element of a bridge that poses an extreme hazard or unsafe condition to the public, but does not impair the structural integrity of the bridge	je. Examples							
C-H = Critical Hazard Deticiency include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of briefly include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of briefly include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of briefly include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of briefly include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of briefly include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of briefly include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of briefly include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians.								
URGENCY OF REPAIR:								
URGENCY OF REPAIR:								
URGENCY OF REPAIR:  I = Immediate- [Inspector(s) immediately contact District Bridge Inspection Engineer (DBIE) to report the Deficiency and to receive further instruction from him/her].  A = ASAP- [Action/Repair should be initiated by District Maintenance Engineer or the Responsible Party (if not a State owned bridge) upon receipt of the Inspection Report].								

Addendum No. 1, November 17, 2023 PAGE 3 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022

# REMARKS

#### **BRIDGE ORIENTATION**

According to the plans the approaches are South and North, and the elevations are West and East. This is a two span continuous steel beam structure, with spans numbered from South to North. There are nine beams and eight bays numbered from West to East with a center pierwall. The river flows from West to East.

### ITEM 58 - DECK

## <u>Item 58.1 - Wearing Surface</u>

The North half of the Southbound lane has an "L" shaped 50 foot long x up to full width of the roadway bituminous patch. The patch is starting to deteriorate with shallow potholes and cracking at the edges and is slightly depressed. There are 2 temporary patches adjacent to this patch up to 10 feet long x 2 foot wide. **See photo #1.** 

The Northbound lane has a temporary bituminous patch 23 feet long x 5 foot wide at midspan. **See photo #2.** The remainder of the wearing surface has isolated areas of hairline to moderate transverse, longitudinal and map cracking. There is a 3 foot diameter depressed area of map cracking at midspan centerline of the wearing surface. **See photo #3.** 

### Item 58.2 - Deck Condition

The deck has many areas of moderate honeycombing, scaling, full width hairline transverse cracking and isolated minor to moderate hairline map cracking with moderate efflorescence, heaviest in bays #3, #5 and #6 of span #2. See photos #4 - #7.

The past leakage has caused many areas of rusting along the top flanges of the beams and in some cases into the web and bottom flanges.

There is minor spalling and rust and efflorescence staining around the scupper drain pipe in bay #2 of span #2. **See photo #6.** 

There is a full width x full depth repair to bay #4 of span #2 that extends from the north abutment to 6' north of the pier (wooden forms are still in place). **See photo #8.** This full depth concrete repair extends 6' out x full width of the bay in bays #4, #5 and #6.

Both sidewalk/deck fascias have full length intermittent moderate spalling with exposed rusted rebar along the bottom corner. **See photos #9 and #10.** 

### Item 58.4 - Curbs

The West granite curb has a full height x 1/2 inch diagonal crack near midspan. There is minor vegetation growing between the granite curbs and the west sidewalk.

Several of the granite curb sections at the South end of the West sidewalk are out of horizontal alignment, up to 4 inches. **See photo #11.** 

#### Item 58.6 - Sidewalks

There is heavy scaling, up to 35 feet x full width, and spalling up to 6 inches long x 3 foot wide x 3 inch deep with exposed rebar, throughout the East sidewalk. It is hollow sounding from the pier to the South abutment. **See photo #12.** 

The remainder of the East sidewalk has minor to moderate surface scaling and isolated hairline transverse cracking throughout.

The West sidewalk has intermittent areas of spalling and scaling heaviest at the South end. There is a full width  $x \frac{1}{4}$  inch wide crack over the pier.

Both sidewalk fascias have full length severe scaling and spalling, up to 3 inches deep, with exposed rusted rebar throughout, mostly along the bottom corner. **See photos #9 and #10.** 

A00873 - 5

Addendum No. 1, November 17, 2023 PAGE 4 OF 23

 CITY/TOWN
 B.I.N.
 BR. DEPT. NO.
 8.-STRUCTURE NO.
 INSPECTION DATE

 FITCHBURG
 1KR
 F-04-010
 F04010-1KR-DOT-NBI
 AUG 15, 2022

# REMARKS

## Item 58.8 - Railing

There is one bent picket on the West railing, just North of the pier. The bottom pipe rail of the West railing has 100% section loss at the North end.

One 7 foot long section of the East rail at the North end has moderate collision damage between the posts. **See photo #14.** 

The bottom horizontal of the East rail, one panel from the North, has 100% section loss and is disconnected. **See photo #15.** 

The North endpost of the East rail has a 2 inch long x 1 inch high area of 100% section loss to the bottom.

### <u>Item 58.10 - Drainage System</u>

There is a scupper drain at the Northwest end of the wearing surface (bay #2). See photo #6.

#### Item 58.12 - Utilities

There are utilities in bays #1, #7 and #8.

There is moderate rusting throughout to the utility conduits in bay #7, some up to 100% section loss . **See photo #16.** 

Several conduits in bays #1 of span #1 are broken and missing. See photo #17.

There a two disconnected supports to the utilities in bay #8 of span #1.

### **APPROACHES**

# Approaches a - Appr. Pavement Condition

The South approach to deck transition has a full lane width cracking. There is a 1.5 foot diameter pothole in the Northbound lane and a 1 foot diameter patched pothole in the Southbound lane. **See photo #18.** The South approach pavement has moderate transverse and longitudinal cracking throughout.

The North approach to deck transition has a full lane width crack in the Southbound lane extending 6 feet into the Northbound lane. There are three 1 foot diameter patched potholes in the Northbound lane and 1 in the Southbound lane. **See photo #19.** 

#### Approaches c - Appr. Sidewalk Settlement

There is up to 1.5 inches of approach sidewalk settlement at the Southwest approach sidewalk. **See photo #20.** 

### **ITEM 59 - SUPERSTRUCTURE**

## <u>Item 59.4 - Girders or Beams</u>

W 30X108:

Flange thickness: 0.76 inches Web thickness: 0.545 inches

Beams #2 through #6 in both spans have many areas of paint peeling with moderate to heavy surface rusting and minor rust flaking below the areas of leaking at the cracking, scaling and honeycombing of the deck. **See photos #4 - #7.** 

Beam #1 in both spans shows many areas of paint peeling with moderate surface rusting and minor rust flaking to the top and bottom flange on the West face. There is 0.5 inches remaining in span #1 bottom flange and 0.6 inches remaining in span #2 at approximately midspan. **See photo #21.** 

Beam #2 in span #2 has a 6 foot long section of 0.48 inches remaining to the bottom flange, East leg, at the first diaphragm from the North. **See photo #22**.

A00873 - 6

Addendum No. 1, November 17, 2023 PAGE 5 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022

# REMARKS

Beam #3 in span #2 has a 14 foot long section of section loss to the bottom flange, East edge, with measurements as little as 0.41 inches remaining measured 11.25 feet from the North edge of the pier bearing. **See photo #23.** The flange tapers to original thickness 2 feet North of this measurement.

Beam #6 in both spans has the worst deterioration where the paint peeling and rusting encompasses larger areas of the beam. In span #1 at 10 feet from the South end there is 0.52 inches remaining and in span #2 there is 0.51 inches remaining 10 feet north of the pier. **See photo #24.** 

Beam #9 in both spans has many areas of paint peeling on both sides of the beam with moderate to heavy rust flaking to the entire length of the top and bottom flanges and several areas of the web on the outside (East side) of the beam. At the pier and near midspan in spans #1 and #2 there is moderate rust flaking to the web and bottom flange with as little as 0.45 inches remaining to the bottom flange. Near midspan of span #2 the web has areas of 0.27" remaining near the top. **See photos #25 - #27.** 

# Item 59.7 - Conn Pit's, Gussets & Angles

See Item 59.14 - Paint/Coating for comments.

### Item 59.9 - Bearing Devices

All fascia bearings and bearing #5 on the pier show heavy surface rusting. The remainder of the bearings have minor to moderate surface rusting.

Several of the anchor bolt nuts are missing on the North bridge seat (West side of bearing #7, East side of bearings #5 & #6), and some of the nuts are not fully tightened. Of the 6 nuts that secures bearing #8, half of them are loose (West side at the South abutment and pier and to the East side at the North abutment).

# <u>Item 59.10 - Diaphragms/Cross Frames</u>

See Item 59.14 - Paint/Coating for comments.

### Item 59.14 - Paint/Coating

All the steel superstructure elements have moderate to heavy peeling of paint and minor to heavy surface rusting throughout. **See photos #4 - #7.** 

### **SuperStructure Load Deflection Notes**

Minor deflection under heavy live loads.

### **SuperStructure Load Vibration Notes**

Minor vibration under heavy live loads.

#### ITEM 60 - SUBSTRUCTURE

#### Item 60.1 - Abutments

### Item 60.1.b - Bridge Seats

There is a moderate amount of debris on the North bridge seat in bays #2, #3 and #4. See photo #28.

#### Item 60.1.c - Backwalls

The utility cutout in bay #1 of the South backwall shows heavy deterioration with moderate loss of fill which is now on the bridge seat. The loss of fill area is 2 foot wide x 2 foot high x 2 foot deep. The area is below the misaligned curb with daylight coming through. **See photo #29.** 

The utility cutout in bay #1 of the North backwall shows heavy deterioration with moderate loss of fill which is now on the bridge seat. The loss of fill area is 1.5 foot wide x 2.5 foot high x 1 foot deep.

The North backwall has moderate scale throughout and two shallow spalls with exposed rusted rebar in bay #7.

REM.(2)7-96

Addendum No. 1, November 17, 2023 PAGE 6 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022

# REMARKS

Most of the North brick utility backwall in bay #8 has collapsed. See photo #30.

## Item 60.1.d - Breastwalls

The breastwalls consist of mortared granite blocks with concrete caps. The North breastwall has a previous settlement and displacement crack along the pointing below beam #7 that does not extend into the concrete cap. There are 2 cracked stones in the area of the crack. This condition has not changed since the previous inspection. **See photo #7.** 

There is minor rust staining, vertical hairline cracking to the face of both caps.

The North breastwall cap has a 1 foot diameter shallow spall with exposed rusted rebar below beam #9, and a 1 foot diameter area of delamination and incipient spalling below beam #7. There are many areas of missing pointing throughout both breastwalls and voids with up to 4 feet of penetration, to the North breastwall at the East end. **See photo #7.** 

### Item 60.1.e - Channel Walls

The Northeast channel wall is missing some chinking stones and has voids with penetrations up to 5.5 feet.

The Northwest channel wall concrete cap has severe scaling/spalling. See photo #31.

See Item 61.4 - Vegetation for additional comments.

### Item 60.1.f - Slope Paving/Rip-Rap

A 15 foot long x 4 foot wide section of concrete is missing from the concrete and stone scour protection in front of the North abutment, below bays #4 and #5 and the South abutment along the bottom of the stone scour protection. **See photo #32.** 

### Item 60.1.g - Pointing

There is several areas of missing pointing and chinking stones in both breastwalls, with penetrations from 1.5 feet to 4 feet throughout both breastwalls.

### Item 60.1.k - Settlement

See Item 60.1.d - Breastwalls for comments.

#### Item 60.2 - Piers or Bents

# Item 60.2.d - Stems/Webs/Pier Walls

The pier wall has minor waterline abrasion.

# **ITEM 61 - CHANNEL AND CHANNEL PROTECTION**

### Item 61.1 - Channel Scour

There is granite block protection around the pier and evidence of concrete floor in several areas in both spans as a means of scour protection. Areas that do not show scour protection are deeper and possibly have been scoured out but do not present a threat to the integrity of the structure.

### Item 61.4 - Vegetation

There is heavy vegetation growing at all four corners of the bridge.

The Northeast channel wall has a 1 four inch diameter tree growing out of the base, and several through the rip rap. There is a 7 inch diameter tree at the top that is pushing two granite stones outward approximately 4 inches.

# **TRAFFIC SAFETY**

#### Item 36a - Bridge Railing

See Item 58.8 - Railing for comments.

REM.(2)7-96

Addendum No. 1, November 17, 2023 PAGE 7 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022

# REMARKS

## <u>Item 36b - Transitions</u>

There are no traffic safety features at the Northeast corner. The remaining corners of the bridge have adjacent driveways and properties and do not require traffic safety features.

# Photo Log

Photo 1: Repair in the Southbound lane at the North end.

Large patch in the Northbound lane near midspan.

Photo 3: Cracking to the wearing surface at midspan of the structure.

Photo 4: Bays #3 and #4 of span #1. Photo 5: Bays #4 and #5 of span #1.

Photo 6: Bays #2 and #3 of span #2. Note scupper drain in bay #2.

Photo 7: Bays #5 and #6 of span #2. Note crack and voids to the North breastwall.

Photo 8: Bays #4 of span #2.

Photo 9: Typical spalls to the deck overhang at the East fascia, span #2. Photo 10: Typical spalls to the deck overhang at the West fascia, span #1.

Photo 11: Loose curb stones at the South end of the West side.

Photo 12: Heavy scaling to the East sidewalk, span #1. Photo 13: Spall to the North end of the East sidewalk.

Photo 14: Bent rail at the North end of the East bridge rail.

Photo 15: 100% section loss to the bottom rail of the East bridge rail at the North end.

Photo 16: Typical corrosion of the utility conduits in bay #7.

Photo 17: Missing section of the utility conduit in bay #1 near South abutment.

Photo 18: South approach to deck transition. Note pothole in the Northbound lane.

Photo 19: North approach to deck transition.

Photo 20 : Southwest approach sidewalk settlement.

Photo 21: Beam #1 in span #1 midspan.

Photo 22: Beam #2 in span #2 near North end.
Photo 23: Beam #3 in span #2 near North end.
Photo 24: Beam #6 in span #2 near midspan.
Photo 25: Beam #9 in span #2 near midspan.

Photo 26 : Beam #9 in span #2 near midspan.

Photo 27: Beam #9 in span #2 near pier.

Photo 28: Debris on top of the North bridge seat in bays #2 - #4.

Photo 29: Fill from utility cutout at the South end of bay #1 in span #1. Note daylight.

Photo 30: Collapsed brick around utility at the North end of bay #8 in span #2.

Photo 31: Heavy scaling to the top of the Northwest channel wall.

Photo 32: Missing scour protection at the North breastwall.

REM.(2)7-96

PAGE 8 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 1: Repair in the Southbound lane at the North end.



Photo 2: Large patch in the Northbound lane near midspan.

PAGE 9 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 3: Cracking to the wearing surface at midspan of the structure.



Photo 4: Bays #3 and #4 of span #1.

PAGE 10 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 5: Bays #4 and #5 of span #1.



Photo 6: Bays #2 and #3 of span #2. Note scupper drain in bay #2.

PAGE 11 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 7: Bays #5 and #6 of span #2. Note crack and voids to the North breastwall.



Photo 8: Bays #4 of span #2.

PAGE 12 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 9: Typical spalls to the deck overhang at the East fascia, span #2.



Photo 10: Typical spalls to the deck overhang at the West fascia, span #1.

PAGE 13 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 11: Loose curb stones at the South end of the West side.



Photo 12: Heavy scaling to the East sidewalk, span #1.

PAGE 14 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 13: Spall to the North end of the East sidewalk.



Photo 14: Bent rail at the North end of the East bridge rail.

PAGE 15 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 15: 100% section loss to the bottom rail of the East bridge rail at the North end.



Photo 16: Typical corrosion of the utility conduits in bay #7.

PAGE 16 OF 23

 CITY/TOWN
 B.I.N.
 BR. DEPT. NO.
 8.-STRUCTURE NO.
 INSPECTION DATE

 FITCHBURG
 1KR
 F-04-010
 F04010-1KR-DOT-NBI
 AUG 15, 2022



Photo 17: Missing section of the utility conduit in bay #1 near South abutment.



Photo 18: South approach to deck transition. Note pothole in the Northbound lane.

PAGE 17 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 19: North approach to deck transition.



Photo 20: Southwest approach sidewalk settlement.

PAGE 18 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 21: Beam #1 in span #1 midspan.



Photo 22: Beam #2 in span #2 near North end.

PAGE 19 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022




Photo 23: Beam #3 in span #2 near North end.



Photo 24: Beam #6 in span #2 near midspan.

PAGE 20 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 25: Beam #9 in span #2 near midspan.



Photo 26: Beam #9 in span #2 near midspan.

PAGE 21 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 27: Beam #9 in span #2 near pier.



Photo 28: Debris on top of the North bridge seat in bays #2 - #4.

PAGE 22 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE
FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022




Photo 29: Fill from utility cutout at the South end of bay #1 in span #1. Note daylight.



Photo 30: Collapsed brick around utility at the North end of bay #8 in span #2.

PAGE 23 OF 23

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI AUG 15, 2022



Photo 31: Heavy scaling to the top of the Northwest channel wall.



Photo 32: Missing scour protection at the North breastwall.

10. 00/000-1241/1		Addend	ли IVO. 1,	November 17
	Classifica	ation		Code Y
(112) NBIS Bridge Length				Y
(104) Highway System (26) Functional Class -	Urban A	rtorial		14
(100) Defense Highway	Olbali A	iteriai		0
(101) Parallel Structure				N
(102) Direction of Traffic -		2-way traffic	•	2
(103) Temporary Structure		z-way ilalik	•	N
(105) Federal Lands Highways				0
(110) Designated National Net				N N
(20) Toll - On free				3
( - )	e Highway Age	encv		01
` '	e Highway Age	•		01
(37) Historical Significance		-	nresumed to	be not eligit Z
` ,			•	Code
(58) Deck				5
(59) Superstructure				5
(60) Substructure				5
(61) Channel & Channel Protect	ction			5
(62) Culverts				N
	Load Rating a	nd Posting		Code
(- / 3	20=M 18	· (LE)		4
<ul><li>(63) Operating Rating Method</li><li>(64) Operating Rating</li></ul>	- Load Facto	or (LF)		1 38.1
(65) Inventory Rating Method -	Load Facto	or (LF)		38.1
(66) Inventory Rating	Loud I doll	), (Li )		22.8
(70) Bridge Posting				5
(41) Structure - Ope	n			Α
	Apprais	sal		Code
(67) Structural Evaluation				5
(68) Deck Geometry				4
(69) Underclearances, vert. and	d horiz.			N
(71) Waterway adequacy				8
(72) Approach Roadway Alignn	nent			6
(36) Traffic Safety Features				0 N N N 4
(113) Scour Critical Bridges	Inspecti	ons		
(90) Inspection Date 08/	15/22	(91)	Frequency	24 MO
(92) Critical Feature Inspection	:			(93) CFI DATE
(A) Fracture Critical Detail		N 00	MO A)	00/00/00
(B) Underwater Inspection		N 00	MOB)	05/01/87
(C) Other Special Inspection		N 00	MO C)	08/05/15
(*) Other Inspection (FLOOD)	)	N 00	MO *)	09/15/23
(*) Closed Bridge		N 00	MO *)	00/00/00
(*) UW Special Inspection		N 00	MO *)	00/00/00
(*) Damage Inspection	Poting L	aada	MO *)	00/00/00
Report Date 03/01/19	Rating Lo	Type	3 Type 3	S2 Type HS
Operating	30.0			
Inventory	18.0	22.0	32.0	25.0
	Field Pos	sting		
Status WAIVED		Postin	g Date 11	/19/19
2 Axle	3 Axle	;	5 Axle	Single
Actual				
Recommended				
Missing Signs N	Misc			
Bridge Name				
N Anti-missile fence	N Acrow Pa	inel	N Jointle	ess Bridge
Freeze/Thaw N : Not Applica	ble			-
# Stairs On/Adjacent 0	Stair Owner(s	s)		
A	ccessibility (Ne	eded/Used	)	
N / N Liftbucket	N/N Riggir	ng	N/N	Other
P/N Ladder	N / N Stagir	ng		
N / N Boat	N / N Traffic	Control	1.	nspection
P/N Wader	N/N RRFI	agperson		nspection Hours: 008
Y / Y Inspector 50	Y/Y Police	:	•	

# National Bridge Element Inspection

BDEPT# F-04-010 Date 08/15/2022

B.I.N. 1KR District Bridge Inspection Eng'r Mahmood Azizi

Item 8 F04010-1KR-DOT-NBI Inspecting Agency Mass. Highway Dept.

Span Group 1 Team Leader John Snyder

Town Fitchburg Team Kenneth A. Openshaw

District 3 Member(s)

El#	Element Name	Units	Env.	Total Q.	% or Q	State 1	State 2	State 3	State 4
12	Re Concrete Deck	sq feet	2	4,406.000	<b>\ </b> \  \  \  \  \  \  \  \  \  \  \  \  \	3,306.000	1,080.000	20.000	
Notes:	•								
> 1080	Delamination/Spall/Patched Area	sq feet	2	600.000	<b>\ </b> \ \ \ \ \ \ \		580.000	20.000	
Notes:	•		•						
> 1130	Cracking (RC and Other)	sq feet	2	1,000.000	<b>\ </b> \ \ \ \ \ \ \	500.000	500.000		
Notes:	•		•						
> 510	Wearing Surfaces	sq feet	2	3,037.000	<b>\ </b> \ \ \ \ \ \ \	2,322.000	705.000	10.000	
Notes:	•								
> > 3210	Del/Spall/Patch/Pot(Wear Surf)	sq feet	2	655.000	<b>\ </b> \ \ \ \ \ \ \		655.000		
Notes:	•								
> > 3220	Crack (Wearing Surface)	sq feet	2	200.000	<u></u> %	140.000	50.000	10.000	
Notes:			_						
107	Steel Opn Girder/Beam	feet	2	804.000	%	204.000	340.000	260.000	
Notes:	•								
> 1000	Corrosion	feet	2	600.000	<u></u> %		340.000	260.000	
Notes:	•								
> 515	Steel Protective Coating	sq feet	2	6,431.000	<b>\ </b> \ \ \ \ \ \ \	0.000	3,215.500	2,250.850	964.650
Notes:	•								
> > 3440	Eff (Stl Protect Coat)	sq feet	2	6,431.000	<b>\ </b> \ \ \ \ \ \ \	0.000	3,215.500	2,250.850	964.650
Notes:	•								
210	Re Conc Pier Wall	feet	2	63.000	<b>\ </b> \  \  \  \  \  \  \  \  \  \  \  \  \	63.000			
Notes:	•								
217	Masonry Abutment	feet	2	126.000	<b>\ </b> \  \  \  \  \  \  \  \  \  \  \  \  \	109.000	17.000		
Notes:	•								

# National Bridge Element Inspection

BDEPT# F-04-010 Date 08/15/2022

B.I.N. 1KR District Bridge Inspection Eng'r Mahmood Azizi

Item 8 F04010-1KR-DOT-NBI Inspecting Agency Mass. Highway Dept.

Span Group 1 Team Leader John Snyder

Town Fitchburg Team Kenneth A. Openshaw

District 3 Member(s)

El #	Element Name	Units	Env.	Total Q.	% or Q	State 1	State 2	State 3	State 4
> 1610	Mortar Breakdown (Masonry)	feet	2	15.000	<b>\ </b> \  \  \  \  \  \  \  \  \  \  \  \  \		15.000		
Notes:		<u> </u>						•	
> 1640	Masonry Displacement	feet	2	2.000	<b>\  \  \  \  \  \  \  \  \  \  \  \  \  \</b>		2.000		
Notes:	•	•					•	•	•
311	Moveable Bearing	each	2	18	<b>\ </b> \  \  \  \  \  \  \  \  \  \  \  \  \	18			
Notes:	•							•	•
> 515	Steel Protective Coating	sq feet	2	54.000	<b>\ </b> \ \ \ \ \ \ \	36.000	9.000	9.000	
Notes:	•							•	•
> > 3440	Eff (Stl Protect Coat)	sq feet	2	54.000	<b>\ </b> \  \  \  \  \  \  \  \  \  \  \  \  \	36.000	9.000	9.000	
Notes:	•							•	•
313	Fixed Bearing	each	2	9	<b>\ </b> \  \  \  \  \  \  \  \  \  \  \  \  \	9			
Notes:	•							•	•
> 515	Steel Protective Coating	sq feet	2	27.000		27.000			
Notes:	•	•					•	•	
> > 3440	Eff (Stl Protect Coat)	sq feet	2	27.000	<b>\ </b> \ \ \ \ \ \ \	27.000			
Notes:								_	
330	Metal Bridge Railing	feet	2	200.000	<b>\ </b> \ \ \ \ \ \ \	170.000	10.000	20.000	
Notes:		_							
> 1000	Corrosion	feet	2	20.000	%		10.000	10.000	
Notes:	<u>.</u>							_	
> 1900	Distortion	feet	2	10.000				10.000	
Notes:									
> 515	Steel Protective Coating	sq feet	2	1,200.000	%	1,200.000			
Notes:	•	1						ı	

# National Bridge Element Inspection

BDEPT# F-04-010 Date 08/15/2022

B.I.N. 1KR District Bridge Inspection Eng'r Mahmood Azizi

Item 8 F04010-1KR-DOT-NBI Inspecting Agency Mass. Highway Dept.

Span Group 1 Team Leader John Snyder

Town Fitchburg Team Kenneth A. Openshaw

District 3 Member(s)

El #	Element Name	Units	Env.	Total Q.	% or Q	State 1	State 2	State 3	State 4
> > 3440	Eff (Stl Protect Coat)	sq feet	2	1,200.000	<b>\</b>	1,200.000			
Notes:									

MASSACHUSETT	S DEPARTMENT OF	F TRANSP	ORTA'	TION	PAGE	1	OF_	5
	S INSPECTION OTHER INSPECT		REP(	ORT			DEPT. N <b>)4-01</b> (	
CITY/TOWN 8ST	RUCTURE NO.	11-Kilo. POINT	90-ROUTI	NE INSP. D	DATE IN	ISPECTIO	N DATE	
FITCHBURG F	04010-1KR-DOT-NBI	080.339	Aug	15, 202	22	Sep	15, 20	023
07-FACILITY CARRIED ST 31 RIVER ST	MEMORIAL NAME/LOCAL NAME		27-YR BUILT 106 <b>1900</b>			YR REHA	B'D (NO)	N 106)
06-FEATURES INTERSECTED WATER N NASHUA RIVER	26-FUNCTIONAL CLASS  Urban Arterial	DIST. BRIDGE II	ER M	. Azizi				
43-STRUCTURE TYPE 402: Steel continuous Stringer/Girder	22-OWNER State Highway Agency 21-MAINTAINER State Highway Agency	TEAM LEADER	L. Fijol					
107-DECK TYPE  1 : Concrete Cast-in-Place	WEATHER TEMP. (air) Overcast 20°C	B. N. THO	NGPH/	ALA				
	Signs In Place	bridge W	Advance E	w	PLAN	S (Y	′N): \	<u></u>
Actual Posting         N         N         N         N           Recommended Posting         N         N         N         N           Waived Date:         11/19/2019         EJDMT Date:         00/00/0	(Y=Yes,N=No, NR=Not Required) Legibility/ Visibility				(V.C.R TAPE#	,	'N): <b>N</b>	1
Inspection data at time of existing rating 158: <b>5</b> 159: <b>5</b> 160: <b>6</b> 162: - Date:08/14				INV	PATING	OF MEMB		
MEMBER  CRACK (Y/N):  WELD'S CONDITION (0-9)	LOCATION OF CORROSION, SECTION L COLLISION DAMAGE, STRESS CONCI	.OSS (%), CRACKS, ENTRATION, ETC.				G ANALYS		ciencies
A								
В								
С								
D								
E								
List of field tests performed:	(Ove	rall Previous Co	ondition)	I-58 5	I-59 <b>5</b>	I-60 5	I-61 <b>5</b>	I-62
		rall Current Con	•	5	5	5	5	-
DEFICIENCY: A defect in a structure that requires corrective a  CATEGORIES OF DEFICIENCIES:  Deficiencies which are prints in patters, generally,	do not impact the structural integrity of the bridge on	d could easily be repaired	Evamples include	do but are not l	limited to: C	nalled coner	sto Minor no	

M = Minor Deficiency Deficiencies which are finite in nature, generally deficiency and set all sets which are finite in nature, generally deficiency and set all sets which are finite in nature, generally deficiency and sets are sets and sets are finite in nature, generally deficiency and sets are sets and sets are finite in nature, generally deficiency and sets are finite in nature.

S= Severe/Major Deficiency Deficiencies which are more extensive in nature and need more planning and effort to repair. Examples include but are not limited to: Moderate to major deterioration in concrete, Exposed and Considerable Severe/Major Deficiency Deficienc

C-S= Critical Structural Deficiency A deficiency in a structural element of a bridge that poses an extreme unsafe condition due to the failure or imminent failure of the element which will affect the structural integrity of the bridge.

C-H= Critical Hazard Deficiency

A deficiency in a component or element of a bridge that poses an extreme hazard or unsafe condition to the public, but does not impair the structural integrity of the bridge. Examples include but are not limited to: Loose concrete hanging down over traffic or pedestrians, A hole in a sidewalk that may cause injuries to pedestrians, Missing section of bridge railing, etc.

#### **URGENCY OF REPAIR:**

I = Immediate-[Inspector(s) immediately contact District Bridge Inspection Engineer (DBIE) to report the Deficiency and to receive further instruction from him/her].

A = ASAP-[Action/Repair should be initiated by District Maintenance Engineer or the Responsible Party (if not a State owned bridge) upon receipt of the Inspection Report].

P = Prioritize-[Shall be prioritized by District Maintenance Engineer or the Responsible Party (if not a State owned bridge) and repairs made when funds and/or manpower is available].

**N=NOT APPLICABLE** H=HIDDEN/INACCESSIBLE X=UNKNOWN R=REMOVED

Addendum No. 1, November 17, 2023 PAGE 2 OF 5

 CITY/TOWN
 B.I.N.
 BR. DEPT. NO.
 8.-STRUCTURE NO.
 INSPECTION DATE

 FITCHBURG
 1KR
 F-04-010
 F04010-1KR-DOT-NBI
 SEP 15, 2023

# REMARKS

## **BRIDGE ORIENTATION**

According to the plans the approaches are South and North, and the elevations are West and East. This is a two span continuous steel beam structure, with spans numbered from South to North. There are nine beams and eight bays numbered from West to East with a center pierwall. The river flows from West to East. **See sketch 1.** 

### **GENERAL REMARKS**

## Scope

This Other Inspection is performed to monitor the structure after the extensive 9/11/2023 flooding event.

### **Bridge Open**

Bridge is open at time of inspection, but the road was closed due to construction project.

## Water Height/Velocity

Water height and velocity are of normal conditions. See photos 1 - 3.

## **Findings**

No deficiencies are noted as a result of the flood event.

#### **Additional Notes**

Due to lack of access, inspection is topside only. Visible channel appears similar to pre-flood conditions.

### Sketch / Photo Log

Sketch 1 : Locus map
Photo 1 : Upstream view
Photo 2 : Downstream

Photo 3: Debris at upstream channel nose

A00873 - 31

2

Ь

က

PAGE

PAGE 4 OF 5

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI SEP 15, 2023



Photo 1: Upstream view



Photo 2: Downstream

PAGE 5 OF 5

CITY/TOWN B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. INSPECTION DATE FITCHBURG 1KR F-04-010 F04010-1KR-DOT-NBI SEP 15, 2023



Photo 3: Debris at upstream channel nose