

PROJECT:

West Parish Filters Water Treatment
Plant
1515 Granville Road
Westfield, MA 01085
Project No. 24-51

ADDENDUM NO. 6 04/25/2024

Posted: 04/25/2024 at 5:32PM EDT

Awarding Authority/Owner:

Springfield Water and Sewer Commission
250 M Street Extension
Agawam, MA 01001

Reference Contract Documents (drawings and specifications) dated 02/26/2024

The attention of Bidders submitting proposals for the above subject project is called to the following addendum to the specifications and drawings. The items set forth herein, whether of omission, addition, substitution, or clarifications are all to be included in and form a part of the proposal submitted.

THE NUMBER OF THIS ADDENDUM (6) MUST BE ENTERED IN THE APPROPRIATE SPACE "B" PROVIDED AFTER THE WORD "NUMBERS" OF THE CONTRACT FORM ENTITLED "FORM FOR GENERAL BID," AND IN SPACE "B" OF THE "FORM FOR SUB-BID."

BID DOCUMENT MODIFICATIONS ARE AS FOLLOWS.

Other Modifications / Attachments:

The following attachment includes additional modifications, clarifications and/or provisions not included in the items above in this Addendum.
See document at the end of document.

All other of the portions of the Contract Documents remain unchanged. Please be reminded to acknowledge this Addendum on the bid forms.

ATTACHMENTS

24-51 Addendum No. 6.pdf

--- End of Addendum No. 6 ---

SPRINGFIELD WATER AND SEWER COMMISSION

WEST PARISH WATER TREATMENT PLANT

SWSC BID NO. 24-51

ADDENDUM NO. 6



Marc W. Morin
04/25/2024

TO ALL CONTRACTORS ESTIMATING:

Bidders are hereby informed that plans and specifications for the above-mentioned contract are modified, corrected, and/or supplemented as follows, and that Addendum No. 6 becomes a part of the Contract Documents and consists of Item Nos. 6-1 through 6-11.

DRAWING CHANGES

ITEM 6-1: S-007 STRUCTURAL STANDARD DETAILS SHEET 5

Delete Note 1 in its entirety and replace with the following:

- “1. CONTRACTOR SHALL FURNISH AND INSTALL STEEL DETAILED ON THIS DRAWING. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION

OF THE STEEL DETAILED ON THIS DRAWING WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR. FILED SUB-BID MASONRY SUBCONTRACTOR SHALL FURNISH AND INSTALL MASONRY ON THIS DRAWING. SEE SPECIFICATION 04 00 00.”

ITEM 6-2: S-008 STRUCTURAL STANDARD DETAILS SHEET 6

Delete Note 1 in its entirety and replace with the following:

- “1. CONTRACTOR SHALL FURNISH AND INSTALL STEEL DETAILED ON THIS DRAWING. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION OF THE STEEL DETAILED ON THIS DRAWING WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR. FILED SUB-BID MASONRY SUBCONTRACTOR SHALL FURNISH AND INSTALL MASONRY ON THIS DRAWING. SEE SPECIFICATION 04 00 00.”

ITEM 6-3: S-1704 WATER TREATMENT BUILDING SECTIONS AND DETAILS-ADMINISTRATION AREA

Delete Note 3 in its entirety and replace with the following:

- “3. SEE ARCH DRAWINGS FOR STONE RELIEF LOCATION AT CANOPY. STONE RELIEF SUPPORT SHALL BE L8X8X1/2 GALVANIZED WITH 1/2" DIAMETER GALVANIZED ADHESIVE ANCHORS AT 16" ON CENTER AND A 6" MINIMUM EMBEDMENT. PROVIDE 3.5" STEEL EDGE DISTANCE IN LEG FOR ANCHOR HOLE. MIN 3 ANCHORS PER ANGLE. CONTRACTOR SHALL FURNISH AND INSTALL STONE RELIEF SUPPORT STEEL. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION OF STONE RELIEF SUPPORT STEEL WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR. THE FILED SUB-BID MASONRY SUBCONTRACTOR SHALL FURNISH AND INSTALL MASONRY ON THIS DRAWING. SEE SPECIFICATION 04 00 00.”

ITEM 6-4: S-1704 WATER TREATMENT BUILDING SECTIONS AND DETAILS-ADMINISTRATION AREA

Detail 5: Delete note in its entirety and replace with the following:

- “NOTE: CONTRACTOR SHALL FURNISH AND INSTALL STEEL SHOWN IN DETAIL 5. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION OF STEEL SHOWN IN DETAIL 5 WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR.

FILED SUB-BID MASONRY SUBCONTRACTOR SHALL INSTALL MASONRY SHOWN IN DETAIL 5. SEE SPECIFICATION 04 00 00.

ITEM 6-5: S-2702 WATER TREATMENT BUILDING SECTIONS - PROCESS AREA SHEET 2

Delete Note 1 in its entirety and replace with the following:

- "1. SEE ARCH DRAWINGS FOR SPLITFACE RELIEF LOCATION. SPLITFACE RELIEF SUPPORT SHALL BE 3/8"X7 1/2"X7 1/2" GALVANIZED STEEL BENT PLATE WITH 1/2" DIAMETER GALVANIZED ADHESIVE ANCHORS AT 24" ON CENTER, 5" MINIMUM EDGE DISTANCE, AND 6" MINIMUM EMBEDMENT. PROVIDE 1 1/2" STEEL EDGE DISTANCE IN LEG FOR ANCHOR HOLE. MINIMUM 3 ANCHORS PER BENT PLATE. CONTRACTOR SHALL FURNISH AND INSTALL SPLITFACE RELIEF SUPPORT STEEL. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION OF SPLITFACE RELIEF SUPPORT STEEL WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR. THE FILED SUB-BID MASONRY SUBCONTRACTOR SHALL FURNISH AND INSTALL MASONRY ON THIS DRAWING. SEE SPECIFICATION 04 00 00."

ITEM 6-6: S-2704 WATER TREATMENT BUILDING SECTIONS - PROCESS AREA SHEET 4

Delete Note 1 in its entirety and replace with the following:

- "1. SEE ARCH DRAWINGS FOR STONE RELIEF LOCATION. STONE RELIEF SUPPORT SHALL BE L8x8x1/2 GALVANIZED WITH 5/8" DIAMETER GALVANIZED ADHESIVE ANCHORS AT 32" ON CENTER, 9 1/2" MINIMUM EDGE DISTANCE, AND 6" MINIMUM EMBEDMENT. PROVIDE 1 1/2" STEEL EDGE DISTANCE IN LEG FOR ANCHOR HOLE. MIN 3 ANCHORS PER ANGLE. CONTRACTOR SHALL FURNISH AND INSTALL STONE RELIEF SUPPORT STEEL. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION OF STONE RELIEF SUPPORT STEEL WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR. THE FILED SUB-BID MASONRY SUBCONTRACTOR SHALL FURNISH AND INSTALL MASONRY ON THIS DRAWING. SEE SPECIFICATION 04 00 00."

ITEM 6-7: S-2706 WATER TREATMENT BUILDING SECTIONS - PROCESS AREA SHEET 6

Delete Note 1 in its entirety and replace with the following:

- "1. SEE ARCH DRAWINGS FOR SPLITFACE RELIEF LOCATION. SPLITFACE RELIEF SUPPORT SHALL BE 3/8" X 7 1/2" X 7 1/2" GALVANIZED STEEL BENT PLATE WITH 1/2" DIAMETER GALVANIZED ADHESIVE ANCHORS AT 24" ON CENTER, 5" MINIMUM EDGE DISTANCE, AND 6" MINIMUM EMBEDMENT. PROVIDE 1 1/2" STEEL EDGE DISTANCE IN LEG FOR ANCHOR HOLE. MIN 3 ANCHORS PER BENT PLATE. CONTRACTOR SHALL FURNISH AND INSTALL SPLITFACE RELIEF SUPPORT STEEL. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION OF SPLITFACE RELIEF SUPPORT STEEL WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR. THE FILED SUB-BID MASONRY SUBCONTRACTOR SHALL FURNISH AND INSTALL MASONRY ON THIS DRAWING. SEE SPECIFICATION 04 00 00."

ITEM 6-8: S-2714 WATER TREATMENT BUILDING SECTIONS - PROCESS AREA SHEET 14

Delete Note 1 in its entirety and replace with the following:

- "1. SEE ARCH DRAWINGS FOR STONE RELIEF LOCATION. STONE RELIEF SUPPORT SHALL BE GALVANIZED STEEL L8X8X1/2 WITH 5/8" DIAMETER GALVANIZED ADHESIVE ANCHORS AT 32" ON CENTER, 5 1/2" MINIMUM EDGE DISTANCE, AND 6" MINIMUM EMBEDMENT. PROVIDE 1 1/2" STEEL EDGE DISTANCE IN LEG FOR ANCHOR HOLE. MIN 3 ANCHORS PER ANGLE. CONTRACTOR SHALL FURNISH AND INSTALL STONE RELIEF SUPPORT STEEL. PRIOR TO INSTALLATION, CONTRACTOR SHALL COORDINATE AND VERIFY LOCATION OF STONE RELIEF SUPPORT STEEL WITH THE FILED SUB-BID MASONRY SUBCONTRACTOR. THE FILED SUB-BID MASONRY SUBCONTRACTOR SHALL FURNISH AND INSTALL MASONRY ON THIS DRAWING. SEE SPECIFICATION 04 00 00."

SPECIFICATION CHANGES

ITEM 6-9: Section 00 11 00 – Advertisement for Bids

Page 1, Delete the Filed Sub-Bid Deadline and insert the following:

"FILED SUB-BID DEADLINE: MAY 14, 2024 2:00 PM"

ITEM 6-10: Section 00 20 00 – Instructions to Bidders

Delete paragraph 9.01 in its entirety and replace with the following:

“All questions about the meaning or intent of the Bidding Documents shall be submitted to Owner in writing to Theo Theocles at Theo.Theocles@waterandsewer.org and to Engineer in writing to Marc Morin at MMorin@hazenandsawyer.com. To receive consideration, questions must be received by Owner and Engineer no later than Tuesday, April 30, 2024 at 4:30 PM (EST) for Filed Sub-Bids and no later than Tuesday, May 14, 2024 at 4:30 PM (EST) for General Bids. Interpretations or clarifications considered necessary by Engineer in response to such questions will be issued by Addenda mailed or delivered to all parties recorded by Engineer as having received the Bidding Documents for receipt not later than Tuesday, May 7, 2024 for Filed Sub-Bids and not later than Tuesday, May 21, 2024 for General Bids. Only questions answered by Addenda will be binding. Oral and other interpretations or clarifications will be without legal effect.”

ITEM 6-11: Section 04 00 00 – Basic Masonry Requirements

Delete paragraphs 1.02.E and 1.02.F in their entirety and replace with the following:

- “E. CONTRACTOR shall furnish and install masonry relief angles and steel lintels and jamb angles with bolted connections to support masonry veneer in accordance with Section 05 05 23 – Metal Fastening and Section 05 50 00 – Metal Fabrications.
 - 1. CONTRACTOR to coordinate locations with MASONRY CONTRACTOR.

- F. CONTRACTOR shall furnish and install steel plate, angle and anchors for top of masonry wall connections in accordance with Section 05 05 23 – Metal Fastening and Section 05 50 00 – Metal Fabrications.
 - 1. CONTRACTOR to coordinate locations with MASONRY CONTRACTOR.”

SPRINGFIELD WATER AND SEWER COMMISSION

Theo G. Theocles, Esq.
Director of Legal Affairs/Chief Procurement Officer

Date: April 25, 2024