



Maura Healey, Governor
Kimberley Driscoll, Lieutenant Governor
Monica Tibbitts-Nutt, Secretary & CEO
Jonathan L. Gulliver, Highway Administrator



May 1, 2024

Proposal No. 609427-125646

ADDENDUM NO. 3

To Prospective Bidders and Others on:

MONTAGUE
Federal Aid Project No. STP(BR-OFF)-003S(734)X
Bridge Replacement, M-28-026, South Street over Sawmill River

THIS PROPOSAL TO BE
OPENED AND READ ON:

TUESDAY, MAY 7, 2024, at 2:00 P.M.

Transmitting changes to the Contract Documents as follows:

RESPONSES TO CONTRACTOR'S QUESTIONS:

1 Page

Please take note of the above and acknowledge Addendum No. 3 in your Expedite Proposal file before submitting your proposal.

Sincerely,

Eric M. Cardone, P.E.
Construction Contracts Engineer

EMC/jmr
cc: Christopher Cameron, Project Manager

MONTAGUE
Federal Aid Project No. STP(BR-OFF)-003S(734)X
Bridge Replacement, M-28-026, South Street over Sawmill River
(609427-125646)

RESPONSES TO CONTRACTOR'S QUESTIONS

ADDENDUM NO. 3, MAY 1, 2024

A.J. Virgilio email dated April 25, 2024:

Question #1: Can you please provide the height you intend for us to use for the VA-5 curb? The height of this curb varies and our curb suppliers need to know the height in order to price. Also, the type VA-5 curb is 6" wide and the type VB curb is only 5" wide. Is it your intention to butt a 5" wide curb up to a 6" wide curb?

Response #1: The depth of the VA5 curb shall be 17"-19". The curb shall be butted and set in accordance with Subsection 501 of the Standard Specifications.

Question #2: Could you please provide an approximate start date for the above project.

Response #2: The Department expects to issue a Notice to Proceed approximately 60 days after the Bid Opening date.

A.J. Virgilio email dated April 30, 2024:

Question #3: The provided permit applications and reports within the specifications mention dredging many times, yet there are no bid items for it. Please confirm that dredging is not required on this project.

Response #3: The Sawmill River will not support a barge and traditional dredging equipment.

Excavating and regrading the existing Sawmill River streambed outside of cofferdams shall be in accordance with Item 143.

Excavating and regrading the existing Sawmill River streambed within cofferdams shall be in accordance with Item 140.1.