



Maura Healey, Governor
Kimberley Driscoll, Lieutenant Governor
Monica Tibbitts-Nutt, Secretary & CEO
Jonathan L. Gulliver, Highway Administrator



August 1, 2025

612109-131226

ADDENDUM NO. 1

To Prospective Bidders and Others on:

CHICOPEE - SOUTH HADLEY
Federal Aid Project No. NHP(NHS)-0032(048)X
Resurfacing and Related Work on Route 33

THIS PROPOSAL TO BE OPENED AND READ: TUESDAY, AUGUST 19, 2025 at 2:00 P.M.

Transmitting revisions to the Contract Documents as follows:

<u>DOCUMENT 00010:</u>	Revised page 1.
<u>DOCUMENT 00715:</u>	Deleted document in its entirety and inserted new document (8 pages).
<u>DOCUMENT B00853:</u>	Deleted document in its entirety and inserted new document (2 pages).
<u>DOCUMENT B00854:</u>	Deleted document in its entirety and inserted new document (2 pages).

Take note of the above, substitute the revised page for the original delete the documents indicated, insert new documents in proper order, and acknowledge Addendum No. 1 in your Expedite Proposal file before submitting your bid.

Very truly yours,

Eric M. Cardone, P.E.
Construction Contracts Engineer

HA
cc: Koby J Lemrise, Project Manager

THIS PAGE INTENTIONALLY LEFT BLANK

① Addendum No. 1, August 1, 2025

DOCUMENT 00010

TABLE OF CONTENTS

DOCUMENT 00010	
TABLE OF CONTENTS	00010-1 through 2
DOCUMENT 00104	
NOTICE TO CONTRACTORS	00104- 1 through 4
DOCUMENT 00210	
REQUIREMENTS OF MASSACHUSETTS GENERAL LAWS CHAPTER 30 SECTION 39R; CHAPTER 30, SECTION 39O	00210-1 through 4
DOCUMENT 00331	
LOCUS MAP	00331-1 through 2
DOCUMENT 00439	
CONTRACTOR PROJECT EVALUATION FORM	00439-1 through 2
DOCUMENT 00440	
SUBCONTRACTOR PROJECT EVALUATION FORM	00440-1 through 2
DOCUMENT 00710	
GENERAL CONTRACT PROVISIONS.....	00710-1 through 2
DOCUMENT 00715	
① SUPPLEMENTAL SPECIFICATIONS	00715-1 through 8
DOCUMENT 00719	
SPECIAL PROVISIONS FOR PARTICIPATION BY DISADVANTAGED BUSINESS ENTERPRISES	00719-1 through 18
DOCUMENT 00760	
REQUIRED CONTRACT PROVISIONS FOR FEDERAL-AID CONSTRUCTION CONTRACTS.....	00760-1 through 14
DOCUMENT 00811	
MONTHLY PRICE ADJUSTMENT FOR HOT MIX ASPHALT (HMA) MIXTURES.....	00811-1 through 2
DOCUMENT 00812	
MONTHLY PRICE ADJUSTMENT FOR DIESEL FUEL AND GASOLINE	00812-1 through 2
DOCUMENT 00813	
PRICE ADJUSTMENT FOR STRUCTURAL STEEL AND REINFORCING STEEL	00813-1 through 4
DOCUMENT 00814	
PRICE ADJUSTMENT FOR PORTLAND CEMENT CONCRETE MIXES	00814-1 through 2
DOCUMENT 00820	
THE COMMONWEALTH OF MASSACHUSETTS SUPPLEMENTAL EQUAL EMPLOYMENT OPPORTUNITY, NON-DISCRIMINATION AND AFFIRMATIVE ACTION PROGRAM	00820-1 through 6
DOCUMENT 00821	
ELECTRONIC REPORTING REQUIREMENTS CIVIL RIGHTS PROGRAM AND CERTIFIED PAYROLL	00821-1 through 2
DOCUMENT 00859	
CONTRACTOR/SUBCONTRACTOR CERTIFICATION FORM	00859-1 through 2

DOCUMENT 00715



SUPPLEMENTAL SPECIFICATIONS

JUNE 30, 2025

The 2025 *Standard Specifications for Highways and Bridges* are amended by the following modifications, additions and deletions. These Supplemental Specifications prevail over those published in the Standard Specifications.

The Specifications Committee has issued these Supplemental Specifications for inclusion into each proposal until such time as they are updated or incorporated into the next Standard Specifications.

Contractors are cautioned that these Supplemental Specifications are dated and will change as they are updated.

DIVISION I

GENERAL REQUIREMENTS AND COVENANTS

SECTION 2.00: PROPOSAL REQUIREMENTS AND CONDITIONS

Subsection 2.09: Rejection of Proposals

Replace bullet (i) in the third paragraph with the following:

- (i.) award of the contract would result in the Bidder exceeding the Aggregate Bonding Capacity or the Single Bonding Capacity established by its Surety Company, or the Bidder's Proposal exceeds its Single Contract Limit, or the Bidder was not prequalified in the specified class of work on or before the time of bid opening; or

SECTION 7.00: LEGAL RELATIONS AND RESPONSIBILITY TO PPUBLIC

Subsection 7.05: Insurance Requirements

Change the title of paragraph A to Workers' Compensation Insurance

Subsection 7.22: Labor, Lodging, Board, Maximum Hours of Employment, Weekly Payment, Keeping of Payroll Records.

In the second paragraph replace the word "workman" to "worker" and the word "workmen" to "workers".

Replace the third paragraph with the following:

Attention of Bidders is called to MGL Chapter 149, Section 148 requiring the weekly payment of employee wages.

SECTION 9.00: MEASUREMENT AND PAYMENT

Subsection 9.03: Payment for Extra Work

Replace paragraph B., first paragraph, numbers (2) and (3) with the following.

- (2) Plus 13 percent of direct labor, for the estimated costs of Federal Insurance Contribution Act (FICA) including Medicare; Federal Unemployment Tax Act (FUTA); State Unemployment Tax Act (SUTA), which includes Unemployment Insurance, the Workforce Training Fund Program, Employer Medical Assistance Contribution, and COVID-19 Recovery Assessment; Earned Sick Time (EST) Law (940 CMR 33.00); and Paid Family and Medical Leave (PFML) Act (458 CMR 2.00); or, as an alternative to the above 13 percent, the Contractor may elect to use actual rates for FICA, FUTA, SUTA, EST and PFML provided the actual rates are supported with verifiable documentation and shall be subject to review by MassDOT Audit Operations.
- (3) Plus the estimated cost of Workers' Compensation and Liability Insurance, Health, Welfare and Pension benefits, and such additional fringe benefits which the Contractor is required to pay as a result of Union Labor Agreements and/or is required by authorized governmental agencies;

In paragraph B., second paragraph, number (3), replace the word "Workmen's" with "Workers".

DIVISION II
CONSTRUCTION DETAILS
SECTION 300: WATER SYSTEMS
SUBSECTION 301: WATER SYSTEMS

Subsection 301.60G: Laying Pipe

Revise the third paragraph to read as follows:

Pipe sections shall be laid with the bell on the upgrade end. Before laying the pipe, the outside of the spigot and the inside of the bell shall be wire brushed and wiped clean and dry.

Subsection 301.80: Method of Measurement

Delete the words cast iron in the first paragraph.

Replace the second paragraph with the following:

Fittings, consisting of bends, tees, caps, wyes, sleeves, reducers, increasers, blow-off fittings and other special fittings, apply only when new materials are necessary and which are not specifically provided for under other items in the Proposal. Fittings other than new will not be paid separately but only under the applicable pipe items. When new fittings are measured separately for payment, the length of pipe occupied by the fittings will not be measured for payment.

SECTION 800: TRAFFIC CONTROL DEVICES

**SUBSECTION 850: TRAFFIC CONTROLS FOR CONSTRUCTION AND MAINTENANCE
OPERATIONS**

Subsection 850.29: Temporary Barrier and Temporary Barrier Removed and Reset

Delete this subsection.

Subsection 850.49: Temporary Barrier

Delete this subsection.

Subsection 850.69: Temporary Barrier and Temporary Barrier Removed and Reset

Delete this subsection.

Subsection 850.80: Method of Measurement

Delete the fifth paragraph from the end of this subsection.

Subsection 850.81: Basis of Payment

Delete the sixth and seventh paragraphs from the end of this subsection.

SUBSECTION 853: TEMPORARY BARRIER

Subsection 853.: Temporary Barrier

Add this new subsection:

DESCRIPTION

853.20: General

Work under this Subsection consists of furnishing, placing, adjusting, resetting, maintaining, and removing temporary barrier.

MATERIALS

853.40: General

Materials shall meet the requirements specified in the following Subsections of Division III, Materials:

Material	Section
Precast, Prestressed, and Prefabricated Concrete Products	M4.09.0
Temporary Barrier	M10.16.0
Limited Deflection Temporary Barrier	M10.16.1
Delineators for Temporary Barrier	M10.16.2

The Contractor shall supply a temporary barrier system that meets or exceeds the Test Level (TL) designated in the description of the bid item.

If the Contractor uses a proprietary temporary barrier system, it shall be listed on the QTCE.

Temporary barrier segments that appear to be damaged or in otherwise unsuitable condition may be rejected or ordered to be replaced by the Engineer at no additional cost.

853.41: Deflection

The deflection of a temporary barrier system is defined as the measured deflection, permanent and/or dynamic, during MASH Test Designation 2-11 (for TL-2) or Test Designation 3-11 (for TL-3).

The Contractor shall supply a temporary barrier system that is equal to or less than the maximum allowable deflection (permanent and/or dynamic) for each run of temporary barrier, as shown in the Plans or stated in the Special Provisions. If no distinction between permanent and temporary deflection is shown in the plans or Special Provisions, then dynamic deflection shall govern.

853.42: Precast Concrete Barriers

Precast Concrete Barriers used as temporary barriers shall be fabricated in accordance with M4.09.0: Precast, Prestressed, and Prefabricated Concrete Products. The Contractor shall submit a Certificate of Compliance (CoC) attesting to meeting this requirement.

853.43: Delineation

Delineators installed at 20-ft intervals throughout the entire barrier run shall be included. The delineators shall conform to M10.16.2: Delineators for Temporary Barrier. Delineators that may act as a washer on a bolted connection shall not be used unless specifically allowed by the barrier manufacturer. Delineators that are damaged, are no longer reflective, or go missing while temporary barrier is deployed shall be replaced in kind by the Contractor.

Delineators may be top or side-mounted to the barrier and oriented in a manner to maximize reflectivity to approaching traffic.

Temporary barrier placed on the right side of the travel way, or top-mounted and separating two or more lanes traveling in the same direction, shall use white delineators. Temporary barrier placed on the left side of the travel way shall use amber or yellow delineators; if separating two-way traffic and top-mounted, the delineator shall be double-sided.

853.44: Anchored Barrier

Temporary barrier systems that include an anchor system in order to meet performance requirements of the contract and/or meet MASH testing requirements may be accepted for use at the discretion of the Department.

Barrier that utilizes an anchor system shall use the same pattern, placement, and material of anchors that was used in MASH crash testing.

853.45: Shop Drawings

Within 30 days of the Notice to Proceed, the Contractor shall provide Shop Drawings showing the proposed temporary barrier system and confirming that it conforms to 853.40: General and will meet the allowable deflection requirements as described in 853.41: Deflection.

If anchors are proposed, the means, methods, pattern, placement, and materials for anchoring and subsequent pavement and/or deck repairs following removal of the temporary barrier system shall be included in the Shop Drawing submittal. If the use of an anchor system is rejected by the Department, the Contractor shall select an unanchored system that meets or exceeds the contract specified performance requirements, at no additional cost.

Shop Drawings for proprietary barrier systems shall include manufacturer's instructions for installation.

CONSTRUCTION METHODS

853.60: General

A Traffic Management Plan approved by the Department is required prior to the installation of the temporary barrier system.

The Contractor shall install temporary barrier systems in accordance with the Plans.

Barrier ends shall not be exposed to approaching traffic during installation. Crashworthy shielding or attenuation shall be provided at all times.

Proprietary temporary barrier systems shall be installed per the manufacturer's instructions.

The Contractor shall not place any breaks in the temporary barrier system that will result in sections that are shorter than the tested minimum length-of-need (LON) under MASH Test 2-11 (for TL-2) or 3-11 (for TL-3). Exceptions shall be allowed for gate systems or changeable length segments placed over expansion joints, if those barrier segment types have been determined to be crashworthy per MASH.

Temporary barrier shall not be placed on unpaved surfaces, unless otherwise shown in the Plans.

The Contractor shall not store materials, vehicles, or other equipment within the measured dynamic deflection envelope, as defined in 853.41: Deflection.

853.61: Temporary Barrier Removed and Reset

Temporary Barrier Removed and Reset consists of relocating a string of temporary barrier from one alignment to another to support the sequence and phasing of construction, as shown in the Plans.

Temporary Barrier Removed and Reset does not include moving all or a portion of the temporary barrier system to gain access to a work area, for the convenience of the Contractor, or to realign units that have moved due to construction activities or a traffic incident.

853.62: Quality Control Inspection

After temporary barrier installation is completed, the Contractor shall perform a Quality Control (QC) Inspection in the presence of the Engineer. QC Inspection activities shall include, but are not limited to the following reviews:

- Installation location per the approved Plans.
- Alignment and connection mechanism between adjacent barrier segments.
- Alignment and connection mechanism between barrier segment and attenuator, if present.
- Anchor system installation, if present.

For proprietary barrier systems, the QC Inspection shall also include any manufacturer-specific inspection details or criteria found in the installation instructions.

Work behind the barrier shall not commence until the QC Inspection has been accepted by the Engineer.

COMPENSATION

853.80: Method of Measurement

Temporary Barrier will be measured by the foot installed, in place.

Temporary Barrier Removed and Reset will be measured by the foot removed and reset.

853.81: Basis of Payment

Temporary Barrier will be paid for at the contract unit price per foot which shall provide full compensation for fabrication, storage, transport, furnishment, installation, delineation, alignment, maintenance, repair, and final removal of the temporary barrier.

Temporary Barrier Removed and Reset will be paid for at the contract unit price per foot which shall provide full compensation for removing, relocating, transporting, and installing new anchorage (if used). If more than one accepted temporary barrier system is approved for use in a single contract, the unit cost for Temporary Barrier Removed and Reset shall not differ among systems.

All costs associated with fabrication, installation, and maintenance of temporary barrier delineators shall be considered incidental to the cost of the item.

All costs associated with Shop Drawings and COCs shall be considered incidental to the item.

All costs associated with patching or repairing the road surface or bridge deck due to the installation and removal of temporary barrier and/or anchors for a temporary barrier system shall be considered incidental to the cost of the item.

853.82: Payment Items

Item number	Description	Unit
853.2	Temporary Barrier (TL-2)	Foot
853.21	Temporary Barrier Removed and Reset	Foot
853.23	Temporary Barrier (TL-3)	Foot
853.33	Temporary Barrier – Limited Deflection (TL-3)	Foot

SECTION 900: STRUCTURES

SUBSECTION 902: ULTA HIGH PERFORMANCE CONCRETE

Subsection 902.32: Mockup

In Table 902.32-1 change the Link Slab width to 2 ft – 0 in. and change the Joint Header width to 0 ft – 6 in. .

Subsection 902.32: - 902.38

Renumber section 902.32 Surface Preparation to 902.33 Surface Preparation and renumber section 902.33 through 902.38 to 902.34 through 902.39.

DIVISION III

MATERIALS SPECIFICATIONS

SECTION M2: AGGREGATES AND RELATED MATERIALS

Subsection M2.01.0 Crushed Stone

Replace the fourth paragraph and the associated asterisk notes with the following;

The crushed stone shall have a maximum 45% wear as determined by the Los Angeles Abrasion Test (AASHTO T 96)

SECTION M5: PIPE, CULVERT SECTIONS AND CONDUIT

Subsection M5.01.0 Joint Materials for Pipe

Replace this subsection with the following;

- Jute or oakum furnished for use in pipe joints shall be of an accepted grade approved for common usage.
- Mortar shall conform to the requirements of M4.04.0: Cementitious Grout, Mortar and Concrete Products
- Standard couplers as approved by the manufacturer shall be used to join corrugated metal pipe
- Rubber ring or plastic gaskets for concrete pipe joints, or manholes section joints shall be of tough, flexible, chemical-resistant material, and of such size and shape as to ensure satisfactory pipe joints when incorporated in the work and shall conform to AWWA C153.
- Rubber gasket joints for ductile iron pipe shall be Styrene-Butadiene Rubber (SBR), Ethylene Propylene Diene Monomer (EPDM) or Nitrile and conform to AWWA C111

Subsection M5.05.03.B Gate Valves

Replace this subsection with the following;

Gate valves shall conform to the requirements of AWWA Standard C500 and/or to the type used by the municipality as specified in the Special Provisions.

SECTION M7: PAINTS, PROTECTIVE COATINGS AND PAVEMENT MARKINGS

Subsection M7.01.04 Fast Drying White and Yellow Waterborne Traffic Paint

Replace the subsection with the following;

Approved waterborne traffic paint shall be tested in accordance with AASHTO M 348 and be listed on the QCML. The dry paint film shall be under the Toxicity Characteristic Leaching Procedure (TCLP) limits for all contaminants listed in 40 CFR 261.24. The markings shall be installed using reflective glass beads meeting the requirements of M7.01.07. For waterborne yellow paint use Organic Yellow No. 65 or No. 75 pigment.

SECTION M9: MISCELLANEOUS MATERIALS

Subsection M9.12.0 Reflectors for Barriers

Delete this subsection.

SECTION M10: TRAFFIC CONTROL DEVICES

Subsection M10.16.0: Temporary Barrier

Subsection M10.16.1: Limited Deflection Temporary Barrier

Subsection M10.16.2: Delineators for Temporary Barrier

Add these new subsections.

Addendum No. 1, August 1, 2025

DOCUMENT B00853

**SCHEDULE OF PARTICIPATION
BY DISADVANTAGED BUSINESS ENTERPRISES (DBEs)**

APPENDIX F – FORM F3: DBE SCHEDULE OF PARTICIPATION

PRIME BIDDER: _____

DATE OF BID OPENING: _____ MassDOT PROJECT NO.: 612109FEDERAL AID PROJECT NUMBER: NHP(NHS)-0032(048)XPROJECT LOCATION: CHICOPEE - SOUTH HADLEY

Name Address and Phone Number of DBE	Name of Activity	NAICS Code(s)	(a) DBE Contractor Activity Amount <i>Construction Work</i>	(b) DBE Other Business Amount <i>Services, Supplies, Material</i>	(c) Total amount eligible for credit
Total Bid Amount	TOTALS:		\$		\$
\$ <u>204,889</u>	DBE Percentage of Total bid:		%		%

A copy of the DBE's most recent certification and an original affidavit must be attached to this document.

Is a Joint Check Approval being submitted for any of the above? ☐ Yes ☒ No

Will any of the contractors listed above be using a third party to deliver materials or perform any portion of work?

☐ Yes ☒ No

(i.e. manufacturing)

SIGNATURE: _____ DATE _____

NAME AND TITLE (PRINT): _____

EMAIL ADDRESS: _____ TEL NO.: _____

Rev'd 5/8/13

THIS PAGE INTENTIONALLY LEFT BLANK

DOCUMENT B00854

DBE Letter of Intent

(To be completed by the DBE – Page 1 of 2)

The DBE firm will also include the latest MassUCP letter with this Letter of Intent.

To: _____ (Prime Bidder)

From: _____ (DBE Firm)

Federal Aid Project No.: NHP(NHS)-0032(048)X Bid Opening or Due Date: _____

Project Name: Resurfacing and Related Work on Route 33 Project Location: CHICOPEE - SOUTH HADLEY

I, _____, authorized signatory of the above-reference DBE firm hereby declare:

(Print Name)

(a) My company is currently certified as a Disadvantaged Business Enterprise (DBE) by the Massachusetts Supplier Diversity Office (SDO), as a (check all that apply):

- ☐ CONTRACTOR ☐ REGULAR DEALER ☐ OTHER
☐ MANUFACTURER ☐ TRUCKING OPERATIONS ☐ PROFESSIONAL SERVICES

[Additional guidance is available at Title 49, Code of Federal Regulations, Part 26.55 (49 CFR Part 26.55)]

- (b) My firm has the ability to manage, supervise and perform the activity described on page 3 of this Letter of Intent. If you are awarded the contract, my company intends to enter into a contract with your firm to perform the items of work or other activity described on the following sheet for the prices indicated.
- (c) There have been no changes affecting the ownership, control or independence of my company since my last certification review on _____. If any such change is planned or occurs prior to my company's completion of this proposed work, I will give prior written notification to your firm and to the Office of Diversity and Civil Rights (ODCR)(MBTA/MassDOT) and SDO.
- (d) I have read the MassDOT proposal for the Project, and acknowledge that my company will comply with that document and the requirements of 49 CFR Part 26.
- (e) For the purpose of obtaining subcontractor approval from the MassDOT, my firm will provide to you:
- a. **The following construction work:**
 - i. a complete list of contact information for proposed Superintendent, i.e., address, phone number and e-mail address, and;
 - ii. a list of projects completed in the last 10 years. I shall also include, for each project: the name and telephone number of a contact person for the contracting authority, person, or organization; project title / location (City/State), dollar value of the work; a description of the work; and the date project completed .
 - b. **The following professional services work:**
 - i. resume, stating the qualifications and experience of person responsible for project oversight and contact information, i.e., address, phone number and e-mail address.
 - ii. proposed team and organization,
 - iii. resumes of key personnel;
 - iv. example projects
 - c. **The following services, materials or supplies:**
 - i. a written agreement and invoices for the materials or supplies, and any other documents evidencing the terms of providing such items to be sent to the Office of Diversity and Civil Rights Government Compliance Unit designee;
 - ii. information concerning brokers fees and commissions for providing services or materials.

DBE Firm Authorized Signature

Date

Addendum No. 1, August 1, 2025

DBE Letter of Intent (Continued)

(To be completed by the DBE – Page 2 of 2)

Prime Bidder: _____

DBE Firm: _____

Federal Aid
Project No.:

NHP(NHS)-0032(048)X

Bid Opening or Due Date: _____

Project Name:

Resurfacing and Related Work on Route 33

Project Location:

CHICOPEE - SOUTH
HADLEY

<u>Item number</u> if applicable	<u>NAICS</u> <u>Code</u>	<u>Description of Activity</u> with notations such as Services, or Brokerage, Labor Only, Material Only, or Complete	<u>Quantity</u>	<u>Unit Price</u>	<u>Amount</u>
TOTAL AMOUNT:					

Please give full explanations, attach additional sheets if necessary.

I HEREBY VERIFY THAT _____

(DBE Firm)

WILL SOLELY PERFORM THE WORK, OR PROVIDE THE SERVICES OR MATERIALS, AS DESCRIBED ABOVE.

DBE Authorized Signature: _____

Name (Print): _____

Title: _____

Email Address: _____

Phone Number: _____

Fax Number: _____

END OF DOCUMENT