

STATE OF RHODE ISLAND
DEPARTMENT OF TRANSPORTATION

RHODE ISLAND CONTRACT NO. 2025-CB-057
FEDERAL-AID PROJECT NO. BHO-026C(001)

BRIDGE GROUP 26C
WOONSOCKET BLACKSTONE RIVER WEST

Rehabilitation of Singleton Street Bridge No. 095501
Rehabilitation of River Street Bridge No. 095601

City of Woonsocket
County of Providence
Rhode Island

DISTRIBUTION OF QUANTITIES

GM2 Associates, Inc.
Pawtucket, Rhode Island

September 2025

Quantity Backup Table of Contents

SINGLETON & RIVER STREET RECONSTRUCTION, BRIDGE GROUP 26C

R.I. Contract No. 2025-CB-057

FAP No. BHO-026C(001)

Item	Item Code	Description	UM	Quantity	Page
1	201.0321	CLEARING AND GRUBBING	SY	650	1
2	201.0414	REMOVE AND DISPOSE PIPE - ALL TYPES	LF	40	2
3	201.0415	REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES	LF	500	3
4	201.0428	REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER	EACH	4	4
5	201.0436	REMOVAL AND DISPOSAL OF CURBING	LF	525	5
6	201.0438	REMOVAL AND DISPOSAL OF FENCES AND RAILINGS	LF	60	6
7	201.0610	REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY, SERVICE, AND STREET SIGNS	EACH	18	7
8	202.0100	EARTH EXCAVATION	CY	600	8
9	202.0900	HANDLE, HAUL, AND STOCKPILE MANAGEMENT OF CONTAMINATED SOILS AND UNCLASSIFIED SOILS	TON	1050	9
10	202.0920	LOAD AND HAUL CONTAMINATED SOIL, TYPE 2	TON	425	10
11	202.0921	DISPOSAL OF CONTAMINATED SOIL, TYPE 2	TON	425	11
12	202.0930	LOAD AND HAUL CONTAMINATED SOIL, TYPE 3	TON	620	12
13	202.0931	DISPOSAL OF CONTAMINATED SOIL, TYPE 3	TON	620	13
14	202.0960	LOAD, HAUL, AND DISPOSAL OF OTHER WASTE	TON	5	14
15	203.0100	STRUCTURE EXCAVATION EARTH	CY	110	15
16	206.0301	COMPOST FILTER SOCK	LF	1000	16
17	209.0220	SACK INSERT INLET PROTECTION	EACH	3	17
18	212.2200	MAINTENANCE AND CLEANING OF EROSION, SEDIMENT, AND POLLUTION PREVENTION CONTROLS	LS	1	18
19	213.0100	PLACEMENT OF MILLINGS BENEATH GUARDRAIL	LF	500	19
20	302.0100	GRAVEL BORROW SUBBASE COURSE	CY	600	20
21	401.0510	HOT MIX ASPHALT PREPARATION - PARTIAL DEPTH	SY	350	21
22	401.0520	HOT MIX ASPHALT PREPARATION - FULL DEPTH	SY	1475	22
23	401.1000	CLASS 19.0 HMA	TON	525	23
24	401.3005	CLASS 9.5 HMA FOR MISCELLANEOUS USE	TON	25	24
25	401.3100	MODIFIED CLASS 9.5 HMA	TON	200	25
26	603.1000	CONTROLLED LOW STRENGTH MATERIAL	CY	20	26
27	701.0300	REINFORCED CONCRETE PIPE M 170 - ALL SIZES	LF	60	27
28	701.5402	DUCTILE IRON WATER PIPE, MECHANICAL JOINT - ALL SIZES	LF	100	28
29	701.8003	PIPE BEDDING CLASS C	CY	40	29
30	702.0501	FRAME AND GRATE - ALL SIZES AND TYPES	EACH	4	30
31	702.0502	FRAME AND COVER - ALL SIZES AND TYPES	EACH	2	31
32	702.0529	INLET STONE - ALL SIZES AND TYPES	EACH	2	32
33	702.0545	APRON STONE - ALL SIZES AND TYPES	EACH	1	33
34	702.1000	MANHOLE, CATCH BASIN, OR DROP INLET ASSEMBLY - (0' - 12' DEPTH)	EACH	1	34
35	704.0500	RECONSTRUCT DRAINAGE STRUCTURE	EACH	3	35
36	707.0100	ADJUST DRAINAGE OR UTILITY STRUCTURE TO GRADE	EACH	8	36
37	708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	LF	200	37
38	708.9044	CLEANING AND FLUSHING VERTICAL STRUCTURE	EACH	7	38
39	709.0400	CONCRETE FOR THRUST BLOCKS, HEADWALLS, AND MISC PURPOSES	CY	5	39
40	712.0300	GATE BOX - ALL TYPES	EACH	1	40
41	713.0100	ADJUST CURB STOP OR UTILITY BOX TO GRADE	EACH	7	41
42	803.0350	REMOVAL AND DISPOSAL OF EXISTING CONCRETE MASONRY	CY	725	42
43	803.0500	TEMPORARY DECK UNDERSIDE AND SIDE PROTECTIVE SHIELDING	SF	23000	43
44	808.0322	CONCRETE SUBSTRUCTURE CLASS HP 3/4" END POSTS	CY	75	44
45	808.0602	CONCRETE SUBSTRUCTURE CLASS XX 3/4" BACKWALLS	CY	10	45
46	808.9901	LIGHTWEIGHT CONCRETE SUPERSTRUCTURE CLASS HP 3/4" BRIDGE DECKS	CY	560	46
47	808.9902	LIGHTWEIGHT CONCRETE SUPERSTRUCTURE CLASS HP 3/4" BRIDGE SIDEWALKS	CY	150	47
48	808.9903	EXPOSED AGGREGATE SURFACE TREATMENT	SF	10750	48
49	810.0210	GALVANIZED BAR REINFORCEMENT GRADE 60	LBS	160000	49
50	810.0702	WELDED WIRE FABRIC (GALVANIZED)	SF	1300	50
51	817.2142	REPAIRS TO STRUCTURE CONCRETE MASONRY - FORM AND CAST IN PLACE CONCRETE	CF	475	51
52	819.0800	DRILL AND GROUT REINFORCING DOWELS	EACH	125	52
53	820.0100	CONCRETE SURFACE TREATMENT PROTECTIVE SEALER	SF	16600	53
54	823.9901	PREFORMED JOINT SEAL	LF	120	54
55	824.2000	STRUCTURAL STEEL	LBS	9000	55
56	824.2200	WELDED STUD SHEAR CONNECTORS	EACH	6250	56

Quantity Backup Table of Contents

SINGLETON & RIVER STREET RECONSTRUCTION, BRIDGE GROUP 26C

R.I. Contract No. 2025-CB-057

FAP No. BHO-026C(001)

Item	Item Code	Description	UM	Quantity	Page
57	824.9901	STRUCTURAL STEEL REPAIRS	LBS	115000	57
58	824.9902	RIVET REPLACEMENT	EACH	1000	58
59	825.8040	PAINTING EXISTING STRUCTURAL STEEL	SF	81500	59
60	825.8050	SURFACE PREPARATION FOR EXISTING STEEL	SF	86000	60
61	827.8038	THERMAL SPRAYED ZINC COATING STRUCTURAL STEEL	SF	86000	61
62	830.1000	METAL BRIDGE RAILING	LF	850	62
63	834.0100	GRANITE CURB FOR BRIDGES	LF	850	63
64	836.0100	STRUCTURAL CONCRETE CRACK REPAIR BY EPOXY-RESIN BASE ADHESIVE INJECTION	LF	75	64
65	841.0100	PRE AND POST CONSTRUCTION CONDITION SURVEY	LS	1	65
66	901.1000	STEEL BEAM GUARDRAIL	LF	350	66
67	901.1050	GUARDRAIL CONNECTION TO END POST	EACH	7	67
68	901.1100	STEEL BEAM GUARDRAIL APPROACH END TREATMENT	EACH	3	68
69	901.1200	GUARDRAIL END TREATMENT PLATFORM	EACH	3	69
70	901.1300	STEEL BEAM GUARDRAIL ANCHORAGE TRAILING END SECTIONS	EACH	2	70
71	903.0510	FENCE - PERMANENT ALL TYPES AND SIZES	LF	50	71
72	904.0100	REMOVE AND RESET FENCE AND/OR RAILING	LF	100	72
73	905.1000	PORTLAND CEMENT CONCRETE SIDEWALKS AND DRIVEWAYS	SY	575	73
74	906.0310	GRANITE CURB	LF	520	74
75	906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES	LF	275	75
76	919.0101	TEST PITS	EACH	5	76
77	920.0320	RIPRAP R-3, R-4, R-5 STANDARD 8 3.0	SY	1000	77
78	929.0110	FIELD OFFICE	PMO	42	78
79	936.0110	MOBILIZATION	LS	1	79
80	937.0100	FURNISH, INSTALL, MAINTAIN, AND MOVE TEMPORARY TRAFFIC PROTECTION	LS	1	80
81	943.0300	TRAINEE HOURS	HR	2000	81
82	999.9901	MISCELLANEOUS WORK	EACH	75000	82
83	L01.0102	LOAM BORROW 4 INCHES DEEP	SY	125	83
84	L02.0107	SEEDING	SY	125	84
85	L06.9901	ARONIA MELONCARPA - BLACK CHOKEBERRY	EACH	5	85
86	L06.9902	PRUNUS VIRGINIANA - CHOKE CHERRY	EACH	4	86
87	L06.9903	RHUS TYPHINA - STAGHORN SUMAC	EACH	3	87
88	L06.9904	NEW ENGLAND CONSERVATION - WILDLIFE SEED MIX	SY	100	88
85	T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	SF	85	85
86	T15.0200	REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN	EACH	2	86
87	T20.0101	PAVEMENT MARKINGS	LF	2000	87
88	T20.0102	TEMPORARY PAVEMENT MARKINGS	LS	1	88
89	T20.0103	ARROWS, WORDS, OR SYMBOLS PAVEMENT MARKINGS	EACH	5	89



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 1

ITEM CODE: 201.0321 CLEARING AND GRUBBING

UM: SY

<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>
	Bridge 095501	300
	Bridge 095601	300

As Directed By the Engineer

50

TOTAL 650 SY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 2

ITEM CODE: 201.0414 REMOVE AND DISPOSE PIPE - ALL SIZES

UM: LF

PROJECT WIDE

<u>LOCATION</u>	<u>PIPE SIZE</u>	<u>TOTAL</u>
River St	18"	30

As Directed by Engineer

10

TOTAL 40 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 3

ITEM CODE: 201.0415 REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES

UM: LF

<u>PROJECT WIDE</u>	<u>Sta</u>	=	<u>Say</u>
Singleton St	201+00 Lt	110	110
	201+00 Rt	120	120
	203+60 Lt	20	20
	203+60 Rt	40	40
River St.	301+75 Rt	70	70
	302+00 Rt	60	60
	304+50 Lt	30	30

As Directed By the Engineer

50

TOTAL 500 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 4

ITEM CODE: 201.0428 REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER

UM: EA

PROJECT WIDE

<u>Location</u>	<u>TOTAL</u>
Singleton St.	1
River St.	2

As Directed by Engineer

1

TOTAL 4 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 5

ITEM CODE: 201.0436 REMOVAL & DISPOSAL OF CURBING

UM: LF

<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>
	Singleton St.	151
	River St.	353

As Directed by Engineer

21

TOTAL 525 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 6

ITEM CODE: 201.0438 REMOVAL & DISPOSAL OF FENCES AND RAILINGS

UM: LF

<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>
Ref Item No. 903.0510	Singleton St.	50

As Directed by Engineer

10

TOTAL 60 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	KM	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 7

ITEM CODE: 201.0610 REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY,

SERVICE, AND STREET SIGNS UM: EA

PROJECT WIDE

TOTAL

Ref. Item T15.0100	Replacement of old to new	17
--------------------	---------------------------	----

PRICE INCLUDES EACH SIGN ASSEMBLY

As Directed by Engineer

1

TOTAL 18 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 8

ITEM CODE: 202.0100 EARTH EXCAVATION

UM: CY

PROJECT WIDE

Installation of Gravel Borrow Subbase

SF

CF

CY

Roundup

CY

<u>Ref Item 401.0520/302.0100</u>	12 inches	12,456	12456	461.3333	462
<u>Ref Item 905.1000/302.0100</u>	8 inches	4,392	2942.64	108.9867	109
<u>Ref Item 401.0520/302.0100</u>	8 inches	174	116.58	4.317778	5

As Directed by Engineer

24

TOTAL 600 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 9

ITEM CODE: 202.0900 HANDLE, HAUL, AND STOCKPILE MANAGEMENT OF
CONTAMINATED SOILS AND UNCLASSIFIED SOILS
UM: TON

SINGLETON STREET

	<u>Depth</u>	<u>SF</u>	<u>CF</u>	<u>CY</u>	<u>Weight</u>
<u>Ref Item 401.0520</u>	1	8,001	8,001	296.33	445
<u>Ref Item 905.1000</u>	0.667	1,884	1,257	46.54	70
<u>Ref Item 401.0520</u>	0.667	30	20	0.74	2
<u>Ref Item 203.0100</u>				60	90

RIVER STREET

<u>Ref Item 401.0520</u>	1	4,455	4,455	165.00	248
<u>Ref Item 905.1000</u>	0.67	2,508	1,680	62.24	94
<u>Ref Item 401.0520</u>	0.67	144	96	3.57	6
<u>Ref Item 203.0100</u>				45	68

As Directed by Engineer

27

TOTAL 1,050 TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 10

ITEM CODE: 202.0920 LOAD AND HAUL CONTAMINATED SOIL, TYPE 2

UM: TON

RIVER STREET

Weight

<u>Ref Item 401.0520</u>	248
<u>Ref Item 905.1000</u>	94
<u>Ref Item 401.0520</u>	6
<u>Ref Item 203.0100</u>	68

As Directed by Engineer

9

TOTAL 425 TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 11

ITEM CODE: 202.0921 DISPOSAL OF CONTAMINATED SOIL, TYPE 2

UM: TON

RIVER STREET

Weight

<u>Ref Item 401.0520</u>	248
<u>Ref Item 905.1000</u>	94
<u>Ref Item 401.0520</u>	6
<u>Ref Item 203.0100</u>	68

As Directed by Engineer

9

TOTAL 425 TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 12

ITEM CODE: 202.0930 LOAD AND HAUL CONTAMINATED SOIL, TYPE 3

UM: TON

SINGLETON STREET

Weight

<u>Ref Item 401.0520</u>	445
<u>Ref Item 905.1000</u>	70
<u>Ref Item 401.0520</u>	2
<u>Ref Item 203.0100</u>	90

As Directed by Engineer

13

TOTAL 620 TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project: Singleton & River St. Reconstruction, Bridge Group 26C
RICN 2025-CB-057
PTS ID 2607E
OSP ID TCB26005787
Office ID 41110.06

Estimator	Date
JSC	9/24/2025
Rev.	Date
Sheet	13

DISTRIBUTION OF QUANTITIES

ITEM CODE: 202.0931 DISPOSAL OF CONTAMINATED SOIL, TYPE 3

UM: TON

SINGLETON STREET

Weight

<u>Ref Item 401.0520</u>	445
<u>Ref Item 905.1000</u>	70
<u>Ref Item 401.0520</u>	2
<u>Ref Item 203.0100</u>	90

As Directed by Engineer

13

TOTAL 620 TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project: Singleton & River St. Reconstruction, Bridge Group 26C
RICN 2025-CB-057
PTS ID 2607E
OSP ID TCB26005787
Office ID 41110.06

Estimator	Date
JSC	9/24/2025
Rev.	Date

DISTRIBUTION OF QUANTITIES

Sheet 14

ITEM CODE: 202.0960 LOAD, HAUL, AND DISPOSE OF OTHER WASTE

UM: TON

PROJECT WIDE

As Directed by Engineer

5

TOTAL

5

TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge (	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 15

ITEM CODE: 203.0100 STRUCTURE EXCAVATION EARTH

		UM:	CY
<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>	
	Bridge 095501	60	
	Bridge 095601	45	

As Directed by Engineer 5

TOTAL 110 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 16

ITEM CODE: 206.0301 COMPOST FILTER SOCK

UM: LF

<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>
	Singleton St. Bridge	380
	River St. Bridge	590

As Directed by Engineer

30

TOTAL 1,000 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 17

ITEM CODE: 209.0220 SACK INSERT INLET PROTECTION

UM: EA

<u>PROJECT WIDE</u>	<u>Location</u>	<u>STA</u>	<u>TOTAL</u>
	Singleton St	205+00 Lt	1
	River St.	304+95 Lt	1
		304+95 Rt	1

As Directed by Engineer

0

TOTAL 3 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 18

ITEM CODE: 212.2200 MAINTENANCE AND CLEANING OF EROSION, SEDIMENT, AND
POLLUTION PREVENTION CONTROLS UM: LS

PROJECT WIDE

TOTAL

1

TOTAL 1 LS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 19

ITEM CODE: 213.0100 PLACEMENT OF MILLINGS BENEATH GUARDRAIL

		UM:	LF
PROJECT WIDE	Sta	=	Say
Singleton St	201+00 Lt	75	75
	201+00 Rt	110	110
	203+60 Lt	30	30
	203+60 Rt	30	30
	203+75 Lt	50	50
River St.	301+75 Lt	60	60
	301+20 Rt	80	80
	304+50 Lt	50	50

As Directed by Engineer

15

TOTAL 500 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 20

ITEM CODE: 302.0100 GRAVEL BORROW SUBBASE COURSE

UM: CY

PROJECT WIDE

	<u>Depth</u>	<u>SF</u>	<u>CF</u>	<u>CY</u>	Roundup <u>CY</u>
<u>Ref Item 401.0520 -Rdwy</u>	12 inches	12,456	12456	461.33	462
<u>Ref Item 905.1000</u>	8" inches	4,392	2942.64	108.99	109
<u>Ref Item 401.0520 -BCD</u>	8" inches	174	116.58	4.32	5

As Directed by Engineer

24

TOTAL 600 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project: Singleton & River St. Reconstruction, Bridge Group 26C
RICN 2025-CB-057
PTS ID 2607E
OSP ID TCB26005787
Office ID 41110.06

Estimator	Date
GAF	9/24/2025
Rev.	Date

DISTRIBUTION OF QUANTITIES

Sheet 21

ITEM CODE: 401.0510 HOT MIX ASPHALT PREPARATION - PARTIAL DEPTH

						UM:	SY
							Area
							Total
<u>PROJECT WIDE</u>	<u>Location</u>	<u>Method</u>	<u>Micro-Mill.</u> <u>Depth</u>	<u>SF</u>	<u>SY</u>	Roundup <u>SY</u>	
	River St. - East Appr.	MO - 1	1.5"	1,575	175	180	
	River St. - West Appr.	MO - 1	1.5"	1,440	160	160	
			SF Total	3,015			

As Directed by Engineer

10

TOTAL 350 SY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 22

ITEM CODE: 401.0520 HOT MIX ASPHALT PREPARATION - FULL DEPTH

UM: SY

PROJECT WIDE

Location		Length	Width	SF	SY
Singleton St.	East Appr.	75	32	2,400	270
	East Appr.	25	32	800	90
	West Appr.	143	32	4,576	510
	West Appr.	15	15	225	30
River St.	East Appr.	20	35	700	80
	CB's	16	5	80	10
	West Appr.	105	35	3,675	410

Rdwy Total 12,456 1400

STA			Length	Width	SF	SY
203+90 Lt	Singleton St.	BCD	15	2	30	4
301+00 Lt	River St.	BCD	25	2	50	6
304+68 Lt	River St.	BCD	22	2	44	5
304+68 Lt	River St.	BCD	25	2	50	6

BCD Total 174 21

As Directed By the Engineer

54

TOTAL 1,475 SY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 23

ITEM CODE: 401.1000 CLASS 19.0 HMA

UM: TON

5.5 " Depth

PROJECT WIDE

SY

TOTAL

Ref Item No. 410.0520

1,475

486

As Directed by Engineer

39

TOTAL

525

TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project: Singleton & River St. Reconstruction, Bridge Group 26C
RICN 2025-CB-057
PTS ID 2607E
OSP ID TCB26005787
Office ID 41110.06

Estimator	Date
GAF	9/24/2025
Rev.	Date
Sheet	24

DISTRIBUTION OF QUANTITIES

ITEM CODE: 401.3005 CLASS 9.5 HMA FOR MISCELLANEOUS WORK

Curb Installation, Utility Trench & Driveways						UM:	TON
						2.0" Factor	
PROJECT WIDE		STA	LF	*Ave. Width*	TYPE	Roundup SY	Tons
Singleton St.		203+90 Lt	15	2	BCD	4	1
River St.		301+00 Lt	25	2	BCD	6	1
River St.		304+68 Lt	22	2	BCD	5	1
River St.		304+68 Lt	25	2	BCD	6	1
			LF	*Ave. Width*			
Ref Item No. 906.0310			520	1	Curb	58	8
Ref Item No. 906.0700			275	1	Curb	31	5
Utility Trench & Patching						5	

As Directed by Engineer

3

TOTAL 25 TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 25

ITEM CODE: 401.3100 MODIFIED CLASS 9.5 HMA

PROJECT WIDE	SY	UM:	TON
		1.5" Factor	
		Tons	
<u>Ref Item 401.0510</u>	350.00	36	
<u>Ref Item 401.0520 - Rdwy</u>	1475.00	149	

As Directed by Engineer

15

TOTAL 200 TON



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 26

ITEM CODE: 603.1000 CONTROLLED LOW STRENGTH MATERIAL

UM: CY

<u>PROJECT WIDE</u>	<u>LOCATION</u>	<u>TOTAL</u>
---------------------	-----------------	--------------

	Bridge 095501	8
--	---------------	---

	Bridge 095601	8
--	---------------	---

As Directed by Engineer

4

TOTAL 20 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 27

ITEM CODE: 701.0300 REINFORCED CONCRETE PIPE M 170 - ALL SIZES

UM: LF

<u>PROJECT WIDE</u>	<u>LOCATION</u>	<u>PIPE SIZE</u>	<u>TOTAL</u>
	Singleton St.	12"	30
	River St.	18"	30

As Directed by Engineer

0

TOTAL 60 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 28

ITEM CODE: 701.5402 DUCTILE IRON WATER PIPE, MECHANICAL JOINT - ALL SIZES

UM: LF

<u>PROJECT WIDE</u>	<u>LOCATION</u>	<u>PIPE SIZE</u>	<u>TOTAL</u>
---------------------	-----------------	------------------	--------------

	Bridge 095501		50
--	---------------	--	----

	Bridge 095601		50
--	---------------	--	----

As Directed by Engineer

0

TOTAL 100 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 29

ITEM CODE: 701.8003 PIPE BEDDING CLASS C

UM: CY

PROJECT WIDE

<u>LOCATION</u>		<u>Width</u>	<u>Length</u>	<u>Depth</u>	<u>TOTAL</u>
Singleton St.	12" Drain	5	30	2.5	14.00
River St.	18" Drain	5.5	30	3	19.00

As Directed by Engineer

7

TOTAL 40 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 30

ITEM CODE: 702.0501 FRAME AND GRATE - ALL SIZES AND TYPES

		UM: EA			
		RI STD. #	RI STD. #	RI STD. #	RI STD. #
PROJECT WIDE	Loc.	6.3.2			TOTAL
	Singleton St.	1			1
	River St.	2			2

As Directed by Engineer

1

TOTAL

4

EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 31

ITEM CODE: 702.0502 FRAME AND COVER - ALL SIZES AND TYPES

	UM:	EA
<u>PROJECT WIDE</u>	<u>RI STD. #</u>	<u>RI STD. #</u>
	6.2.1	
Singleton St.	1	1

As Directed by Engineer

1

TOTAL 2 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 32

ITEM CODE: 702.0529 INLET STONE - ALL SIZES AND TYPES

						UM:	EA
PROJECT WIDE	Location	RI STD. #	RI STD. #	RI STD. #	RI STD. #	TOTAL	
		7.1.5	7.1.6	7.3.5	7.3.6		
	River St.				2	2	

As Directed by Engineer

0

TOTAL 2 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 33

ITEM CODE: 702.0545 APRON STONE – ALL TYPES AND SIZES

						UM:	EA
<u>PROJECT WIDE</u>	<u>Loc.</u>	<u>RI STD. #</u> <u>7.1.7</u>	<u>RI STD. #</u> <u>7.1.8</u>	<u>RI STD. #</u> <u>7.3.7</u>	<u>RI STD. #</u> <u>7.3.8</u>	<u>TOTAL</u>	
	Singleton St.				1	1	

As Directed by Engineer

0

TOTAL 1 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 34

ITEM CODE: 702.1000 MANHOLE, CATCH BASIN, OR DROP INLET ASSEMBLY -
(0' - 12' DEPTH)

UM: EA

<u>PROJECT WIDE</u>	<u>RI STD. #</u>	<u>RI STD. #</u>	<u>RI STD. #</u>	<u>RI STD. #</u>	<u>TOTAL</u>
<u>Location</u>	<u>4.4.0</u>				
Singleton St.	1				1

As Directed by Engineer

0

TOTAL 1 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 35

ITEM CODE: 704.0500 RECONSTRUCT DRAINAGE STRUCTURE

UM: EA

PROJECT WIDE Location

TOTAL

Singleton St.

1

River St

2

As Directed by Engineer

0

TOTAL 3 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 36

ITEM CODE: 707.0100 ADJUST DRAINAGE OR UTILITY STRUCTURE TO GRADE

UM: EA

PROJECT WIDE

(Roadway & Sidewalk)

TOTAL

<u>Location</u>	<u>SMH</u>	<u>DMH</u>	<u>F & G</u>	<u>EMH</u>	<u>TMH</u>	<u>H.H</u>	
Singleton St.	2	1	0	0	0	0	3
River St.	1	1	2	0	0	0	4

As Directed by Engineer

1

TOTAL 8 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 37

ITEM CODE: 708.9040 CLEANING AND FLUSHING PIPE ALL SIZES

UM: LF

<u>PROJECT WIDE</u>	<u>Location</u>	<u>LF</u>
	Singleton St.	100
	River St.	70

As Directed by Engineer 30

TOTAL 200 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 38

ITEM CODE: 708.9044 CLEANING AND FLUSHING VERTICAL STRUCTURE

UM: EA

<u>PROJECT WIDE</u>	<u>Location</u>	<u>CB/DI</u>	<u>DMH</u>	<u>TOTAL</u>
	Singleton St.	1	2	3
	River St.	2	1	3

As Directed by Engineer

1

TOTAL 7 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 39

ITEM CODE: 709.0400 CONCRETE FOR THRUST BLOCKS, HEADWALLS AND
MISC PURPOSES

UM: CY

PROJECT WIDE Concrete Swale at Bridge 095601 - East Abutment **TOTAL**

6' x 1' x 18' / 27 = 4.0 CY Say 5

As Directed by Engineer 0

TOTAL 5 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 40

ITEM CODE: 712.0300 GATE BOX - ALL TYPES

UM: EA

PROJECT WIDE

TOTAL

As Directed by Engineer

1

TOTAL 1 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 41

ITEM CODE: 713.0100 ADJUST CURB STOP OR UTILITY BOX TO GRADE

UM: EA

PROJECT WIDE (Roadway & Sidewalk)

<u>Location</u>	<u>CS</u>	<u>WG</u>	<u>GG</u>	<u>TOTAL</u>
Singleton St.		3	3	6
River St.		0	0	0

As Directed by Engineer

1

TOTAL 7 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 42

ITEM CODE: 803.0350 REMOVAL AND DISPOSAL OF EXISTING CONCRETE MASONRY

		UM:	CY
<u>PROJECT WIDE</u>	<u>Location</u>		<u>CY</u>
	Bridge 095501		326
	Bridge 095601		363

As Directed by Engineer

36

TOTAL 725 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 43

ITEM CODE: 803.0500 TEMPORARY DECK UNDERSIDE AND SIDE PROTECTIVE SHIELDING

UM: SF

PROJECT WIDE

Location

SF

TOTAL

Bridge 095501

10380

10380

Bridge 095601

11838

11838

As Directed by Engineer

782

TOTAL 23000 SF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 44

ITEM CODE: 808.0322 CONCRETE SUBSTRUCTURE CLASS HP 3/4" END POSTS

UM: CY

PROJECT WIDE

Location

TOTAL

Bridge 095501

52

Bridge 095601

20

As Directed by Engineer

3

TOTAL 75 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 45

ITEM CODE: 808.0602 CONCRETE SUBSTRUCTURE CLASS XX 3/4" BACKWALLS

UM: CY

PROJECT WIDE

Location

TOTAL

Bridge 095501

4

Bridge 095601

4

As Directed by Engineer

2

TOTAL 10 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 46

ITEM CODE: 808.9901 LIGHTWEIGHT CONCRETE SUPERSTRUCTURE
CLASS HP 3/4" BRIDGE DECKS

UM: CY

PROJECT WIDE

Location

TOTAL

Bridge 095501

253

Bridge 095601

294

As Directed by Engineer

13

TOTAL 560 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 47

ITEM CODE: 808.9902 LIGHTWEIGHT CONCRETE SUPERSTRUCTURE
CLASS HP 3/4" BRIDGE SIDEWALKS

UM: CY

PROJECT WIDE

Location

TOTAL

Bridge 095501

54

Bridge 095601

89

As Directed by Engineer

7

TOTAL 150 CY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 48

ITEM CODE: 808.9903 EXPOSED AGGREGATE SURFACE TREATMENT

			UM:	SF
<u>PROJECT WIDE</u>	<u>Location</u>	<u>SF</u>		<u>TOTAL</u>
	Bridge 095501 - Singleton St.	2100	say	2,250
	Bridge 095601 - River St	3255	say	3,500
	Ref Item 905.1000	4,392	say	5,000

As Directed by Engineer

0

TOTAL 10,750 SF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	49

DISTRIBUTION OF QUANTITIES

ITEM CODE: 810.0210 GALVANIZED BAR REINFORCEMENT GRADE 60

UM: LBS

<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>
	Bridge 095501	72,600
	Bridge 095601	81,400

As Directed by Engineer 6000

TOTAL 160,000 LBS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	50

DISTRIBUTION OF QUANTITIES

ITEM CODE: 810.0702 WELDED WIRE FABRIC (GALVANIZED)

		UM:	SF
PROJECT WIDE	Location	TOTAL	
	Concrete Swale at Bridge 095601 - East Abutment		
	6' X 18' = 108 SF	SAY	125
	Bridge 095501		666
	Bridge 095601		446

As Directed by Engineer 63

TOTAL 1,300 SF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 51

ITEM CODE: 817.2142 REPAIRS TO STRUCTURE CONCRETE MASONRY -
FORM AND CAST IN PLACE CONCRETE

UM: CF

<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>
	Bridge 095501	222
	Bridge 095601	149

As Directed by Engineer

104

TOTAL 475 CF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 52

ITEM CODE: 819.0800 DRILL AND GROUT REINFORCING DOWELS

UM: EACH

PROJECT WIDE

Location

TOTAL

Bridge 095501

53

Bridge 095601

63

As Directed by Engineer

9

TOTAL 125 EACH



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 53

ITEM CODE: 820.0100 CONCRETE SURFACE TREATMENT PROTECTIVE SEALER

UM: SF

PROJECT WIDE

Location

TOTAL

Bridge 095501 - REPAIR AREAS
Bridge 095501 - DECK

1274
7200

Bridge 095601 - REPAIR AREAS
Bridge 095601 - DECK

686
7400

As Directed by Engineer

40

TOTAL 16600 SF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 54

ITEM CODE: 823.9901 PREFORMED JOINT SEAL

UM: LF

PROJECT WIDE

Location

TOTAL

Bridge 095501

55

Bridge 095601

64

As Directed by Engineer

1

TOTAL 120 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 55

ITEM CODE: 824.2000 STRUCTURAL STEEL

UM: LBS

PROJECT WIDE

Location

TOTAL

Bridge 095501

4,329

Bridge 095601

4,393

As Directed by Engineer

278

TOTAL 9000 LBS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 56

ITEM CODE: 824.2200 WELDED STUD SHEAR CONNECTORS

UM: EACH

PROJECT WIDE

Location

TOTAL

Bridge 095501

2735

Bridge 095601

3345

As Directed by Engineer

170

TOTAL 6250 EACH



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 57

ITEM CODE: 824.9901 STRUCTURAL STEEL REPAIRS

		UM:	LBS
<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>	
	Bridge 095501	19,034	
	Bridge 095601	71,874	

As Directed by Engineer

24092

TOTAL 115000 LBS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 58

ITEM CODE: 824.9902 RIVET REPLACEMENT

UM: EACH

PROJECT WIDE

Location

TOTAL

Bridge 095501

500

Bridge 095601

500

TOTAL 1000 EACH



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 59

ITEM CODE: 825.8040 PAINTING EXISTING STRUCTURAL STEEL

		UM:	SF
<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>	
	Bridge 095501	37,104	
	Bridge 095601	42,219	

As Directed by Engineer

2177

TOTAL 81500 SF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 60

ITEM CODE: 825.8050 SURFACE PREPARATION FOR EXISTING STEEL

		UM:	SF
<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>	
	Bridge 095501	39,031	
	Bridge 095601	44,579	

As Directed by Engineer

2390

TOTAL 86000 SF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 61

ITEM CODE: 827.8038 THERMAL SPRAYED ZINC COATING STRUCTURAL STEEL

UM: SF

PROJECT WIDE

Location

TOTAL

Bridge 095501

39,031

Bridge 095601

44,579

As Directed by Engineer

2390

TOTAL 86000 SF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 62

ITEM CODE: 830.1000 METAL BRIDGE RAILING

UM: LF

PROJECT WIDE

Location

TOTAL

Bridge 095501

418

Bridge 095601

420

As Directed by Engineer

12

TOTAL 850 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 63

ITEM CODE: 834.0100 GRANITE CURB FOR BRIDGES

		UM:	LF
<u>PROJECT WIDE</u>	<u>Location</u>	<u>TOTAL</u>	
	Bridge 095501	418	
	Bridge 095601	420	

As Directed by Engineer

12

TOTAL 850 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 64

ITEM CODE: 836.0100 STRUCTURAL CONCRETE CRACK REPAIR BY EPOXY-RESIN
BASE ADHESIVE INJECTION

UM: LF

PROJECT WIDE

Location

TOTAL

Bridge 095501

11

Bridge 095601

50

As Directed by Engineer

14

TOTAL 75 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 65

ITEM CODE: 841.0100 PRE AND POST CONSTRUCTION
CONDITION SURVEYS

UM: LS

PROJECT WIDE

As Directed by Engineer

1

TOTAL 1 LS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 66

ITEM CODE: 901.1000 STEEL BEAM GUARDRAIL

Subtract UM: LF

PROJECT WIDE

	<u>Sta.</u>	=	<u>End Treat.</u> <u>Lengths</u>	<u>Say</u>
Singleton St.	201+00 Lt	75	10	65
	201+00 Rt	110	50	60
	203+60 Lt	30		30
	203+60 Rt	30		30
	203+75 Lt	50	50	0
River St.	301+75 Lt	60	10	50
	301+20 Rt	80	50	30
	304+50 Lt	50		50

As Directed by Engineer

35

TOTAL 350 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 67

ITEM CODE: 901.1050 GUARDRAIL CONNECTION TO END POST
(Bridge Parapet, Exist Guardrail or Barrier)
UM: EA

<u>PROJECT WIDE</u>	<u>Locations</u>	<u>TOTAL</u>
	Singleton St. Bridge	4
	River St. Bridge	3

As Directed by Engineer

0

TOTAL 7 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 68

ITEM CODE: 901.1100 STEEL BEAM GUARDRAIL APPROACH END TREATMENT
RI Std.34.3.0

UM: EA

50' estimated Length

PROJECT WIDE

Location

TOTAL

Singleton St.	200+50 Rt	1
	203+75 Lt	1
River St.	301+75 Rt	1

As Directed by Engineer

0

TOTAL 3 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 69

ITEM CODE: 901.1200 GUARDRAIL END TREATMENT PLATFORM

UM: EA

PROJECT WIDE

Location

TOTAL

Ref Item No. 901.1100

3

As Directed by Engineer

0

TOTAL 3 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 70

ITEM CODE: 901.1300 STEEL BEAM GUARDRAIL ANCHORAGE TRAILING END SECTIONS
RI Std.34.3.2

UM: EA

10' estimated Length

PROJECT WIDE

Location

TOTAL

Singleton St 200+75 Lt

1

River St. 301+75 Rt

1

As Directed by Engineer

0

TOTAL 2 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	71

DISTRIBUTION OF QUANTITIES

ITEM CODE: 903.0510 FENCE - PERMANENT ALL TYPES AND SIZES

			UM:	LF
<u>PROJECT WIDE</u>	<u>Location</u>	<u>Type</u>	<u>TOTAL</u>	

	Singleton St.	CLF	40	
--	---------------	-----	----	--

As Directed by Engineer

10

TOTAL 50 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 72

ITEM CODE: 904.0100 REMOVE AND RESET FENCE AND/OR RAILING

UM: LF

PROJECT WIDE

Location

TOTAL

As Directed by Engineer

100

TOTAL 100 LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 73

ITEM CODE: 905.1000 PORTLAND CEMENT CONCRETE SIDEWALKS AND DRIVEWAYS

Includes WCR Areas

UM: SY

PROJECT WIDE

* Average

VALUES ROUNDED UP


Location	STA	Type	Length	Width*	SF	SY
Singleton St.	203+60 Rt	WCR	26	6	156	20
	203+75 Lt	WCR	45	6	270	30
	200+25 Rt	SW	20	6	120	20
	200+25 Rt	WCR	27	6	162	20
	200+50 Rt	SW	16	6	96	20
	201+00 Lt	SW	121	6	726	90
	200+25 Lt	WCR	27	6	162	20
	200+25 Lt	SW	12	6	72	10
River St.	204+25 Rt	WCR	20	6	120	20
	304+50 Lt	SW	30	6	180	20
	304+75 Lt	CDW	25	6	150	20
	305+00 Lt	SW	20	6	120	20
	305+00 Rt	SW	15	6	90	10
	304+75 Rt	CDW	25	6	150	20
	304+50 Rt	SW	18	6	108	20
	301+50 Rt	SW	160	6	960	110
	301+50 Lt	SW	100	6	600	70
	301+00 Lt	CDW	25	6	150	20

SF Total= 4,392

As Directed by Engineer

15

TOTAL 575 SY



Estimator	Date
GAF	9/24/2025
Rev.	Date
Sheet	74

Sheet 74

UM: LF

353

16

TOTAL	520	LF
-------	-----	----



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 75

ITEM CODE: 906.0700 REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT,
CIRCULAR ALL TYPES

UM: LF

PROJECT WIDE

Location

TOTAL

Singleton St.	East Appr.	25
	West Appr.	235

As Directed by Engineer

15

TOTAL

275

LF



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	RC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 76

ITEM CODE: 919.0101 TEST PITS

UM: EACH

PROJECT WIDE

TOTAL

As Directed by Engineer

5

TOTAL 5 EACH



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	77

DISTRIBUTION OF QUANTITIES

ITEM CODE: 920.0320 RIPRAP R-3, R-4, R-5 STANDARD 8.3.0

UM: SY

PROJECT WIDE

	<u>SF</u>	<u>SY</u>
Bridge 095501		
W. Abut.	2162	241
E. Abut.	1210	135
Bridge 095601		
W. Abut.	2397	267
E. Abut.	2066	230

As Directed by Engineer

127

TOTAL 1,000 SY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	78

DISTRIBUTION OF QUANTITIES

ITEM CODE: 929.0110 FIELD OFFICE

UM: PMO

TOTAL

PROJECT WIDE

42

TOTAL 42 PMO



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	RC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 79

ITEM CODE: 936.0110 MOBILIZATION

UM: LS

PROJECT WIDE

TOTAL

1

TOTAL 1 LS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	JSC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 80

ITEM CODE: 937.0100 FURNISH, INSTALL, MAINTAIN, AND MOVE TEMPORARY
TRAFFIC PROTECTION

UM: LS

PROJECT WIDE

TOTAL

Duration:

1

TOTAL 1 LS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
DISTRIBUTION OF QUANTITIES			
		Sheet	81

ITEM CODE: 943.0300 TRAINEE HOURS

UM: HR

PROJECT WIDE

2000

Note: As per RIDOT

TOTAL 2000 HR



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	RC	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 82

ITEM CODE: 999.9901 MISCELLANEOUS WORK

UM: EA

PROJECT WIDE

TOTAL

As Directed by Engineer

75,000

TOTAL 75,000 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 83

ITEM CODE: L01.0102 LOAM BORROW 4 INCHES DEEP

UM: SY

PROJECT WIDE

Location

Ave.
Length (Ft) Width (Ft.)

SF

SY

Roundup
SY

Singleton St	West Appr.	300	2	600	66.67	67
	East Appr.	60	2	120	13.33	14
River St.	West Appr.	160	2	320	35.56	36

As Directed by Engineer

8

TOTAL 125 SY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	84

DISTRIBUTION OF QUANTITIES

ITEM CODE: L02.0107 SEEDING

UM: SY

PROJECT WIDE

TOTAL

Ref Item L01.0102 LOAM BORROW

125

TOTAL 125 SY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	CO	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	85

DISTRIBUTION OF QUANTITIES

ITEM CODE: L06.9901 ARONIA MELONCARPA - BLACK CHOKEBERRY

UM: EA

PROJECT WIDE

River Street Bridge No 095601 5

TOTAL 5 EACH



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	CO	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	86

DISTRIBUTION OF QUANTITIES

ITEM CODE: L06.9902 PRUNUS VIRGINIANA - CHOKE CHERRY

UM: EA

PROJECT WIDE

River Street Bridge No 095601

4

TOTAL 4 EACH



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	CO	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	87

DISTRIBUTION OF QUANTITIES

ITEM CODE: L06.9903 RHUS TYPHINA - STAGHORN SUMAC

UM: EA

PROJECT WIDE

River Street Bridge No 095601

3

TOTAL 3 EACH



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	CO	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	88

DISTRIBUTION OF QUANTITIES

ITEM CODE: L06.9904 NEW ENGLAND CONSERVATION - WILDLIFE SEED MIX

UM: SY

PROJECT WIDE

River Street Bridge No 095601

100

TOTAL 100 SY



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project: Singleton & River St. Reconstruction, Bridge Group 26C
RICN 2025-CB-057
PTS ID 2607E
OSP ID TCB26005787
Office ID 41110.06

Estimator	Date
KM	9/24/2025
Rev.	Date
Sheet	89

DISTRIBUTION OF QUANTITIES

ITEM CODE: T15.0100 DIRECTIONAL REGULATORY AND WARNING SIGNS

PROJECT WIDE

UM: SF

Sign #	NAME	SIZE	AREA	#of signs	TOTAL
1-1	W8-6(mod)	30 X 30	6.25	1	6.25
2-1	R1-1	30 x 30	6.25	1	6.25
2-2	R4-11	30 x 30	6.25	1	6.25
2-3	W11-15	30 x 30	6.25	1	6.25
2-4	W16-9p	24 x 12	2	1	2
2-5	D11-1	24 x 18	3	1	3
2-6	W11-15	30 x 30	6.25	1	6.25
2-7	W16-7p	24 x 12	2	1	2
2-8	R1-1	18 x 18	2.25	1	2.25
2-9	R5-3	24 x 24	4	1	4
2-10	R1-1	30 x 30	6.25	1	6.25
2-11	R9-1(mod)	18 x 24	3	1	3
2-12	D11-1	24 x 18	3	1	3
2-13	W11-15	30 x 30	6.25	1	6.25
2-14	W16-7p	24 x 12	2	1	2
2-15	R1-1	30 X 30	6.25	1	6.25
2-16	W11-15	30 x 30	6.25	1	6.25
2-17	W16-9p	24 x 12	2	1	2
				Total = 18 EA	0
				X	0
				X	0
				As Directed by Engineer	5.5
TOTAL=					85.0000



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	GAF	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	90

DISTRIBUTION OF QUANTITIES

ITEM CODE: T15.0200 REMOVAL AND RELOCATE DIRECTIONAL REGULATORY

AND WARNING SIGN

UM: EA

PROJECT WIDE

TOTAL

As Directed by Engineer

2

TOTAL 2 EA



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	KM	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		
		Sheet	91

DISTRIBUTION OF QUANTITIES

ITEM CODE: T20.0101 PAVEMENT MARKINGS

*Ave

UM:

LF

PROJECT WIDE

<u>Location</u>	<u>Sta.</u>	<u>Sta.</u>	<u>Type</u>				<u>TOTAL</u>
Singleton Street	200+00	203+50	4DY	350	2	700	700
	200+20		Xwalk	120	1	120	120
	203+70		Xwalk	140	1	140	140
	200+30		Stop Bar	30	1	30	30
	203+80	RT	Stop Bar	15	1	15	15
	203+80	RT	4DY	15	2	30	30
	203+80	LT	Stop Bar	10	1	10	10
	203+80	LT	4Y	10	1	10	10
River Street	301+00	305+00	4DY	400	2	800	800

As Directed by the Engineer

145

TOTAL= 2,000



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project:	Singleton & River St. Reconstruction, Bridge Group 26C	Estimator	Date
RICN	2025-CB-057	KM	9/24/2025
PTS ID	2607E	Rev.	Date
OSP ID	TCB26005787		
Office ID	41110.06		

DISTRIBUTION OF QUANTITIES

Sheet 92

ITEM CODE: T20.0102 TEMPORARY PAVEMENT MARKINGS

UM: LS

PROJECT WIDE

TOTAL

1

From Item T20.0101

Assume 2 layers

Includes grinding, sweeping, removed temporary pavement markings

TOTAL 1 LS



200 Main Street
Pawtucket, RI 02860
Tel. 401.726.4084
Fax: 401.728.1533

Project: Singleton & River St. Reconstruction, Bridge Group 26C
RICN 2025-CB-057
PTS ID 2607E
OSP ID TCB26005787
Office ID 41110.06

Estimator	Date
KM	9/24/2025
Rev.	Date
Sheet	93

DISTRIBUTION OF QUANTITIES

ITEM CODE: T20.0103 ARROWS, WORDS, OR SYMBOLS PAVEMENT MARKINGS

		UM:			EA
PROJECT WIDE	SHEET #	20.1.0	20.1.0	Bike	TOTAL
		ARROWS	WORDS	Symbol	
	Singleton Street			4	4

As Directed by the Engineer

1

TOTAL 5 EA