

**ITEM 850.01****TRAFFIC CONTROLS FOR CONSTRUCTION  
AND MAINTENANCE OPERATIONS****LUMP SUM**

The work to be done under this Item shall conform to the relevant provisions of Subsection 850 and the following:

Work under this Section consists of furnishing, installing and maintaining in proper operating condition various traffic control devices for the protection of the traveling public and working personnel during construction and maintenance operations. The installation of all devices shall conform to the Construction Standard Details, the MUTCD, and/or as directed.

The Contractor shall be responsible for the installation of adequate safety precautions for the protection of the traveling public and all project personnel.

All construction vehicles not protected by any form of traffic control device on a project which is open to traffic shall have an amber flashing light mounted on the cab roof or on the highest practical point of the machinery. The light shall be in operation whenever the equipment is working on the highway or travelway. Amber flashers must be a minimum of 40 cd and have a flashing frequency of 50 to 60 times per minute. Either rotating beacons or strobe lights meeting these requirements are acceptable.

All materials provided by the Contractor under the items of this section shall remain the property of the Contractor upon completion of the project.

All work under this Section shall conform to the approved Traffic Management Plan.

**BASIS OF PAYMENT**

Payment for the Traffic Controls for Construction and Maintenance Operations shall constitute full payment for all material, labor and equipment required or incidental to the satisfactory completion of the work as described above. Any devices provided under this section which are lost, stolen, destroyed or deemed unacceptable while their use is required on the project shall be replaced without additional compensation. Devices damaged by traffic will be compensated in accordance with Subsection 7.17: Traffic Accommodation including temporary impact attenuators. This shall not include other temporary traffic control devices, such as cones, drums and temporary signs.