

MASSACHUSETTS WATER RESOURCES AUTHORITY
DEER ISLAND - 33 TAFTS AVENUE
BOSTON, MASSACHUSETTS 02128

NEEDHAM DEWATERING DRAINAGE LINE

CONTRACT NO. 8086

ADDENDUM NO. 1

TO ALL CONTRACTORS ESTIMATING:

Bidders are hereby informed that plans and specifications for the above-mentioned contract are modified, corrected and/or supplemented as follows and that Addendum No. 1 becomes part of the Contract Documents and consists of Items 1-1 through 1-13.

ITEM 1-1: SPECIFICATIONS TABLE OF CONTENTS

After “02240 – CONSTRUCTION DEWATERING AND GROUNDWATER CONTROL”, **ADD** “02310 – ROCK AND BOULDER EXCAVATION”.

ITEM 1-2: SECTION 01025 – MEASUREMENT AND PAYMENT

DELETE Section 01025 – Measurement and Payment and **REPLACE** in its entirety with Section 01025 – Measurement and Payment, attached hereto as Attachment A, Addendum No. 1, Item 1-2 (consisting of four pages).

ITEM 1-3: SECTION 02200 – EARTHWORK

Paragraph 1.2

After Paragraph 1.2-D. “Section 02240 – Construction Dewatering and Groundwater Control”, **ADD** Paragraph 1.2-E. “Section 02310 – Rock and Boulder Excavation”. Renumerate the following Paragraphs 1.2-F. through 1.2-K.

ITEM 1-4: SECTION 02200 – EARTHWORK

Paragraph 1.9-J.

DELETE “Obstruction is defined as intact bedrock.”

ITEM 1-5: SECTION 02200 – EARTHWORK

Paragraph 3.4-J.

DELETE Paragraph 3.4-J. in its entirety and **REPLACE** with the following:

“J. Rock excavation shall be in accordance with Section 02310 – Rock and Boulder Excavation.”

ITEM 1-6: SECTION 02200 – EARTHWORK

Paragraph 3.4-L.

DELETE Paragraph 3.4-L. in its entirety and **REPLACE** with the following:

“L. (Not used).”

ITEM 1-7: SECTION 02226 – EXCAVATED MATERIAL HANDLING AND DISPOSAL

Paragraph 3.03

DELETE Paragraph 3.03-A. in its entirety and **REPLACE** with the following:

“A. Soils were identified in the field program as summarized in the Environmental Site Testing Data as appended to Specifications Volume 2 Appendix A. The work includes management, handling, stockpiling, sampling and testing of all excavated materials which Contractor is to include in its lump sum price in Item No. 1. The work for disposal of excavated soils that cannot be reused and the transportation of such materials to disposal sites shall be paid for under Item No. 4 Excess Soil Disposal Allowance.”

ITEM 1-8: SECTION 02226 – EXCAVATED MATERIAL HANDLING AND DISPOSAL

Paragraph 3.03

DELETE Paragraph 3.03-B., Paragraph 3.03-C., and Paragraph 3.03-D. in their entirety and **REPLACE** with the following:

“B. Excavated material from beyond the project limits indicated on the plans shall be disposed of at no additional cost to the Authority.”

ITEM 1-9: SECTION 02310 – ROCK AND BOULDER EXCAVATION

ADD Section 02310 – Rock and Boulder Excavation, attached hereto as Attachment B, Addendum No. 1, Item 1-9 (consisting of five pages).

ITEM 1-10: CONTRACT DRAWING G-003

Contract Drawing G-003, Utility and General Notes, Note 17

DELETE Note 17 in its entirety.

ITEM 1-11: CONTRACT DRAWING C-101

DELETE Drawing C-101 and **REPLACE** with Drawing C-101, attached hereto as Attachment C, Addendum No. 1, Item 1-11.

ITEM 1-12: CONTRACT DRAWING C-102

Contract Drawing C-102, Profile

DELETE the 9'-2" dimension annotation. **DELETE** the 10'-5" dimension annotation.

ITEM 1-13: CONTRACT DRAWING C-103

Contract Drawing C-103 approximate STA 4+00

DELETE the callout "SUPPORT AND PROTECT 48" RCP DRAIN. PROVIDE PROVISIONS FOR SEALING LEAKING JOINTS." and **REPLACE** with "SUPPORT AND PROTECT 48" RCP DRAIN. FURNISH AND INSTALL FIVE GROUT BANDS SIZED FOR 48" RCP AND PORTLAND CEMENT GROUT AS PROVISIONS TO SEAL JOINTS IF FOUND TO BE LEAKING AFTER EXPOSURE DURING THE WORK."

MASSACHUSETTS WATER RESOURCES AUTHORITY

Douglas J. Rice
Director of Procurement
Date: October 20, 2026