m Addendum No. 4, November 4, 2026

Project # 609204	Contract # 136695			
Location : BELMONT				
Description : Community Path, Belmont Component of the MCRT (Phase I)				
ITEM #	**QUANTITY**	**ITEM WITH UNIT BID PRICE WRITTEN IN WORDS**	**UNIT PRICE**	**AMOUNT**
804.65	50	JACKING 6 INCH PIPE AT _____ PER FOOT		
m 806.1	100	1 INCH ELECTRICAL CONDUIT TYPE RM - GALVANIZED STEEL AT _____ PER FOOT		
811.112	3	ELECTRIC MANHOLE 6 FT X 13 FT AT _____ EACH		
811.22	20	ELECTRIC HANDHOLE - SD2.022 AT _____ EACH		
812.09	13	LIGHT STANDARD FOUNDATION PRECAST AT _____ EACH		
812.20	1	LIGHTING LOAD CENTER FOUNDATION AT _____ EACH		
813.30	110	WIRE TYPE 7 NO. 10 GENERAL PURPOSE AT _____ PER FOOT		
m 813.31	2,000	WIRE TYPE 7 NO. 8 GENERAL PURPOSE AT _____ PER FOOT		
813.32	150	WIRE TYPE 7 NO. 6 GENERAL PURPOSE AT _____ PER FOOT		

m Item 813.35 has been deleted.

Project # 609204	Contract # 136695			
Location : BELMONT				
Description : Community Path, Belmont Component of the MCRT (Phase I)				
ITEM #	**QUANTITY**	**ITEM WITH UNIT BID PRICE WRITTEN IN WORDS**	**UNIT PRICE**	**AMOUNT**
813.80	1	SERVICE CONNECTION (OVERHEAD) AT _____ EACH		
821.14	13	HIGHWAY LIGHTING POLE (ANCHOR BASE) 12 FOOT BRACKET AT _____ EACH		
823.101	13	HIGHWAY LIGHTING LUMINAIRE - GARDCO PPT SCONES LED AT _____ EACH		
823.311	4	UNDERPASS LIGHTING LUMINAIRE 6 FOOT LED AT _____ EACH		
823.60	1	HIGHWAY LIGHTING LOAD CENTER AT _____ LUMP SUM		
823.70	1	HIGHWAY LIGHTING POLE AND LUMINAIRE REMOVED AND RESET AT _____ EACH		
825.1	1	RECTANGULAR RAPID FLASHING BEACON LOCATION NO. 1 AT _____ LUMP SUM		
832.	153	WARNING-REGULATORY AND ROUTE MARKER - ALUMINUM PANEL (TYPE A) AT _____ PER SQUARE FOOT		
847.1	40	SIGN SUP (N/GUIDE)+RTE MKR W/1 BRKWAY POST ASSEMBLY - STEEL AT _____ EACH		

Project # 609204	Contract # 136695			
Location : BELMONT				
Description : Community Path, Belmont Component of the MCRT (Phase I)				
ITEM #	**QUANTITY**	**ITEM WITH UNIT BID PRICE WRITTEN IN WORDS**	**UNIT PRICE**	**AMOUNT**
852.	510	SAFETY SIGNING FOR TRAFFIC MANAGEMENT AT _____ PER SQUARE FOOT		
853.1	15	PORTABLE BREAKAWAY BARRICADE TYPE III AT _____ EACH		
854.0161	70	PAVEMENT MARKINGS - 6 INCH (PAINTED) BRIDGE AT _____ PER FOOT		
856.060	180	ARROW BOARD (TYPE B) AT _____ PER DAY		
856.12	450	PORTABLE CHANGEABLE MESSAGE SIGN AT _____ PER DAY		
859.	36,000	REFLECTORIZED DRUM AT _____ PER DAY		
859.1	720	REFLECTORIZED DRUMS WITH SEQUENTIAL FLASHING WARNING LIGHTS AT _____ PER DAY		
864.04	60	PAVEMENT ARROWS AND LEGENDS REFLECTORIZED WHITE (THERMOPLASTIC) AT _____ PER SQUARE FOOT		
864.1	230	GREEN FRICTION SURFACE FOR BIKE LANES AT _____ PER SQUARE FOOT		

Project # 609204	Contract # 136695			
Location : BELMONT				
Description : Community Path, Belmont Component of the MCRT (Phase I)				
ITEM #	**QUANTITY**	**ITEM WITH UNIT BID PRICE WRITTEN IN WORDS**	**UNIT PRICE**	**AMOUNT**
866.106	240	6 INCH REFLECTORIZED WHITE LINE (THERMOPLASTIC) AT _____ PER FOOT		
866.112	325	12 INCH REFLECTORIZED WHITE LINE (THERMOPLASTIC) AT _____ PER FOOT		
867.104	1,800	4 INCH REFLECTORIZED YELLOW LINE (THERMOPLASTIC) AT _____ PER FOOT		
867.106	450	6 INCH REFLECTORIZED YELLOW LINE (THERMOPLASTIC) AT _____ PER FOOT		
867.112	55	12 INCH REFLECTORIZED YELLOW LINE (THERMOPLASTIC) AT _____ PER FOOT		
871.22	1	PERMANENT NTCS FOR TRAILS AT _____ EACH		
874.	5	STREET NAME SIGN AT _____ EACH		
874.51	14	WAYFINDING SIGN AT _____ EACH		
874.71	5	MISCELLANEOUS SIGNS REMOVED AND RESET AT _____ EACH		

Project # 609204	Contract # 136695			
Location : BELMONT				
Description : Community Path, Belmont Component of the MCRT (Phase I)				
ITEM #	**QUANTITY**	**ITEM WITH UNIT BID PRICE WRITTEN IN WORDS**	**UNIT PRICE**	**AMOUNT**
904.	5	4000 PSI, 3/4 INCH, 610 CEMENT CONCRETE AT _____ PER CUBIC YARD		
904.3	2,150	5000 PSI, 3/4 INCH, 685 HP CEMENT CONCRETE AT _____ PER CUBIC YARD		
910.1	651,600	STEEL REINFORCEMENT FOR STRUCTURES - EPOXY COATED AT _____ PER POUND		
945.10	610	DRILLED MICROPILES AT _____ PER FOOT		
950.5	2,100	TEMPORARY SUPPORT OF EXCAVATION AT _____ PER SQUARE YARD		
950.51	1	TEMPORARY SUPPORT OF EXCAVATION - BRIDGE AT _____ LUMP SUM		
964.11	1,600	ANTI-GRAFFITI COATING AT _____ PER SQUARE YARD		
983.1	4,075	RIPRAP AT _____ PER TON		
986.	450	MODIFIED ROCKFILL AT _____ PER TON		

m Addendum No. 4, November 4, 2026

Project # 609204	Contract # 136695			
Location : BELMONT				
Description : Community Path, Belmont Component of the MCRT (Phase I)				
ITEM #	**QUANTITY**	**ITEM WITH UNIT BID PRICE WRITTEN IN WORDS**	**UNIT PRICE**	**AMOUNT**
995.01	1	BRIDGE STRUCTURE, BRIDGE NO. 8-07-017 AT _____ LUMP SUM		
995.07	140	REMOVAL AND REPLACEMENT OF RAILROAD AT _____ PER FOOT		
996.01	1	WALL STRUCTURE, WALL NO. 1 AT _____ LUMP SUM		
996.03	3,790	SMALL BLOCK LANDSCAPE RETAINING WALL AT _____ PER SQUARE FOOT		
m **Total Qty:**	921,488			