DOCUMENT 00911
ADDENDUM NO. 2

DATE: November 5, 2026

CONTRACT: Damons Point Pier Improvements, Contract 2027-HM-1

OWNER: Marshfield Select Board

ENGINEER: PGB Engineering, LLC, Marshfield, MA

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents first issued October 21, 2026, with amendments and additions noted below.

Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

This Addendum consists of 2 pages.

I. QUESTIONS, ANSWERS AND CLARIFICTIONS

1. *When is the anticipated notice to proceed on the project?*
   The notice to proceed will be issued as soon as the Town executes the contracts. This is typically about two weeks after the contractor submits the signed contracts, bonds and insurance.

2. *Please confirm if the stated pile lengths are overall purchase lengths before driving and cutoff, or are they required installed lengths?*
   The stated pile lengths are the purchase lengths.

3. *At the prebid, we understood that the Town wants the five removed float piles. Section 01200, Item 1 currently requires removal and disposal. Please confirm whether the piles are to be salvaged, the stockpile or delivery location, and who supplies loading, trucking, and unloading?*

   The five removed float piles shall be removed and disposed of by the contractor.

4. *Sheet 3 specifies CCA treatment at 2.5 pcf for beams and joists. Please identified the required species and grade for the timber.*

   All lumber shall be new Southern Yellow Pine, Grade #1 in accordance with the Southern Pine Inspection Bureau. Treated lumber (beams and joists) shall be treated by vacuum pressure process, full cell method, with CCA (Chromated Copper Arsenate), with a retention of 2.5 pounds per cubic foot and shall conform to AWPA Standard P-5 and Federal Specifications TT-W-550. Treatment method shall conform

to AWPA Standard Specification C-2, C-14 and C-8 and Federal Specification TT-W-571.

5. *Section 02740 prohibits permanent paving between November 15 and April 1, while the project requires approximately 24 square feet of repaving and states an April 1 completion date. Can paving be completed prior to April 1?*

   Paving will be allowed before April 1.

6. *Are we required to maintain access to the pier, gangway, and floats for the general public throughout construction, or may these areas be closed for the duration of the project?*

   The Owner will coordinate with commercial fishermen that use the facility. The pier shall be closed off to the general public.

7. *Where is the contractor's staging area for the project?*

   The contractor's staging area is the small parking area on the west side of Damons Point Road and the paved area immediately adjacent to the pier.

8. *At the prebid meeting it was mentioned that there is 45' of water depth in the channel immediately northwest of the project site. Can you confirm this depth? The plans from the revetment restoration project in the dropbox folder show the channel bottom at elevation -18.95?*

   Use the record information from the plans in the Dropbox folder (i.e. -18.95).